

MOBILIZATION	
LOCATION	L. SUM
HENDERSON COUNTY	0.5
WARREN COUNTY	0.5
TOTAL	1

ENGINEERS FIELD OFFICE, TYPE A	
LOCATION	CAL MO.
HENDERSON COUNTY	1
WARREN COUNTY	1
TOTAL	2

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DA
HENDERSON COUNTY	5
WARREN COUNTY	5
TOTAL	10

TRAFFIC CONTROL AND PROTECTION	
LOCATION	STD.701326
	L SUM
HENDERSON COUNTY	0.5
WARREN COUNTY	0.5
TOTAL	1

PAINT PAVEMENT MARKING - LINE 4"			
LOCATION		EDGE LINE - WHITE	
		SB/EB	NB/WB
FT			
HENDERSON COUNTY			
STA. 223+63.16	TO STA. 369+15.58 BK	14,552	14,552
STA. 369+07.76 AH	TO STA. 469+79.52	10,072	10,072
HENDERSON COUNTY SUB-TOTAL		49,248	
WARREN COUNTY			
STA. 469+79.52	TO STA. 731+36.59	26,157	26,157
WARREN COUNTY SUB-TOTAL		52,314	
TOTAL		101,562	

SCHEDULE OF MAILBOXES AND MAILBOX TURNOUTS			
LOCATION	NOTES	AGG SURFACE CSE, TY B	RELOCATE EXIST. MAILBOX
		TON	EACH
HENDERSON COUNTY			
LT. STA. 454+00.00		3.19	1
LT. STA. 455+28.67		3.71	1
RT. STA. 458+92.39		4.52	1
HENDERSON COUNTY TOTAL:		11	3
WARREN COUNTY			
LT. STA. 494+00.00		10.11	1
LT. STA. 538+89.75		4.32	1
LT. STA. 545+32.18		7.22	1
WARREN COUNTY TOTAL:		22	3
TOTAL:		33	6

FILE NAME = 68C07 - IL 116 Henderson and Warren.dgn	USER NAME = aubreygs	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 5/21/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET 5 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
665	137W-1+ (138, 139)W-2	HENDERSON/ WARREN	15	10
CONTRACT NO. 68C07				
ILLINOIS FED. AID PROJECT				