



TYPICAL #4

LT. STA. 37+89.45 TO 41+15.25  
 RT. STA. 37.89.45 TO 41+45.23

LEGEND - TYPICAL #4

- ① EXIST BITUMINOUS SURFACE COURSE, 1 1/2"
- ② EXIST LEVELING BINDER, 1 1/2"
- ③ EXIST BITUMINOUS SURFACE COURSE 1 1/4"
- ④ EXIST BITUMINOUS BINDER COURSE 2 1/2"
- ⑤ EXIST BRICK COURSE, 3"
- ⑥ EXIST SAND CUSHION, 1"
- ⑦ EXIST PCC PAVEMENT, 6"
- ⑧ EXIST PCC BASE COURSE WIDENING, 8"
- ⑨ EXIST PCC BASE COURSE WIDENING, 9"
- ⑩ EXIST CONCRETE CURB, TY B
- ⑪ EXIST BITUMINOUS BINDER COURSE, 3/4"
- ⑫ EXIST PCC SIDEWALK, 4"
- ⑬ EXIST THERMOPLASTIC PAVEMENT MARKING

FILE NAME * S:\CONTRACTS\72H22 - IL 18 - Lincol	USER NAME * shahdm Patching\plan sheets.dgn	DESIGNED - DMS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TYPICAL SECTION FAP 320</b>			F.A.P. RTE. 320	SECTION *	COUNTY LOGAN	TOTAL SHEETS 15	SHEET NO. 6
	PLOT SCALE * 48.0000' / in.	DRAWN - DMS	REVISED -		SCALE:	SHEET 3	OF 4 SHEETS	STA.	TO STA.	CONTRACT NO. 72H22		
Default	PLOT DATE * May-19-2014 11:42:56AM	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE -	REVISED -		* DE SPRING RD REPAIR 2014-24							