

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	COUNTY	ALEXANDER
				FUNDING	100% STATE
					ROADWAY
					0005
					RURAL
40600647	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	2774		2774
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	584		584
40600990	TEMPORARY RAMP	SQ YD	74		74
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	5632		5632
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	255		255
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	3.4		3.4
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	674.6		674.6
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	20.2		20.2
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	47216		47216
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	66007		66007
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1334		1334
48203100	HOT-MIX ASPHALT SHOULDERS	TON	74		74
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3		3
67100100	MOBILIZATION	L SUM	1		1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1