		CODE NO.	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	TRAFFIC SIGNALS 0021		
									63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER- CONNECT
		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	270	270					
	*	81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	237			237			
"	*	X0370121	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL (CDOT)	FOOT	518			518			
"	*	X0370122	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL (CDOT)	FOOT	634			634			
"	*	X0370123	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL (CDOT)	FOOT	140			140			
"	*	X0370124	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL (CDOT)	FOOT	3,010						3,010
"	*	X0370125	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL (CDOT)	FOOT	952			952			
	*	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	221			221			
	*	81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6"x6"x4"	EACH	12			12			
	*	81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x10"x6"	EACH	6			6			
	*	81300948	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24"x24"x10"	EACH	2			2			
"	*	X0370126	UNIT DUCT, 600 V, 3-1/C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE (CDOT)	FOOT	102			102			
"	*	X0370127	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10 (CDOT)	FOOT	2,786			2,786			
"	*	X0370128	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4 (CDOT)	FOOT	932			932			
"	*	X0370129	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2 (CDOT)	FOOT	2,500			2,500			
	*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5,982			5,982			
"	*	X0370130	REMOVE EXISTING STREET LIGHTING EQUIPMENT (CDOT)	L SUM	1			1			
"	*	X0370120	RACK, SECONDARY-AERIAL, 2-WIRE (CDOT)	EACH	1			1			
"	*	X0370131	REMOVE CONDUIT ATTACHED TO STRUCTURE (CDOT)	FOOT	2,083			2,083			
"	*	X0370132	MAINTENANCE OF STREET LIGHTING SYSTEM (CDOT)	L SUM	1			1			
"	*	X0370003	CABLE IN CONDUIT, TRIPLEX, 2-1/C NO.6 1/C NO.8 (CDOT)	FOOT	2,692			2,692			
"	*	X0370133	PAINT EXISTING STREET LIGHT/TRAFFIC EQUIPMENT COMPLETE (CDOT)	EACH	1			1			
"	*	X0370134	JUNCTION BOX, POLE OR POST MOUNTED (CDOT)	EACH	2				1	1	
		X2011000	TEMPORARY FENCE (SPECIAL)	FOOT	453		453				

* DENOTES SPECIALTY ITEM

" DENOTES CHICAGO DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION

24