

CODE NO.	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST / YALE AVE	63RD ST / WENTWORTH AVE	INTER- CONNECT
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	92		92				
X6020083	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	1	1					
X6022505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	4	4					
X0370135	CONCRETE CURB, TYPE B(SPECIAL) (CDOT)	FOOT	101	101					
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	235	235					
X0370136	REMOVE EXISTING JUNCTION BOX (CDOT)	EACH	30			30			
X0370137	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING (CDOT)	L SUM	1			1			
X0370138	ELECTRIC CABLE IN CONDUIT, COAXIAL VIDEO, RG-59/U (CDOT)	FOOT	197				48	149	
Z0004552	APPROACH SLAB REMOVAL	SO YD	738	738					
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	685		685				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0018004	DRAINAGE SCUPPERS, DS-12	EACH	4		4				
Z0018800	DRAINAGE SYSTEM	L SUM	1		1				
Z0026407	TEMPORARY SHEET PILING	SO FT	662		662				
X0370139	MAINTENANCE OF LIGHTING SYSTEM (CDOT)	CAL MD	6			6			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
Z0062456	TEMPORARY PAVEMENT	SO YD	117	117					
Z0073100	TEMPORARY SHORING	EACH	4		4				
X0370080	COMBINATION CURB AND GUTTER TYPE B V.12 (CDOT)	FOOT	570	570					
3101860	SUBBASE GRANULAR MATERIAL, TYPE B 24"	SO YD	43	43					
X032747	MODIFY CONCRETE BARRIER AND RETAINING WALL	L SUM	1	1					
X0370081	SAND CUSHION, 4" (CDOT)	SO FT	2,538	2,538					

• DENOTES SPECIALTY ITEM
 • DENOTES CHICAGO DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION

5/22/2013 12:27:28 PM
 GR@EF 2501 S. Michigan Road, Suite 200
 Chicago, Illinois 60631
 (773) 399-0012

USER NAME - J405 DESIGNED - JSJ DRAWN - HJM CHECKED - TNS PLOT DATE - 5/22/2013	REVISIONS REVISION - REVISION - REVISION - REVISION -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	63rd STREET BRIDGE REPLACEMENT - COOK COUNTY SUMMARY OF QUANTITIES	F.A.I. RYE. 94 SECTION 1920-B COUNTY COOK CONTRACT NO. 60J15	TOTAL SHEETS 137 SHEET NO. 7C
SCALE: 1"=60' SHEET 6 OF 8 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT		