

BEAM 11

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for DL Deflection
BK. W. ABUT.	20+24.77	38.54	601.14	601.14
CL. Brg. W. Abut.	20+26.02	38.54	601.17	601.17
A	20+36.02	38.54	601.40	601.44
B	20+46.02	38.54	601.62	601.70
C	20+56.02	38.54	601.85	601.93
D	20+66.02	38.54	602.06	602.12
E	20+76.02	38.54	602.24	602.27
CL. Brg. Pier 1	20+84.78	38.54	602.39	602.39
F	20+94.78	38.54	602.53	602.53
G	21+04.78	38.54	602.64	602.65
H	21+14.78	38.54	602.73	602.75
I	21+24.78	38.54	602.80	602.82
J	21+34.78	38.54	602.85	602.85
CL. Brg. Pier 2	21+44.84	38.54	602.87	602.87
K	21+54.84	38.54	602.86	602.88
L	21+64.84	38.54	602.83	602.88
M	21+74.84	38.54	602.79	602.85
N	21+84.84	38.54	602.73	602.78
P	21+94.84	38.54	602.66	602.69
CL. Brg. Pier 3	22+08.44	38.54	602.53	602.53
Q	22+18.44	38.54	602.43	602.43
R	22+28.44	38.54	602.31	602.32
S	22+38.44	38.54	602.17	602.19
T	22+48.44	38.54	602.03	602.04
U	22+58.44	38.54	601.86	601.87
CL. Brg. Pier 4	22+68.46	38.54	601.69	601.69
V	22+78.46	38.54	601.50	601.52
W	22+88.46	38.54	601.30	601.35
X	22+98.46	38.54	601.12	601.19
Y	23+08.46	38.54	600.96	601.03
Z	23+18.46	38.54	600.83	600.87
CL. Brg. E. Abut.	23+26.00	38.54	600.75	600.75
BK. E. ABUT.	23+27.24	38.54	600.74	600.74

H:\projects\2013\0223\CAD\AS+Structure\06-1149-Final\00\06\015-s12-Top5.dgn 5/20/2013 11:24:02 AM



USER NAME =	DESIGNED - J.Z.	REVISED -
CHECKED - J.A.Z.	REVISED -	
PLOT SCALE =	DRAWN - E.E.J.	REVISED -
PLOT DATE =	DATE - 5/17/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TOP OF DECK SLAB ELEVATIONS V
STRUCTURE NO. 016-1149**

SHEET NO. S12 OF 50 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	1920-B	COOK	137	71
CONTRACT NO. 60J15				
ILLINOIS FED. AID PROJECT				