

FROM	TO	20200100	
		EARTH EXCAVATION	EMBANKMENT
STATION	STATION	CU YD	CU YD
Infield		9218	0
IL 31			
116+00	116+50	57	3
116+50	117+00	41	4
117+00	117+50	31	1
117+50	118+00	26	180
118+00	118+50	30	291
118+50	119+00	41	267
119+00	119+50	50	312
119+50	120+00	54	296
120+00	120+50	54	281
120+50	121+00	55	264
121+00	121+50	77	216
121+50	122+00	96	187
122+00	122+50	57	252
122+50	123+00	10	157
123+00	123+50	0	0
123+50	124+00	0	0
124+00		0	0
WATKINS			
01+00	01+35	110	107
01+35	01+50	21	61
01+50	02+00	337	106
02+00	02+30	483	17
02+30	02+50	340	27
02+50	02+68	184	24
02+68	03+00	175	4
03+00	03+50	134	9
03+50	04+00	91	6
04+00	04+30	36	2
04+30	04+50	16	3
04+50	05+00	14	7
TOTALS		11,837	3,082

F:\projects\2010\20100303\cad\site\01\0160V53-sht-Schedule-Earthwork.dgn
 5/16/2013 2:45:33 PM

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED - RS	REVISED -
PLOT DATE = 5/16/2013	DATE - 05/17/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WATKINS STREET AT IL ROUTE 31
EARTHWORK SCHEDULE

SHEET NO. 1 OF 1

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3902	12R-N	KANE	92	16
CONTRACT NO. 60V53				
ILLINOIS FED. AID PROJECT				