

LOCATION	30300112	35501308	35501316	35501324	35600716	40600200	40600300	40600400	40600635	40603335	40603340	40701936
	AGGREGATE SUBGRADE IMPROVEMENT, 12"	HOT-MIX ASPHALT BASE COURSE, 6"	HOT-MIX ASPHALT BASE COURSE, 8"	HOT-MIX ASPHALT BASE COURSE, 10"	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	MIXTURE FOR JOINTS, CRACKS, AND FLANGEWAYS	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 12 3/4"
	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(TON)	(TON)	(SQ YD)
WATKINS	2604	96	0	105	78	2	11	1	125	11	90	2064
IL 31	1224	0	611	0	0	1	4	0	0	68	0	959
US 30	0	0	0	0	0	0	0	0	0	0	0	0
RAMP C	63	0	0	0	0	0	0	0	0	0	0	0
RAMP D	57	0	0	0	0	0	0	0	0	0	0	0
TOTALS	3948	96	611	105	78	3	15	1	125	79	90	3023

LOCATION	42300400	42400300	44300200	48101600	48102100	48203047	48203048	50300300	60600605	60603800	60605000			
	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	PORTLAND CEMENT CONCRETE SIDEWALK, 6"	STRIP REFLECTIVE CRACK CONTROL TREATMENT	AGGREGATE SHOULDERS, TYPE B, 8"	AGGREGATE WEDGE SHOULDER, TYPE B	HOT-MIX ASPHALT SHOULDERS, 12 1/2"	HOT-MIX ASPHALT SHOULDERS, 12 3/4"	PROTECTIVE COAT	CONCRETE CURB, TYPE B	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24			
	(SQ YD)	(SQ FT)	(FT)	(SQ YD)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(FT)	(FT)			
WATKINS	37	618	954	11	0	0	131	272	66	31	524	272	72	0
IL 31	0	0	0	268	0	0	230	0	0	0	0	0	0	0
US 30	0	0	0	0	20	0	0	0	0	0	0	0	0	0
RAMP C	0	0	0	33	0	56	0	0	0	0	0	0	0	0
RAMP D	0	0	0	26	0	50	0	0	0	0	0	0	0	0
TOTALS	37	618	954	337	20	106	361	272	97	796	72			

LOCATION	63000001	63100045
	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 2
	(FT)	(EACH)
WATKINS	0	0
IL 31	0	0
US 30	0	0
RAMP C	50	1
RAMP D	0	0
TOTALS	50	1

LOCATION	LENGTH	AREA	21101695	30300112	50300300	60618300	60605000
			TOPSOIL, FURNISH & PLACE, 30"	AGGREGATE SUBGRADE IMPROVEMENT, 12"	PROTECTIVE COAT	CONCRETE MEDIAN SURFACE, 4"	COMB CONC CURB & GUTTER, TYPE B-6.24
FROM	TO	FOOT	SQ FT	SQ YD	SQ YD	SQ FT	FOOT
WATKINS STREET							
0+40	0+81	41	495	0	24	84.1	82
1+26	1+79	53	555	0	31	99	106
IL 31							
117+51	118+99	148	2,318	258	85	102.8	296
US 30							
1262+40	1263+40	100	840	93	58	69.7	200
TOTALS			351	198	356	1,050	684

P:\1052010\20103003\cadd\site\vgd\01\06053-sht+Schedule-Roadway.dgn
 5/16/2013 2:45:53 PM

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / 1"	CHECKED - RS	REVISED -
PLOT DATE = 5/16/2013	DATE - 05/17/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WATKINS STREET AT IL ROUTE 31
ROADWAY AND MEDIAN SCHEDULE

SHEET NO. 1 OF 1

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3902	12R-N	KANE	92	17
CONTRACT NO. 60V53				
ILLINOIS FED. AID PROJECT				