

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2013-001-I	COOK	13	4

CONTRACT: 60W18

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 5' PARALLEL	SIDEWALK 8" R&R (SQFT) 5' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	CONC. CURB, TYPE B (LF)	REMARKS
58th Street and Nagle Avenue	0.0	0.0	0.0	0.0	240.0	0.0	0.0	80.0	0.0	Replace all 4 corners of intersection with ADA Ramps
62nd Street and Kenneth Avenue	0.0	0.0	0.0	0.0	240.0	0.0	0.0	80.0	0.0	Replace all 4 corners of intersection with ADA Ramps
5614 South Austin Avenue	0.0	0.0	0.0	6.0	90.0	0.0	0.0	0.0	0.0	Replace 3 Sidewalk Squares & Service Walk
5712 South Austin Avenue	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 6 sidewalk squares
5828 South Austin Avenue	10.0	1.7	1.7	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares and 10 ft of cracked curb
6116 South Austin Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares (tripping hazard)
6651 South Karlov Avenue	0.0	0.0	0.0	0.0	120.0	0.0	0.0	0.0	0.0	Replace 4 sidewalk squares
6644 South Karlov Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
6424 South Kedvale	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 damaged sidewalk squares
6212 South Kilbourn Avenue	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 6 sidewalk squares
6001 South Kildare Avenue	0.0	0.0	0.0	9.0	0.0	0.0	0.0	0.0	0.0	Replace sinking courtesy walk on 60th Street side
6353 South Kildare	0.0	0.0	0.0	0.0	120.0	0.0	0.0	0.0	0.0	Replace 4 damaged sidewalk squares
6112 South Kilpatrick Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
6509 South Kilpatrick Avenue	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 6 sidewalk squares
6002 South Kilpatrick Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
6604 South Kilpatrick Avenue	0.0	0.0	0.0	0.0	30.0	0.0	0.0	0.0	0.0	Replace 1 sidewalk square - tripping hazard
6122 South Knox Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
5535 South Kolin Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares (tripping hazard).
6004 South Kolin Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
6321 South Kolin Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0	Replace 3 sidewalk squares
6338 South Kolin	0.0	0.0	0.0	4.5	0.0	0.0	0.0	0.0	0.0	Replace 1 damaged courtesy walk square closest to street
6805 South Kolin Avenue	0.0	0.0	0.0	0.0	30.0	0.0	0.0	0.0	0.0	Replace cracked sidewalk square
6812 South Kolin Avenue	0.0	0.0	0.0	0.0	120.0	0.0	0.0	0.0	0.0	Replace 4 sidewalk squares
5535 South Kolin Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 1 or 2 sidewalk squares - tripping hazard
5743 South Kolmar	0.0	0.0	0.0	0.0	240.0	0.0	0.0	0.0	0.0	Replace 8 sidewalk squares
6211 South Komensky Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
6612 South Komensky Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
6534 South Kostner Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares (standing water)
6350 South Lamont Avenue	0.0	0.0	0.0	27.0	0.0	0.0	0.0	0.0	0.0	Replace Courtesy Walk
6339 South Long Avenue	18.0	3.0	0.0	27.0	0.0	0.0	0.0	0.0	0.0	Replace 18 feet of damaged curb and gutter
3841 West Marquette Road	50.0	8.4	0.0	75.0	0.0	0.0	0.0	0.0	0.0	Replace curb and gutter to help alleviate standing water issue, as well as the two sinking walkways (3'6" x 5' and 3' x 5')
3700 West Marquette Road	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
6208 South Mason Avenue	0.0	0.0	0.0	36.0	0.0	0.0	0.0	0.0	0.0	Replace 24 ft of carriage walk
6105 South Massasoit Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
5653 South McVicker Avenue	0.0	0.0	0.0	45.0	0.0	0.0	0.0	0.0	0.0	Replace 20 ft of carriage walk
6004 South Mobile Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares
5617 South Nagle Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares
SUB-TOTAL	78.0	13.1	1.7	229.5	3570.0	0.0	0.0	160.0	0.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

07-09-13 RP