

INDEX OF SHEETS

- 1. COVER SHEET
- 2. COMMITMENT SHEET
- 3-6. GENERAL NOTES
- 7-14. SUMMARY OF QUANTITIES
- 15-19. TYPICAL SECTIONS
- 20-25. SCHEDULE OF QUANTITIES
- 26. LINE DIAGRAM
- 27. EXISTING AND REMOVAL ITEMS
- 28. PROPOSED ITEMS
- 29-32. EXISTING CULVERT REPAIR
- 33. PROPOSED MEDIAN
- 34. PAVEMENT MARKING IN BRIMFIELD
- 34A. CURB AND GUTTER REMOVAL AND REPLACEMENT
- 35-37. MAHER ROAD IMPROVEMENT
- 38. EROSION CONTROL ITEMS
- 39. RIGHT-OF-WAY PLANS
- 40. FLASHING SIGNAL PLANS
- 41. RECOVERY TIES
- 42-43. HMA SURFACE REMOVAL DETAIL
- 44-45. ROAD CLOSURE & DETOUR DETAILS
- 46-51. PROPOSED 8'X6' BOX CULVERT
- 52. SOIL BORINGS SHEET
- 53. BACKFILL FOR 8'X6' BOX CULVERT
- 54. RIPRAP DETAILS
- 55-65. DISTRICT 4 CADD STANDARDS
- 66-76. CROSS-SECTIONS

COMMITMENTS

COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN APPROVAL OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE.

- 1- PARCEL 4AKB001 AND I.E.
COMMITMENT TO HAROLD D. TURLEY & ASSOCIATES, INC. FOR THE RESIDENT ENGINEER TO CONTACT THE PROPERTY MANAGER (309-742-2273 OR 309-264-4294) PRIOR TO WORK ON THE EXISTING FIELD TILE THAT CONNECTS TO THE EXISTING BOX CULVERT AT THE NORTH INLET STATION 214+10.80
- 2- PARCEL 4AKB002 & I.E.
COMMITMENT TO MR. RICHARD LITTLE 14830 EAST ROUTE 150 BRIMFIELD, ILLINOIS 61517 (309-696-5263) TO NOT DISTURB THE TREE OR ROOT SYSTEM LOCATED AT STA. 213+52 @ 35' RT DURING CULVERT CONSTRUCTION.
- 3- ROAD CLOSURE RESTRICTION
NO WORK SHALL BE PERFORMED ON US 150 FROM JEFFERSON ST TO MAHER RD BETWEEN 3:30 PM AUGUST 2, 2013 TO 6:00 AM AUGUST 12, 2013 AND BETWEEN 3:30 PM AUGUST 1, 2014 TO 6:00 AM AUGUST 11, 2014 DUE TO US 150 BEING CLOSED FOR OLD SETTLERS DAYS
CONTACT HOLLY JOHNSON (BRIMFIELD VILLAGE CLERK) @ (309)-446-3412 TO CONFIRM THE DATES ABOVE

CONTACTS FOR ROAD CLOSURE

	Brimfield	Kickapoo/Edwards
Municipality	(309)-446-3412 (309)-446-9678	(309)-446-1518
Police (local)	(309)-672-6011	(309)-672-6011
State Police	(309)-383-2133	(309)-383-2133
Fire Dept	800-517-5678	800-517-5678
School	(309)-446-3378	(309)-446-3378
US Post Office	(309)-446-3025	(309)-676-5866
Peoria County Highway Dept Engineer		(309)-697-6400 (309)-253-0531

JOB SPECIFIC NOTE

EXISTING BOX CULVERT DESCRIPTION :

The existing box culvert is 8'X8'X46' with the following additional elements: an upstream drop box 12' long X9' wide X8' high with wall thickness of 8" and a retaining wall that measures 18'X11'X1'. On the downstream side there exist a concrete pad 9'X9'X8" and two (2) wingwalls 13'X11'X10" and 13'X 8'to11' X10" and various concrete footing and sheet pile (at least 267sq ft). All quantities are estimated as there were no asbuilt plans found. the fill height over the top of existing culvert is approximately 9 feet.

There is a sanitary line running from the old restaurant situated in the S.E. corner of the intersection of US 150 and Maher Rd. The sanitary line runs from the restaurant, across Maher Rd, and in front the trailer park situated in the S.W. corner of the intersection of US 150 and Maher Rd.

Signing for the proposed 4-way stop shall be installed by district 4 Traffic Operation personnel. The Contractor shall contact Jen Rudzinski (309-671-4466) or Bill Harmann (309-693-5176) to coordinate the installation of signs.

FILE NAME * 68614-plans.dgn	USER NAME * reming	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMMITMENTS SHEET	F.A. RTE. FAS 2402 U.S. 150	SECTION (110,111,112,113)RS-3j 114RS-4(112C-2	COUNTY PEORIA	TOTAL SHEETS 76	SHEET NO. 2
	PLOT SCALE * 7.6804" = 1"	DRAWN -	REVISED -			SCALE: _____	SHEET NO. _____ OF _____ SHEETS	FED AID PROJECT		CONTRACT NO. 68614
	PLOT DATE * 6/12/2013	CHECKED -	REVISED -							