



STA 27+00 TO STA 35+00 (in Brimfield)

★ QUANTITIES ADDED FOR CL TREATMENT (SEE RESURFACING SCHEDULE)

**LEGEND**

- ① EXIST. PCC PAVEMENT
- ② EXIST. BASE CSE WIDENING
- ③ EXIST. HMA OVERLAY
- ④ EXIST SIDEWALK
- ⑤ EXIST CONC CURB
- ⑩ PROP. HOT-MIX ASPHALT SURF REMOVAL 1 1/2"
- ⑪ PROP. HOT-MIX ASPHALT SURF REMOVAL 2 1/4"
- ⑫ PROP. POLY LEV BIND (M M) IL 4.75 N50 (3/4")
- ⑬ PROP. POL. HOT-MIX ASPHALT SURF CSE "D" N50 (1 1/2")
- ⑭ COMB. CONC CURB AND GUTTER B-6.12 REMOVAL AND REPLACEMENT

For location & quantities of CCC & G B-6.12 SEE SHEET 34A

FILE NAME #	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TYPICAL SECTIONS</b>			F.A. RTE. FAS 2402	SECTION (110,111,112,113)RS-3;	COUNTY	TOTAL SHEETS	SHEET NO.			
	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	U.S. 150	114RS-4;112C-2	PEORIA	76	18
	CHECKED -	REVISED -					FED AID PROJECT			CONTRACT NO. 68614				
	DATE -	REVISED -												