

# SCHEDULE OF QUANTITIES

STATION TO STATION			BIT SURF REMOVAL	TEMP RAMPS
			BUTT-JOINT	
			SQ YD	SQ YD
896+30	TO	896+60	80	13
@ RURAL SIDE SIDEROADS			2,460	267
AT THE BRIDGE			173	29
415+00	TO	415+30	87	14
<b>TOTAL</b>			<b>2,800</b>	<b>323</b>

AGG WEDGE SHOULDER, TYPE B			TON	
			LT	RT
896+30	TO	904+50	BIT SHOULDERS	
904+50	TO	996+78	350	350
STA EQUA 996+78BK=-1+00 AH				
-1+00	TO	307+90	1,173	1,173
307+90	TO	310+54	BIT SHOULDERS	
310+54	TO	312+40	BRIDGE OMISSION	
312+40	TO	315+24	BIT SHOULDERS	
315+24	TO	415+30	380	380
DEDUCTION FOR GUTTERS			-204	-216
DEDUCTION FOR IN TOWN			-42	-42
<b>SUB-TOTAL</b>			<b>1,657</b>	<b>1,645</b>
<b>TOTAL</b>			<b>3,302</b>	

LOCATION	TREE REMOVAL
	ACRES
ALONG US 150 (STA 214+10) AT THE CULVERT	0.36
<b>TOTAL</b>	<b>0.36</b>

STATION TO STATION			GUTTER REMOVAL	COMB. CONC CURB & GUTTER REMOVAL	CONC GUTTER TYPE A	COMB. CONC CURB & GUTTER T B-6.12
			FOOT	FOOT	FOOT	FOOT
27+55	TO	35+96	-----	840	-----	840
288+00	TO	291+00	300	-----	300	-----
<b>TOTAL</b>			<b>300</b>	<b>840</b>	<b>300</b>	<b>840</b>

STATION TO STATION LEFT			INLET AND PIPE PROTECTION	PIPE CULVERT REMOVAL	STORM SEWERS CL A T 2 24"	MANH T A 5' DIA W/SPL FRAME & GRATE	
							OFFSET
213+60	TO	214+25	35' RT	2	45	65	1
<b>TOTAL</b>			<b>----</b>	<b>2</b>	<b>45</b>	<b>65</b>	<b>1</b>

STATION TO STATION		TOPSOIL FURNISH & PLACE 4"	SEEDING CLASS 3A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	TEMPORARY EROSION CONT SEEDING
		SQ YD	ACRE	POUND	POUND	POUND	ACRE	POUNDS
US 150		918	0.24	22	22	22	0.24	72
ALONG THE STREAM		651	0.41	36	36	36	-----	122
<b>TOTAL</b>		<b>1,569</b>	<b>0.65</b>	<b>58</b>	<b>58</b>	<b>58</b>	<b>0.24</b>	<b>194</b>

LOCATION		REM & DISP OF UNSUIT MATERIAL	EARTH EXCAVATION	FOR INFORMATION ONLY			EROSION CONTROL BLANKET
				EARTH EXCAV ADJUST FOR 25% SHRINKAGE	EMBANKMENT	FURNISHED EXCAVATION	
		CU YD	CU YD	CU YD	CU YD	CU YD	SQ YD
212+50	TO 213+82	-----	23.9	17.9	(811.4)	811.4	----
*213+82	TO 214+37						
212+37	TO 216+00	-----	27.0	20.3	(90.9)	90.9	----
AT THE CULVERT		108					
ALONG STREAM		-----	1,399.4	1,049.5	835.6	(835.6)	651.0
<b>TOTAL</b>		<b>108</b>	<b>1,450</b>	<b>1,088</b>	<b>(67)</b>	<b>67</b>	<b>651</b>

\* QUANTITIES OVER BOX CULVERT ARE NOT INCLUDED IN THE EARTH EXCAVATION PAID FOR AS PART OF REMOVE EXISTING STRUCTURES