SCHEDULE OF QUANTITIES

	MODIFIED URETHANE	MODIFIED URETHANE	MODIFIED URETHANE		MODIFIED URETHANE	MODIFIED URETHANE
STATION TO STATION	& TEMP PVT	& TEMP PVT	& TI	EMP PVT	& TEMP PVT	& TEMP PVT MKG
	MARKING LINE - 6"	MARKING LINE - 8"	MARKI	NG LINE - 12"	MARKING LINE - 24"	LETTERS & SYMBOLS
	(WHITE)	(WHITE)	WHITE	YELLOW	(WHITE)	(WHITE)
	FT	FT	FT		SQ FT	SQ FT
AT MAHER RD AND US 150		569	118.0	196.0	128.0	47.0
RT TURN AT JUB COLLEGE STATE PARK		400				46.8
RT TURN AT TIMBER RIDGE		200				31.2
IN TOWN (BRIMFIELD)		400	100.0			124.8
CROSS WALK STA 35+88 (BRIMFIELD)	124					
TOTAL	124	1,569		414	128	250

				* SHORT-TERM	WORK ZONE
			LENGTH	PAVEMENT	PVT. MRK.
STATION	то я	STATION		MARKING	REMOVAL
				FT	SQ FT
896+30	ТО	996+78	10,048	3,014	1,005
STA EQUA 996+78 BK = -1+00 AH					
-1+00	то	310+50	31,150	9,345	3,115
310+50	ТО	312+36	186	56	19
312+36	то	415+30	10,294	3,088	1,029
TOTAL				15,503	5,168

* 3 APPLICATIONS

			PERIMETER
STA TO STA			EROSION
			CONTROL
			FOOT
US 150 LT			
212+50	то	213+95	145
US 150 RT			
213+55	ТО	216+00	320
STREAM RT			
1+75			60
TOTAL			525

	TEMP
	DITCH
LOCATION	CHECK
	FOOT
MAINLINE LEFT	
212+75	9
213+05	9
213+25	9
MAINLINE RIGHT	
214+25	9
214+50	9
214+75	9
215+00	9
215+50	9
STREAM	
1+30	14
1+75	14
TOTAL	100

TRAF CONT & PROT STD BLR 21 SPL	CAL DAY
JOBSITE	21
TOTAL	21

CONSTRUCTING TEST STRIP	EACH
SURFACE COURSE	1
TOTAL	1

ENGINEER FIELD OFFICE TYPE A	CAL MO
JOBSITE	6
TOTAL	6

MOBILIZATION	L SUM
JOBSITE	1
TOTAL	1

TRAF CONT & PROT STD 701201	L. SUM
JOBSITE	1
TOTAL	1

TRAF CONT & PROT STD 701306	L. SUM
JOBSITE	1

TRAF CONT & PROT STD 701326	L. SUM
JOBSITE	1
TOTAL	1

CONSTRUCTION LAYOUT	L. SUM
JOBSITE	1
TOTAL	1

PERMANENT SURVEY MARKERS T1	EACH
S.E. CORNER OF CULVERT	1
TOTAL	1

TOTAL	1
JOBSITE	1
TRAF CONT & PROT STD BLR 21 SPL	L. SUM

TRAFFIC CONTROL SURVEILLANCE	EACH
US 150	4
MAHER ROAD	2
TOTAL	6

FILE NAME =	USER NAME =	DESIGNED -	REVISED -					F.A. RTE.	SECTION	COLINTY	TOTAL SHEET
		DRAWN -	REVISED -	STATE OF ILLINOIS		SCHEDULE OF QUANTITIES		FAS 2402	(110,111,112,113)RS-3;	0001111	SHEETS NO.
	PLOT SCALE =	CHECKED - REVISED -	REVISED -	DEPARTMENT OF TRANSPORTATION				U.S. 150	114RS-4;112C-2	PEORIA	76 22
	PLOT DATE = 3/20/2013	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA.	TO STA.	FE	ED AID PROJECT	CONTRACT	NO. 68614