SCHEDULE OF QUANTITIES

GUARDRAI	TON					
LT	941+94	ТО	944+57	50.5		
RT	943+00	TO	943+50	9.6		
RT	943+80	TO	944+30	9.6		
LT	952+39	ТО	955+01	50.5		
RT	953+22	ТО	953+72	9.6		
LT	962+68	TO	965+30	50.4		
RT	963+29	TO	963+79	9.6		
RT	964+09	TO	964+59	9.6		
LT	989+32	TO	989+82	9.6		
LT	990+10	TO	990+60	9.6		
RT	989+28	TO	989+78	9.6		
RT	990+06	TO	990+56	9.6		
LT	50+25	TO	50+75	9.6		
RT	50+25	TO	50+75	9.6		
LT	73+45	ТО	73+95	9.6		
LT	74+25	TO 74+75		9.6		
RT 73+45		TO	73+95	9.6		
RT 74+25		TO 74+75		9.6		
LT	178+03	ТО	180+65	50.4		
RT	178+03	TO	180+65	50.4		
LT	212+68	ТО	215+68	57.8		
RT	212+73	TO	215+98	62.6		
	517					

					SPBGR	LONG-SPAN
				OFFSET	TYPE A	G RAIL
	STA	TO	STA		6 FOOT	OVER CULV
					POSTS	12'- 6" SPAN
				FOOT	FOOT	FOOT
LT	942+44	TO	944+06.5	6.0		162.5
LT	952+88.5	TO	954+51	6.0		162.5
LT	963+18	ТО	964+80.5	6.0		162.5
RT	19+58	ТО	20+58	EXISTING	100.0	
LT	178+53	ТО	180+15.5	6.0		162.5
RT	178+53	TO	180+15.5	6.0		162.5
LT	213+17.5	TO	215+17.5	6.0	200.0	
RT	213+22.5	TO	215+47.5	6.0	225.0	
	TOTAL				525	812.5

			RAISED REF	RAISED REF
			PAVEMENT	PVT MRKRS
STATION	TO	STATION	MAKERS	REMOVAL
			EACH	EACH
26+00	TO	38+00	66	66
TOTAL			66	66

		EARTH	НМА	SHLDRS		
			EXCAV	SHLDRS	RUMBLE	
LOCATION (INSIDE SHO	ULDERS)	WIDENING	8"	STRIP 8"	
	(3' WIDE)					
			CUYD	SQ YD	FOOT	
380+70	TO	387+00	46.7	210.0	630.0	
341+75	TO	354+50	94.4	425.0	1,275.0	
72+00	ТО	82+60	78.5	353.3	1,060.0	
TOTAL			220	988	2,965	

ı	FILE NAME =	USER NAME =	DESIGNED -	REVISED -					F.A. RTE. SECTION		COUNTY	TOTAL	SHEET
			DRAWN -	REVISED -	STATE OF ILLINOIS	SCHEDULE OF QUANTITIES			FAS 2402	(110,111,112,113)RS-3;	COUNTY	SHEETS	NO.
		PLOT SCALE =	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION				U.S. 150	114RS-4;112C-2	PEORIA	76	_24
		PLOT DATE = 3/20/2013	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA.	TO STA.	FED AID PROJECT		CONTRACT NO. 6861		4