



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 23, 2013

SUBJECT: West Belleville Trail
Project TE-00D8(181)
Section 10-00215-00-BT (Belleville)
St. Clair County
Contract No. 97515
Item 103
August 2, 2013 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

- 1. Revised the Index.**
- 2. Revised page 14 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with the initials "P.E." written in a smaller font to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

INDEX TO SPECIAL PROVISIONS

<u>SPECIAL PROVISIONS</u>	<u>SHEET</u>
DESCRIPTION OF WORK	1
SITE INSPECTION	1
SAFETY AND PROTECTION	1
TRAFFIC CONTROL PLAN	2
TRAFFIC CONTROL AND PROTECTION	3
CONSTRUCTION AND MAINTENANCE SIGN SUPPORTS	4
BARRICADES OR DRUMS	4
AGGREGATE FOR TEMPORARY ACCESS	4
JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (JULIE)	5
COOPERATION WITH UTILITIES	5
STATUS OF UTILITIES TO BE ADJUSTED	6
TEMPORARY CONSTRUCTION EASEMENTS	6
TRENCH BACKFILL	7
SEEDING	7
PIPE CULVERTS	8
BOLLARDS	8
WOOD POST AND RAIL FENCE	8
PIPE HANDRAIL	8
FOLD DOWN BOLLARDS	8
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	9
SAW CUTS	9
MEDIAN SURFACE REMOVAL	9
DRIVEWAY PAVEMENT REMOVAL	9
DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	9
HANDHOLE TO BE ADJUSTED	10
RELOCATE GATE POSTS AND GATE	10
TIMBER RETAINING WALL REMOVAL	10
REMOVE EXISTING PARKING BLOCKS	10
REMOVE AND RE-ERECT EXISTING SIGN	11
RELOCATE LIGHTING UNITS AND POLES	11
EXISTING STORM SEWER CONNECTIONS TO PROPOSED DRAINAGE STRUCTURES	11
PRIMARY FLASHER CONTROLLER	12
SECONDARY FLASHER CONTROLLER	12
INDUCTION LOOP DETECTOR AMPLIFIER (SPECIAL)	12
RADIO COMMUNICATIONS SYSTEM	13
FLASHING BEACON INSTALLATION	13
CONSTRUCTION LAYOUT	14
PAYROLL AND PROCEDURES	15
DEPARTMENT OF THE ARMY PERMIT	18
STORM WATER POLLUTION PREVENTION PLAN	27

Description: This work shall consist of furnishing and installing a flashing beacon in accordance with Section 880 of the Standard Specifications for Road and Bridge Construction on a wood sign post as shown on the plan sheets. The signal head shall be polycarbonate, LED, 1-Face, 1-Section and the conduit shall be 1 ½" galvanized steel.

Installation: The flashing beacon shall be installed per Standard 880001 and the plan sheet details.

Basis of Payment: This work will be paid for at the contract unit price per each for FLASHING BEACON INSTALLATION which price shall include the signal head, galvanized steel conduit, all hardware / material and labor. The wood sign post will be paid for separately along with the signs.

CONSTRUCTION LAYOUT

The City of Belleville will provide all reference points and benchmarks as needed by the Contractor in order to construct the proposed improvements. The Contractor shall provide their own construction staking.