

INDEX OF SHEETS

SHEET NO.	ITEM
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES
2	SCHEDULE OF QUANTITIES
3	SUMMARY OF QUANTITIES
4-6	LOCATION MAPS
7-14	STRUCTURE PLANS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS

STD. NO.	DESCRIPTION
000001-07	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
631031-15	TRAFFIC BARRIER TERMINAL, TYPE 6
701101-05	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701400-09	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701402-12	LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH BARRIER
701601-09	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W, WITH NONTRAVERSABLE MEDIAN
701801-06	LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE
701901-08	TRAFFIC CONTROL DEVICES
704001-08	TEMPORARY CONCRETE BARRIER

DESCRIPTION	STATION	TO	STATION	TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-DIRECTIVE), TEST LEVEL 3
				(FOOT)	
FAYETTE COUNTY I-70					
SN 026-0019	609+00	TO	614+50	550	1
CLARK COUNTY I-70					
SN 012-0007	213+40	TO	217+90	450	1
TOTAL				1000	2



GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS; THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED APRIL 1, 2016; AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THIS PROJECT IS LOCATED IN CLARK, FAYETTE, AND MACON COUNTIES. STRUCTURE NUMBER 012-0007 IS IN CLARK COUNTY ON FAI 70 APPROXIMATELY 1.7 MILES EAST OF THE IL ROUTE 1 INTERCHANGE. STRUCTURE NUMBER 026-0019 IS IN FAYETTE COUNTY ON FAI 70 APPROXIMATELY 0.7 MILES EAST OF THE US ROUTE 51 INTERCHANGE. STRUCTURE NUMBER 058-0111 IS IN MACON COUNTY ON FAP 320 (IL 121) APPROXIMATELY 1.5 MILES SOUTHEAST OF THE FAI 72 INTERCHANGE. THE WORK INCLUDED IN SECTION D-7 BRIDGE REPAIRS 2020-3 CONSISTS OF PARAPET REPAIRS, TRAFFIC CONTROL, AND ANY OTHER WORK NECESSARY TO COMPLETE THE SECTION.

AN ADDITIONAL QUANTITY OF PAVEMENT MARKING BLACKOUT TAPE, 7" IS INCLUDED FOR COVERING REFLECTIVE PAVEMENT MARKERS.

A QUANTITY OF GUARDRAIL REMOVAL IS INCLUDED FOR THE REMOVAL OF THE DAMAGED TYPE 6 TRAFFIC BARRIER TERMINAL.

DESCRIPTION	STATION	TO	STATION	PAVEMENT MARKING BLACKOUT TAPE, 7"
				(FOOT)
FAYETTE COUNTY I-70				
SN 026-0019	595+12	TO	613+00	492
CLARK COUNTY I-70				
SN 012-0007	197+77	TO	215+78	496
MACON COUNTY IL-121				
SN 058-0111	981+00	TO	997+60	457
TOTAL				1445

MODEL: Default  
FILE NAME: p:\uplanroom.dat\illinois.gov\pww\DOT\Documents\DOT Offices\District 7\Projects\74918\CADDData\CAD\sheet\74918-sht-schedule.index & schedule.dgn

REV. 7-19-2019

\* CLARK, FAYETTE, & MACON

USER NAME = steffemk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 5/16/2019	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES, INDEX OF SHEETS,  
& SCHEDULE OF QUANTITIES

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	D7 BRIDGE REPAIRS 2020-3	*	14	2
			CONTRACT NO. 74918	
( ILLINOIS / FED. AID PROJECT )				

100%  
STATE

100%  
STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		CLARK 0013	FAYETTE 0013	MACON 0013
50102400	CONCRETE REMOVAL	CU YD	2.3	0.5	1.5	0.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2.3	0.5	1.5	0.3
50300300	PROTECTIVE COAT	SQ YD	15.8	3.5	9.3	3.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	365	50	290	25
50800530	MECHANICAL SPLICERS	EACH	20		20	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1		
63200310	GUARDRAIL REMOVAL	FOOT	38	38		
67100100	MOBILIZATION	L SUM	1	0.33	0.33	0.34
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD	EACH	2	1	1	
	701402					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1			1
	701601					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1			1
	701801					
70107007	PAVEMENT MARKING BLACKOUT TAPE, 7"	FOOT	1444	492	495	457
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	42	14	14	14

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		CLARK 0013	FAYETTE 0013	MACON 0013
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1000	450	550	
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1	
* X6330900	VERTICAL ADJUSTMENT OF GUARDRAIL	FOOT	25	25		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	10	3		7

\* SPECIALTY ITEM

REV. 7-19-2019  
\* CLARK, FAYETTE, & MACON

MODEL: Default  
FILE NAME: P:\highwayroom.dat\illinois.gov\PWIDOT\Documents\DOT\_Offices\District\_7\Projects\174919\CADD\Drawings\CADD\Drawings\174919-pts-500.dgn

USER NAME = steffemk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 5/14/2019	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D7 BRIDGE REPAIRS 2020-3	*	14	3
			CONTRACT NO. 74918	
ILLINOIS FED. AID PROJECT				