
07A

DU086

DUPAGE AIRPORT AUTHORITY WEST CHICAGO, ILLINOIS




CONSTRUCTION PLANS FOR DUPAGE AIRPORT

PHASE III - UPGRADE WILDLIFE HAZARD FENCING ON NORTHERN AIRPORT BOUNDARY


ILLINOIS PROJECT: DPA-4652 FEDERAL PROJECT: 3-17-SBGP-TBD LETTING DATE: AUGUST 2, 2019 ISSUE DATE: JULY 2, 2019



Ch2M:



LOCATION MAP



PROJECT

LOCATION

Add Marrinew DATE CH2M LICENSE: 062-053655 EXPIRES: 11/30/2019



G-103 CONTRACTOR STAGING AND ACCESS ROUTE PLAN G-105 CONSTRUCTION SAFTEY / PHASING PLAN 1 G-106 **CONSTRUCTION SAFTEY / PHASING PLAN 2** G-201 CONSTRUCTION SAFTEY / PHASING PLAN DETAILS 1 G-202 CONSTRUCTION SAFTEY / PHASING PLAN DETAILS 2 G-203 10 CONSTRUCTION SAFTEY / PHASING PLAN DETAILS 3 G-204 11 CONSTRUCTION SAFTEY / PHASING PLAN DETAILS 4 G-205 CONSTRUCTION SAFTEY / PHASING PLAN DETAILS 5 C-300 FENCING NOTES AND GATE SCHEDULE C-301 14 **FENCING PLAN 1** C-302 15 FENCING PLAN 2 C-303 FENCING PLAN 3 C-304 17 FENCING PLAN 4 C-501 **FENCE DETAILS 1** C-502 FENCE DETAILS 2 C-503 **FENCE DETAILS 3** C-504 21 **FENCE DETAILS 4** CG-100 22 STORMWATER POLLUTION PREVENTION PLAN 1 CG-101 23 STORMWATER POLLUTION PREVENTION PLAN 2 CG-102 24 STORMWATER POLLUTION PREVENTION PLAN 3 25 CG-103 STORMWATER POLLUTION PREVENTION PLAN 4 26 CG-104 STORMWATER POLLUTION PREVENTION PLAN DETAILS

DESCRIPTION

DRAWING NO. SHEET NO

G-101

G-102

CALL J.U.L.I.E

BEFORE EXCAVATING
1-800-892-0123

SUMMARY OF QUANTITIES

SUMMAR	Y - ALL ITEMS			BASE BID
ITEM NO.	PAY ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY
1	AR150520	MOBILIZATION	LS	1
2	AR150530	TRAFFIC MAINTENANCE	LS	1
3	AR156510	SILT FENCE	LF	465
4	AR156515	STRAW WATTLE	LF	400
5	AR156520	INLET PROTECTION	EA	43
6	AR152410	UNCLASSIFIED EXCAVATION	CY	232
7	AR152460	TOPSOIL STRIPPING	CY	775
8	AR162220	CLASS E MANUAL SLIDE GATE - 20'	EA	1
9	AR162508	CLASS E FENCE 8'	LF	4,487
10	AR162531	WALKWAY GATES, CLASS E	EA	5
11	AR162610	CLASS E GATE - 10'	EA	2
12	AR162614	CLASS E GATE - 14'	EA	1
13	AR162616	CLASS E GATE - 16'	EA	1
14	AR162716	ELECTRIC GATE - 16'	EA	1
15	AR162720	ELECTRIC GATE - 20'	EA	3
16	AR162722	ELECTRIC GATE - 22'	EA	1

SUMMAR	Y - ALL ITEMS			BASE BID
ITEM NO.	PAY ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY
17	AR162725	ELECTRIC GATE - 25'	EA	1
18	AR162730	ELECTRIC GATE - 30'	EA	1
19	AR162900	REMOVE CLASS E FENCE	LF	4,628
20	AR162905	REMOVE GATE	EA	5
21	AR162908	REMOVE ELECTRIC GATE	EA	7
22	AR162910	REMOVE CLASS E GATE	EA	7
23	AR162920	REMOVE MANUAL SLIDE GATE	EA	1
24	AR162948	ADJUST ELECTRIC GATE	EA	6
25	AR209606	CRUSHED AGG BASE COURSE - 6"	SY	4,676
26	AR801759	WILDLIFE DETERRENT BARRIER	LF	10,464
27	AR801760	CONCRETE PAD AT GATES	CY	2
28	AR801762	BARBED WIRE 3 STRANDS	LF	19,745
29	AR901510	SEEDING	AC	1.6
30	AR908510	MULCHING	AC	1.6
31	AS162401	VINYL FENCE UPGRADE	LF	4,713

NOTE:
ALL PAY ITEMS INCLUDED IN THE PLAN SUMMARY OF QUANTITY TABLE ARE SHOWN WITH AN "AR" DESIGNATION (EXAMPLE ITEM AR162905 GATE REMOVAL) WHICH INDICATES A BASE BID PAY ITEM AND QUANTITY. ADDITIVE ALTERNATE PAY ITEMS SHALL BE DESIGNATED BY "AS" CORRESPONDING TO ADDITIVE ALTERNATE 1.

FEDERAL AVIATION ADMINISTRATION FAR FIELD MONITOR

BID ADDITIVES:
BID ADDITIVE 1 - QUANTITIES ARE REPRESENTATIVE OF ADDING VINYL COATING TO THE PROPOSED FENCE AND GATES.

ABBREVIATIONS:

EL or ELEV ESVCP EX

EXTRA STRONG VITRIFIED CLAY PIPE EXISTING

AB ABV A/C AC ADJ AGG AGS ALD ALSF ARFF AS ASPH ASTM AUX AVE. ATCT AX	AGGREGATE BASE ABOVE ACCESS CONTROL ACRES ADJUST AGGREGATE AUXILIARY GAS VALVE AIRFIELD LIGHTING DUCT APPROACH LIGHTING SEQUENCE FLASHERS AIRPORT RESCUE AND FIRE FIGHTING AERIAL SURVEYS ASPHALT AMERICAN SOCIETY FOR TESTING AND MATERIALS AUXILIARY AVENUE AIR TRAFFIC CONTROL TOWER AXIS OF ROTATION
B-B BLVD BM BV	BACK TO BACK BOULEVARD BENCHMARK BALL VALVE
CL CB CC CED CI CM CMH CMP COMED COMM CONC C.Y. CSPN	CENTERLINE CATCH BASIN CENTER TO CENTER COMBINED / COMMON ELECTRICAL DUCTBANK CAST IRON CONSTRUCTION MANAGER COMMUNICATION MANHOLE CORRUGATED METAL PIPE COMMONWEALTH EDISON COMMUNICATIONS CONCRETE CUBIC YARD CARGO SITE PREP NORTH
DAA DET DIA. DIP DME DOA	DUPAGE AIRPORT AUTHORITY DETAIL DIAMETER DUCTILE IRON PIPE DISTANCE MEASURING EQUIPMENT DEPARTMENT OF AVIATION
E ED or E.D. EMH EL or ELEV ESVCP	EAST EDGE DRAIN ELECTRIC MANHOLE ELEVATION EXTRA STRONG VITRIFIED CLAY PIPE

ABBREVIATIONS:

FH FT	FIRE HYDRANT FEET
G	GRADE
GRND	GROUND
GS	GLIDE SLOPE
HR	HANGAR ROAD
HV	HIGH VOLTAGE
IDOT ILS IE or I.E. ID IH INV.	ILLINOIS DEPARTMENT OF TRANSPORTATION INSTRUMENT LANDING SYSTEM INVERT ELEVATION IDENTIFICATION INSPECTION HOLE INVERT
JV	JUNCTION CHAMBER
JC	JOINT VALVE
KV	KILOVOLT
K=L/A	LENGTH OF VERTICAL CURVE/ALGEBRAIC DIFFERENCE IN GRADE
L	LENGTH
L.S.	LUMP SUM
LOC	LOCALIZER
MAX MH MIN MJ MPR	MAXIMUM MANHOLE MINIMUM MECHANICAL JOINT MOUNT PROSPECT ROAD
N NAVD N.C. N.O. N.I.C.	NORTH NORTH AMERICAN VERTICAL DATUM NORMALLY CLOSED NORMALLY OPEN NOT IN CONTRACT
NTS	NOT TO SCALE
NO	NUMBER
NPR	NORTH PERIMETER ROAD
O.D. OFA OZ	OUTSIDE DIAMETER OBJECT FREE AREA OUNCE

ABBREVIATIONS:

PAPI PC PCC PCCP P.I. PL PT PVC PVI PVT PVC PIPE PSI	PRECISION APPROACH PATH INDICATOR LIGHTS POINT OF CURVATURE POINT OF COMPOUND CURVATURE PORTLAND CEMENT CONCRETE PAVEMENT POINT OF INTERSECTION PROPERTY LINE POINT OF TANGENCY POINT OF VERTICAL CURVATURE POINT OF VERTICAL INTERSECTION POINT OF VERTICAL TANGENCY POLYVINYL CHLORIDE PIPE POUNDS PER SQUARE INCH
R RAD RC RCP RPP RPU REV. RGS RD. RSA R/W RPZ	REMOVE RADIUS REINFORCED CONCRETE REINFORCED CONCRETE PIPE REINFORCED POLYPROPYLENE REMOTE PROCESSING UNIT REVISION RIGID STEEL ROAD RUNWAY SAFETY AREA RUNWAY RUNWAY PROTECTION ZONE
SA SCH SD SHT S SQR S.F. S.Y. STA ST. ST	SANITARY SCHEDULE STORM DRAIN SHEET SOUTH SQUARE SQUARE SQUARE FEET SQUARE YARD STATION STREET STORM SEWER
T T.S. TSA T/W TDZ TYP	TANGENT TANGENT SPIRAL TAXIWAY SAFETY AREA TAXIWAY TOUCHDOWN ZONE TYPICAL
UD or U.D. UMH U.N.O.	UNDERDRAIN UNDERDRAIN MANHOLE UNLESS NOTED OTHERWISE
VERT. VPI W W/ WMG YD	VERTICAL VERTICAL POINT OF INTERSECTION WEST WITH WEST MASS GRADING YARD

SUMMARY OF QUANTITIES AND ABBREVIAITONS **VERIFY SCALE**

BAR IS ONE INCH ON ORIGINAL DRAWING.

DPA-4652

2 of 26

G-101

2. THE PROJECT IS TO BE COMPLETED IN A TIMELY MANNER IN ACCORDANCE WITH THE CONTRACTOR'S APPROVED PROJECT SCHEDULE. THE SCHEDULE SHALL BE PROVIDED FOR COMPLETION OF THE WORK AS SHOWN ON THE PLANS AND DESCRIBED IN THE CONTRACT SPECIFICATIONS. THE CONTRACTOR SHALL KEEP AIRPORT OPERATIONS INFORMED OF UPDATES TO THE PROJECT SCHEDULE AT ALL TIMES.

3. THE CONTRACTOR SHALL COMPLETE THE ENTIRE PROJECT WITHIN THE TIME STATED IN THE CONTRACT.

4. THE AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF WORK WITH THE DAA, FAA, IDOT AND LOCAL ATCT REPRESENTATIVES IS MANDATORY TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS.

5. CONSTRUCTION AND MAINTENANCE OPERATIONS BY OTHERS MAY OCCUR CONCURRENTLY AND AT TIMES IN THE VICINITY OF CONSTRUCTION ASSOCIATED WITH THIS PROJECT. THE CONTRACTOR SHALL COORDINATE HIS OPERATIONS AND COOPERATE WITH MAINTENANCE CREWS AND OTHER CONTRACTORS WORKING ON THE AIRPORT. CONTRACTOR COORDINATION WITH APPROPRIATE GOVERNMENT AND UTILITY AGENCIES IS ALSO REQUIRED PRIOR TO AND DURING CONSTRUCTION.

6. ACCESS TO THE SITE - THE CONTRACTOR'S ACCESS POINTS TO THE SITE SHALL BE THROUGH DESIGNATED SECURITY GATES AS SHOWN ON THE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL VEHICLES AND PERSONNEL THAT ENTER THROUGH THESE DESIGNATED AIRPORT SECURITY GATES. AIRPORT SECURITY GATES SHALL BE SECURED AT ALL TIMES WHEN NOT IN USE.

7. HAUL ROUTES - THE CONTRACTOR'S ON-AIRPORT HAUL ROUTES AND CONSTRUCTION ACCESS SHALL BE EXISTING HAUL ROADS WHERE AVAILABLE. ANY DEBRIS (WHETHER CAUSED BY THE CONTRACTOR OR NOT) SHALL BE REMOVED IMMEDIATELY BY THE CONTRACTOR. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS, COUNTY ROADS, OR CITY STREETS) WITH THE APPROPRIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE ROADS USED AS HAUL ROUTES/CONSTRUCTION ACCESS SHALL BE MAINTAINED AND STABILIZED BY THE CONTRACTOR AS REQUIRED TO SUPPORT CONSTRUCTION EQUIPMENT THROUGHOUT THE DURATION OF THIS PROJECT AND SHALL BE RESTORED, AT THE CONTRACTOR'S EXPENSE, TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL ROUTE/CONSTRUCTION ACCESS UNLESS OTHERWISE DIRECTED BY THE RESIDENT ENGINEER. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL ROUTES/CONSTRUCTION ACCESS SHALL BE JOINTLY INSPECTED AND AGREED UPON BY THE CONTRACTOR AND THE RESIDENT ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT/REMOVE TEMPORARY HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S TOTAL RESPONSIBILITY AND SHALL BE APPROVED BY THE RESIDENT ENGINEER PRIOR TO COMMENCING THE WORK. ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES.

8. CONTRACTOR'S STAGING AREAS - AN AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS. THE CONTRACTOR SHALL PROTECT EXISTING UTILITIES, FENCE, TREES, ETC. WITHIN THE STAGING AREA AND THE SITE SHALL BE RESTORED TO ITS ORIGINAL CONDITION WITHIN THIRTY (30) DAYS OF THE COMPLETION OF USE. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED. CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE/STAGING AREA WHEN CONSTRUCTION IS NOT IN PROGRESS.

9. DISPOSAL AREAS - EXCESS SOILS, MILLED ASPHALT, CONCRETE RUBBLE, FENCE POSTS, FENCE FOOTINGS, FENCE FABRIC AND UNSUITABLE EXCAVATION MUST BE DISPOSED AT APPROVED LOCATIONS OFFSITE. OFFSITE DISPOSAL AREAS SHALL BE IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL LAWS.

10. SAFETY - THE CONTRACTOR SHALL CONDUCT ALL ACTIVITIES IN A SAFE MANNER AS SPECIFIED BY LOCAL, STATE AND FEDERAL LAWS.

11. EXISTING AIRFIELD LIGHTING SYSTEMS - NO INTERRUPTIONS OF EXISTING AIRFIELD LIGHTING SYSTEMS ARE ANTICIPATED IN THIS PROJECT AND SHALL NOT BE PERMITTED. ALL AIRFIELD LIGHTING CIRCUITS AFFECTED BY THIS PROJECT SHALL BE TEMPORARILY MAINTAINED BY THE CONTRACTOR DURING OPERATIONAL PERIODS AND COORDINATED THROUGH THE RESIDENT ENGINEER. THE CONTRACTOR SHALL IMMEDIATELY REPLACE RUNWAY/TAXIWAY SIGNS AND LIGHTS DAMAGED AS A RESULT OF THE CONTRACTOR'S OPERATION AT THE CONTRACTOR'S EXPENSE.

12. CONSTRUCTION LIMITS - ALL CONTRACTOR VEHICLES AND TRAFFIC (UNLESS OTHERWISE AUTHORIZED) SHALL REMAIN WITHIN THE DESIGNATED STAGING AREA, CONSTRUCTION LIMITS AND HAUL ROUTES. CONSTRUCTION, STORAGE AND STOCKPILING LIMITS ARE FURTHER DEFINED IN THE SECTION TITLED, "SAFETY REQUIREMENTS DURING CONSTRUCTION".

13. PORTABLE FLOODLIGHTING - IF NEEDED, THE CONTRACTOR SHALL PROVIDE PORTABLE FLOODLIGHTING AS REQUIRED FOR NIGHT CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL PROVIDE SUFFICIENT UNITS SO THAT ALL WORK AREAS ARE ILLUMINATED TO A MINIMUM LEVEL OF 5 HORIZONTAL FOOT CANDLES. THE LIGHTING LEVELS SHALL BE CALCULATED AND MEASURED IN ACCORDANCE WITH THE CURRENT STANDARDS OF THE ILLUMINATION ENGINEERING SOCIETY. THE CONTRACTOR SHALL COORDINATE THE USE OF FLOODLIGHTING WITH THE AIR TRAFFIC CONTROL TOWER TO ENSURE LIGHTING DOES NOT COMPROMISE THE CONTROL TOWER PERSONNEL'S VISIBILITY OR CAUSE CONFUSION TO PILOTS.

14. THE CONTRACTOR SHALL OBTAIN ALL PERMITS AND LICENSES REQUIRED FOR THE CONSTRUCTION WORK. REFER TO THE SPECIAL CONDITIONS AND GENERAL CONDITIONS SECTIONS OF THE CONTRACT DOCUMENTS.

15. EXISTING TOPOGRAPHIC, UNDERGROUND AND ABOVE GROUND UTILITY DATA FOR THIS PROJECT WERE OBTAINED FROM AVAILABLE "AS-BUILTS" AND ARE FOR REFERENCE ONLY. UTILITIES MUST BE FIELD LOCATED.

16. PROTECTION AND REPAIR OF EXISTING UTILITIES - LOCATIONS OF KNOWN EXISTING AIRPORT UNDERGROUND UTILITIES ARE SHOWN ON THE PLANS FOR INFORMATION ONLY. THE CONTRACTOR SHALL VERIFY ALL UTILITIES. BY VISUAL, ELECTRICAL AND BY HAND EXCAVATION OR OTHER METHODS IN COORDINATION WITH ALL UTILITY COMPANIES AND DAA FACILITIES, PRIOR TO BEGINNING ANY CONSTRUCTION OPERATIONS. ANY AND ALL CONFLICTS OF EXISTING UTILITIES BY THE PROPOSED IMPROVEMENTS SHALL BE RESOLVED WITH THE RESIDENT ENGINEER PRIOR TO BEGINNING THE CONSTRUCTION ACTIVITIES. ANY REPAIRS TO EXISTING UTILITIES DAMAGED BY CONTRACTOR ACTIVITIES SHALL BE COMPLETED IMMEDIATELY BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF AN FAA REPRESENTATIVE. THE FAA MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS, IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS AT NO ADDITIONAL EXPENSE TO THE OWNER.

17. IF ANY UNUSUAL ODORS, SOIL STAINS OR BURIED WASTES ARE ENCOUNTERED, STOP WORK IMMEDIATELY AND NOTIFY THE OWNER, AND/OR RESIDENT ENGINEER.

CALL J.U.L.I.E BEFORE EXCAVATING 1-800-892-0123

18. THE CONTRACTOR SHALL FURNISH THE OWNER FIVE (5) SETS OF OPERATION AND MAINTENANCE MANUALS FOR ALL NEW EQUIPMENT INSTALLED.

19. WORK PERFORMED UNDER THIS CONTRACT WILL NOT BE CONSIDERED COMPLETE UNTIL FINAL ACCEPTANCE OF THE PROJECT BY THE OWNER AND RECEIPT AND APPROVAL OF THE FOLLOWING DOCUMENTS:

A) CONTRACTOR'S WAIVER AND RELEASE OF LIEN.
B) ABSOLUTE BILL OF SALE.
C) CONTRACTOR'S LETTER OF WARRANTY (I.E., LETTER AGREEMENT).
D) CONTRACTOR AS-BUILTS.

E) FINAL PUNCH LIST COMPLETED AND ACCEPTED BY THE RESIDENT ENGINEER.

F) TRANSFER OF OWNER WARRANTY.

20. IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, PREVAILING WAGE RATES SHALL BE POSTED AT THE CONTRACTOR STAGING AREA IN A WEATHERPROOF ENCLOSURE AND COPIES SHALL BE SUBMITTED TO THE RESIDENT ENGINEER AND THE OWNER.

21. CONTRACTOR SHALL PROVIDE ALL NECESSARY TRAFFIC CONTROL TO ALLOW FOR A MINIMUM OF ONE LANE OF TRAFFIC AT ALL TIMES AND CONTRACTOR SHALL MAINTAIN ACCESS TO BUILDING PARKING LOTS AT ALL TIMES DURING CONSTRUCTION. (INCIDENTAL TO THE CONTRACT).

22. WHERE THE CONTRACTOR IS IMPACTING EXISTING GRADES THE CONTRACTOR SHALL CONSTRUCT ALL IMPROVEMENTS TO DRAIN OFF. ANY AREAS IMPACTED BY THE CONTRACTOR THAT ARE FOUND TO NOT DRAIN PROPERLY BY THE ENGINEER SHALL BE REMOVED AND REPLACED AT THE CONTRACTORS EXPENSE.

23. MATERIALS REMOVED FROM THE PROJECT WILL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED OTHERWISE.

24. CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS OR A WORKING BEACON LIGHT ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION.

25. TRAFFIC CONTROL DEPICTED IN THESE PLANS AND THE APPLICABLE IDOT DETAILS AND STANDARDS ARE THE MINIMUM REQUIREMENTS. TRAFFIC CONTROL AND PROTECTION SHALL BE PERFORMED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS, DIVISION 700; APPLICABLE GUIDELINES IN THE ILLINOIS MANUAL ON UNIFORM TRAFFIC DEVICES FOR STREETS AND HIGHWAYS; AND APPLICABLE HIGHWAY STANDARDS FOR TRAFFIC CONTROL.

26. CONTRACTOR FIELD STAFF SHALL ATTEND DPA SAFETY MEETING PRIOR TO MOBILIZATION.

27. SURVEYOR IS NOT REQUIRED FOR THE FENCE LAYOUT. LAYOUT WILL BE BASED ON EXISTING ALIGNMENT. AS BUILT SURVEY OF THE FINAL ALIGNMENT IS REQUIRED.

GENERAL PROJECT DESCRIPTION

1. THE WORK GENERALLY CONSISTS OF:

·REMOVAL OF EXISTING 6-FT SECURITY FENCING, GATES, POSTS, AND FOUNDATIONS
·INSTALLATION OF 8-FT SECURITY FENCING, GATES, POSTS AND FOUNDATIONS WITH WILDLIFE DETERRENT FENCE BARRIER AND 4-FT WIDE VEGATATION FREE ZONE OR ADDITION OF WILDLIFE DETERRENT BARRIER AND 4-FT WIDE VEGATATION FREE ZONE TO THE EXISITNG 8-FT SECURITY FENCING
·INSTALLATION OF WILDLIFE DETERRENT PAD UNDER GATES

SECURITY NOTES

1. THE CONTRACTOR SHALL DESIGNATE TO THE RESIDENT ENGINEER IN WRITING THE NAME OF ITS 'CONTRACTOR SECURITY OFFICER' (C.S.O.). THE C.S.O. SHALL REPRESENT THE CONTRACTOR ON THE SECURITY REQUIREMENTS FOR THE CONTRACT. IT IS THE CONTRACTORS RESPONSIBILITY TO FAMILIARIZE HIMSELF/HERSELF WITH THE VARIOUS ASPECTS OF FAR 49 CFR PART 1542: "AIRPORT SECURITY", ADMINISTERED BY THE TRANSPORTATION SECURITY ADMINISTRATION (TSA). ANY VIOLATION OF CFR PART 1542 BY THE CONTRACTOR AND ANY SUBSEQUENT FINES IMPOSED DUE TO THE VIOLATION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

2. CONTRACTOR PERSONNEL SECURITY ORIENTATION: THE C.S.O. SHALL BE RESPONSIBLE FOR BRIEFING ALL CONTRACTOR PERSONNEL ON THESE REQUIREMENTS AND PROVISIONS ADOPTED BY THE DUPAGE AIRPORT AUTHORITY (DAA). ALL NEW CONTRACTOR EMPLOYEES SHALL BE BRIEFED ON THESE REQUIREMENTS PRIOR TO WORKING IN THE CONSTRUCTION AREA.

3. ACCESS TO SITE: THE AIRPORT WILL PROVIDE AIRFIELD OPERATIONS AREA ESCORTS AT NO COST TO THE CONTRACTOR. CONTRACTOR'S ACCESS TO THE SITE SHALL BE AS SHOWN ON THE SAFETY PLAN OR AS DIRECTED BY THE RESIDENT ENGINEER. NO OTHER ACCESS POINT SHALL BE ALLOWED UNLESS APPROVED BY THE RESIDENT ENGINEER. IF GATE IS TO BE LEFT UNLOCKED CONTRACTOR SHALL PROVIDE GATE GUARDS FOR THE DURATION OF THE UNLOCKED CONDITION. ALL CONTRACTOR TRAFFIC AUTHORIZED TO ENTER THE SITE SHALL BE EXPERIENCED IN THE ROUTE OR ESCORTED BY THE CONTRACTOR PERSONNEL. THE CONTRACTOR SHALL BE RESPONSIBLE FOR TRAFFIC CONTROL TO AND FROM THE ACCESS GATE TO THE SITE. A CONTRACTOR'S FLAGMAN OR TRAFFIC CONTROL PERSON SHALL MONITOR AND COORDINATE ALL CONTRACTOR TRAFFIC AT THE ACCESS GATE. THE CONTRACTOR SHALL NOT PERMIT ANY UNAUTHORIZED CONSTRUCTION PERSONNEL OR TRAFFIC ON THE AIRPORT OPERATIONS AREA (AOA). DIRECTIONAL SIGNING ALONG THE DELIVERY ROUTE TO THE STORAGE AREA OR WORK SITE SHALL BE AS DIRECTED BY THE RESIDENT ENGINEER.

4. CONSTRUCTION AREA LIMITS: THE LIMITS OF CONSTRUCTION, MATERIAL STORAGE AREAS, PARKING AREA AND OTHER AREAS DEFINED FOR THE CONTRACTOR'S EXCLUSIVE USE DURING CONSTRUCTION SHALL BE MARKED AND LIGHTED. THE CONTRACTOR SHALL ERECT AND MAINTAIN FENCING AROUND THE PERIMETER OF THESE AREAS AND VISIBLE DEVICES FOR DAY/NIGHT USE. TEMPORARY BARRICADES, FLAGGING AND FLASHING WARNING LIGHTS WILL BE REQUIRED AT CRITICAL ACCESS POINTS. THE TYPE OF MARKING AND WARNING DEVICES SHALL BE APPROVED BY THE RESIDENT ENGINEER AND AIRPORT OPERATIONS.

5. THE C.S.O. SHALL PROVIDE OPERATIONS AND THE RESIDENT ENGINEER A CURRENT LIST OF COMPANIES AUTHORIZED TO CONDUCT WORK ON THE AIRPORT. CONTRACTOR EMPLOYEE PERSONAL VEHICLES SHALL BE RESTRICTED TO THE CONTRACTORS EMPLOYEE PARKING AREA AND ARE NOT ALLOWED ON THE AIRFIELD AT ANY TIME.

LIST OF STATE STANDARDS AND DISTRICT DETAILS

701001-02 OFF-RD OPERATIONS, 2L, 2W MORE THAN 15' AWAY

701006-05 OFF-RD OPERATIONS, 2L, 2W MORE THAN 15' TO 24" FROM PAVEMENT EDGE

701901-05 TRAFFIC CONTROL DEVICES

701901-08 TYPE II TRAFFIC BARRICADE

DUPAGE AIRPORT

TL TM AUTHORITY

BY APVD

	8735 W HIGGINS ROAD						
. NAA.	SUITE 400						
	CHICAGO, IL 60631						
	PHASE III- UPGRADE WILDLIFE HAZARD FENCING						
SECURITY NOTES	ON NORTHERN AIRPORT BOUNDARY	_	2019/07/02	CON	CONSTRUCTION PLANS		F
))	DUPAGE AIRPORT (DPA)	Ö	DATE		REVISION		m m
	WEST CHICAGO, IL	DSGN	 	DR	CHK	APVD	Σ
REUSE	REUSE OF DOCUMENTS: THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF CH2M AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M.	INCORPO PART, FO	RATED HEREIN R ANY OTHER F	, AS AN INSTRUMENT OF PROFESSI PROJECT WITHOUT THE WRITTEN A	IONAL SERVICE, IS THE PROPER UTHORIZATION OF CH2M.	RTY OF	

DATE

PROJ

DWG

SHEET

NTS

VERIFY SCALE

BAR IS ONE INCH ON


ORIGINAL DRAWING.


2019/07/02


DPA-4652


3 of 26


G-102

















DATE: 2019\07\02

PLOT TIME: 5:23:42 PM


VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING.

DPA-4652

10 of 26

G-203



PHASING POINTS

POINT#	LATITUDE	LONGITUDE	NORTHINGS	EASTINGS	ELEV.	CONST. EQUIP.	MAX.	PAVEMENT	SHEET#
FENCE01	41° 54' 27"	88° 15' 20.2"	1,908,892.56	1,005,406.83	758.00	25.00	ELEV. 783.00	STATUS No Closure	G-201
FENCE02	41° 54' 28.4"	88° 15' 20.09"	1,909,033.95	1,005,414.44	758.00	25.00	783.00	No Closure	G-201
FENCE03	41° 54' 29.22"	88° 15' 20.2"	1,909,116.69	1,005,405.91	758.00	25.00	783.00	No Closure	G-201
FENCE04	41° 54' 30.18"	88° 15' 20.28"	1,909,214.01	1,005,400.13	758.00	25.00	783.00	No Closure	G-201
FENCE05	41° 54' 30.16	88° 15' 22.11"	1,909,220.77	1,005,261.79	758.00	25.00	783.00	No Closure	G-201
FENCE06	41° 54' 30.2"	88° 15' 27.67"	1,909,215.90	1,003,201.73	757.00	25.00	782.00	No Closure	G-201
FENCE07	41° 54' 30.19"	88° 15' 28.65"	1,909,215.31	1,004,767.29	757.00	25.00	782.00	No Closure	G-201
FENCE08	41° 54' 29.33"	88° 15' 28.77"	1,909,127.47	1,004,767.29	757.00	25.00	782.00	No Closure	G-201
FENCE09	41° 54' 29.27"	88° 15' 30.61"	1,909,121.66	1,004,730.29	757.00	25.00	782.00	No Closure	G-201
FENCE10	41° 54' 30.12"	88° 15' 33.89"	1,909,206.93	1,004,370.77	760.00	25.00	785.00	No Closure	G-201
FENCE11	41° 54' 30.12"	88° 15' 34.77"	1,909,214.66	1.004.304.69	748.00	25.00	773.00	No Closure	G-201
FENCE12	41° 54' 32.72"	88° 15' 34.69"	1,909,470.93	1,004,310.04	748.00	25.00	773.00	No Closure	G-201
FENCE13	41° 54' 32.72	88° 15' 33.92"	1,909,478.17	1,004,368.38	756.00	25.00	781.00	No Closure	G-201
FENCE14	41° 54' 32.79"	88° 15' 30.18"	1,909,477.94	1,004,651.38	757.00	25.00	782.00	No Closure	G-201
FENCE15	41° 54' 32.79"	88° 15' 29.22"	1,909,477.94	1,004,031.38	757.00	25.00	782.00	No Closure	G-201
FENCE16	41° 54' 32.79	88° 15' 25.58"	1,909,478.75	1,004,723.73	757.00	25.00	782.00	No Closure	G-201
FENCE17	41° 54' 32.79"	88° 15' 24.59"	1,909,478.49	1,004,999.42	757.00	25.00	782.00	No Closure	G-201
FENCE18	41° 54' 34.87"	88° 15' 22.36"	1,909,689.45	1,005,242.51	756.00	25.00	782.00	No Closure	G-201
FENCE19	41° 54' 36.15"	88° 15' 22.52"	1,909,818.57	1,005,230.20	753.00	25.00	778.00	No Closure	G-201
FENCE20	41° 54' 36.23"	88° 15' 25.02"	1,909,826.22	1,005,041.04	754.00	25.00	779.00	No Closure	G-201
FENCE21	41° 54' 36.29"	88° 15' 28.3"	1,909,832.69	1,004,793.24	754.00	25.00	779.00	No Closure	G-201
FENCE22	41° 54' 37.1"	88° 15' 33.81"	1,909,913.52	1,004,376.70	754.00	25.00	779.00	No Closure	G-201
FENCE23	41° 54' 37.77"	88° 15' 34.44"	1,909,982.14	1,004,328.95	752.00	25.00	777.00	No Closure	G-201
FENCE24	41° 54' 37.77"	88° 15' 35.54"	1,909,981.28	1,004,245.91	752.00	25.00	777.00	No Closure	G-201
FENCE25	41° 54' 36.93"	88° 15' 35.71"	1,909,896.84	1,004,233.20	752.00	25.00	777.00	No Closure	G-201
FENCE26	41° 54' 37.41"	88° 15' 36.8"	1,909,945.12	1,004,253.20	755.00	25.00	780.00	No Closure	G-201
FENCE27	41° 54' 38.86"	88° 15' 38.34"	1,910,091.84	1,004,033.94	755.00	25.00	780.00	No Closure	G-201
FENCE28	41° 54' 40.15"	88° 15' 39.1"	1,910,222.16	1,003,976.39	753.00	25.00	778.00	No Closure	G-201
FENCE29	41° 54' 40.32"	88° 15' 40.69"	1,910,239.66	1,003,856.27	752.00	25.00	777.00	No Closure	G-201
FENCE30	41° 54' 43.53"	88° 15' 42.82"	1,910,563.86	1,003,695.06	749.00	25.00	774.00	No Closure	G-202
FENCE31	41° 54' 49.53"	88° 15' 43.35"	1,911,171.31	1,003,654.14	754.00	25.00	779.00	No Closure	G-202
FENCE32	41° 54' 53.99"	88° 15' 43.35"	1,911,623.03	1,003,653.94	757.00	25.00	782.00	No Closure	G-202
FENCE33	41° 54' 54.62"	88° 15' 44.1"	1,911,687.07	1,003,596.87	756.00	25.00	781.00	No Closure	G-202
FENCE34	41° 54' 55.9"	88° 15' 44.11"	1,911,816.02	1,003,596.13	756.00	25.00	781.00	No Closure	G-202
FENCE35	41° 54' 59.19"	88° 15' 43.69"	1,912,149.53	1,003,627.49	759.00	25.00	784.00	No Closure	G-202
FENCE36	41° 54' 58.7"	88° 15' 35.93"	1,912,099.90	1,004,214.58	760.00	25.00	785.00	No Closure	G-202
FENCE37	41° 54' 58.52"	88° 15' 33.64"	1,912,082.35	1,004,387.29	760.00	25.00	785.00	No Closure	G-202
FENCE38	41° 54' 57.53"	88° 15' 19.58"	1,911,982.70	1,005,450.88	752.00	25.00	777.00	No Closure	G-202
FENCE39	41° 54' 57.21"	88° 15' 17.05"	1,911,950.18	1,005,641.76	752.00	25.00	777.00	No Closure	G-202
FENCE40	41° 54' 57.1"	88° 15' 15.69"	1,911,939.42	1,005,744.72	752.00	25.00	777.00	No Closure	G-202
FENCE41	41° 54' 56.95"	88° 15' 13.81"	1,911,924.52	1,005,886.79	752.00	25.00	777.00	No Closure	G-202
FENCE42	41° 54' 56.74"	88° 15' 11.11"	1,911,903.01	1,006,091.32	752.00	25.00	777.00	No Closure	G-202
FENCE43	41° 54' 56.59"	88° 15' 9.23"	1,911,888.09	1,006,233.15	752.00	25.00	777.00	No Closure	G-202
FENCE44	41° 54' 56.48"	88° 15' 7.88"	1,911,877.15	1,006,335.44	752.00	25.00	777.00	No Closure	G-203
FENCE45	41° 54' 56.27"	88° 15' 5.7"	1,911,855.97	1,006,500.11	752.00	25.00	777.00	No Closure	G-203
FENCE46	41° 54' 56.22"	88° 15' 5.15"	1,911,851.38	1,006,541.60	752.00	25.00	777.00	No Closure	G-203
FENCE47	41° 54' 55.98"	88° 15' 2.06"	1,911,826.73	1,006,775.49	752.00	25.00	777.00	No Closure	G-203
FENCE48	41° 54' 55.96"	88° 15' 1.85"	1,911,825.17	1,006,773.49	752.00	25.00	777.00	No Closure	G-203
FENCE49	41° 54' 55.75"	88° 15' 0.52"	1,911,803.74	1,006,891.85	752.00	25.00	777.00	No Closure	G-203
FENCE50	41° 54' 53.75"	88° 15' 0.67"	1,911,533.53	1,006,880.93	752.00	25.00	777.00	No Closure	G-203
- LINOLJU	71 07 00.00	50 15 0.07	1,011,000.00	1,000,000.30	102.00	20.00	111.00	INO CIOSUIE	J-203

PHASING POINTS CONTINUED

					I	CONOT		<u> </u>	
POINT#	LATITUDE	LONGITUDE	NORTHINGS	EASTINGS	ELEV.	CONST. EQUIP. HEIGHT	MAX. ELEV.	PAVEMENT STATUS	SHEET#
FENCE51	41° 54' 52.83"	88° 14' 59.34"	1,911,508.95	1,006,980.92	752.00	25.00	777.00	No Closure	G-203
FENCE52	41° 54' 55.46"	88° 14' 58.02"	1,911,774.93	1,007,080.45	752.00	25.00	777.00	No Closure	G-203
FENCE53	41° 54' 56.25"	88° 14' 55.8"	1,911,854.67	1,007,248.58	752.00	25.00	777.00	No Closure	G-203
FENCE54	41° 54' 58.45"	88° 14' 53.76"	1,912,077.75	1,007,402.55	753.00	25.00	778.00	No Closure	G-203
FENCE55	41° 55' 2.52"	88° 14' 52.05"	1,912,489.73	1,007,531.65	757.00	25.00	782.00	No Closure	G-203
FENCE56	41° 55' 6.62"	88° 14' 51.89"	1,912,904.77	1,007,542.83	759.00	25.00	784.00	No Closure	G-203
FENCE57	41° 55' 11.03"	88° 14' 51.8"	1,913,351.11	1,007,549.30	755.00	25.00	780.00	No Closure	G-203
FENCE58	41° 55' 14.25"	88° 14' 51.74"	1,913,677.28	1,007,553.57	756.00	25.00	781.00	No Closure	G-203
FENCE59	41° 55' 14.89"	88° 14' 49.18"	1,913,742.14	1,007,747.07	758.00	25.00	783.00	No Closure	G-203
FENCE60	41° 55' 14.81"	88° 14' 46.9"	1,913,734.16	1,007,919.25	757.00	25.00	782.00	No Closure	G-203
FENCE61	41° 55' 14.39"	88° 14' 43.8"	1,913,691.61	1,008,153.49	755.00	25.00	780.00	No Closure	G-203
FENCE62	41° 55' 13.97"	88° 14' 40.72"	1,913,649.82	1,008,386.70	755.00	25.00	780.00	No Closure	G-204
FENCE63	41° 55' 11.82"	88° 14' 26.61"	1,913,433.35	1,009,453.54	754.00	25.00	779.00	No Closure	G-204
FENCE64	41° 55' 11.3"	88° 14' 22.11"	1,913,380.88	1,009,793.98	754.00	25.00	779.00	No Closure	G-204
FENCE65	41° 55' 10.07"	88° 14' 20.92"	1,913,256.92	1,009,883.71	754.00	25.00	779.00	No Closure	G-204
FENCE66	41° 55' 8.49"	88° 14' 18.69"	1,913,096.66	1,010,052.53	756.00	25.00	781.00	No Closure	G-204
FENCE67	41° 55' 6.41"	88° 14' 18.72"	1,912,886.06	1,010,050.73	754.00	25.00	779.00	No Closure	G-204
FENCE68	41° 55' 3.51"	88° 14' 18.53"	1,912,593.26	1,010,065.24	752.00	25.00	777.00	No Closure	G-204
FENCE69	41° 54' 52.81"	88° 14' 22.44"	1,911,509.80	1,009,770.91	754.00	25.00	779.00	No Closure	G-204
FENCE70	41° 54' 51.14"	88° 14' 21.69"	1,911,340.37	1,009,827.56	754.00	25.00	779.00	No Closure	G-204
FENCE71	41° 54' 42.32"	88° 15' 42.15"	1,910,441.42	1,003,745.38	751.00	25.00	776.00	No Closure	G-204
FENCE72	41° 54' 44.49"	88° 15' 43.2"	1,910,660.90	1,003,665.54	750.00	25.00	775.00	No Closure	G-204
FENCE73	41° 54' 45.94"	88° 15' 43.35"	1,910,807.63	1,003,654.41	751.00	25.00	776.00	No Closure	G-204
FENCE74	41° 54' 47.12"	88° 15' 43.35"	1,910,927.63	1,003,654.32	752.00	25.00	777.00	No Closure	G-204
FENCE75	41° 54' 48.31"	88° 15' 43.35"	1,911,047.63	1,003,654.23	753.00	25.00	778.00	No Closure	G-204
FENCE76	41° 54' 50.64"	88° 15' 43.35"	1,911,284.24	1,003,654.09	755.00	25.00	780.00	No Closure	G-204
FENCE77	41° 54' 51.76"	88° 15' 43.35"	1,911,397.17	1,003,654.04	756.00	25.00	781.00	No Closure	G-204
FENCE78	41° 54' 52.88"	88° 15' 43.35"	1,911,510.10	1,003,653.99	757.00	25.00	782.00	No Closure	G-204
FENCE79	41° 54' 57.49"	88° 15' 43.94"	1,911,976.79	1,003,608.64	758.00	25.00	783.00	No Closure	G-204
FENCE80	41° 55' 7.68"	88° 14' 51.87"	1,913,012.41	1,007,544.30	758.00	25.00	783.00	No Closure	G-203

NOTES:

- 1. ALL AIRFIELD PAVEMENT CLOSURES SHALL BE TEMPORARY CLOSURES AS DESCRIBED IN FAA AC 150/5370-2G, "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION". THE CONTRACTOR SHALL COMPLY WITH ALL THE REQUIREMENTS SET FORTH IN THE CONTRACT DOCUMENTS REGARDING AIRFIELD CLOSURES, SAFETY, AND SECURITY.
- 2. PRIOR TO REOPENING CLOSED AIRFIELD PAVEMENTS, THE ENTIRE SAFETY AREA MUST MEET FAA CRITERIA UNLESS OTHERWISE DIRECTED BY THE RESIDENT ENGINEER. PAVEMENT CLOSURES ARE NOT ANTICIPATED ON THIS PROJECT. LOW-PROFILE BARRICADES BEING UTILIZED TO DELINEATE PAVEMENT EDGE ADJACENT TO CONTRACTOR WORKING AREA.
- 3. FLASHERS TO BE BATTERY OPERATED AND/OR SOLAR POWERED. LENS TO BE RED AND BE ABLE TO ROTATE 90°.
- 4. FACING OF LOW-PROFILE BARRICADE TO BE COVERED WITH REFLECTIVE MATERIAL.
- 5. LOW-PROFILE BARRICADES TO BE PLACED WITH A MAXIMUM 8'-0" GAP BETWEEN BARRICADES ALONG OPERATIONAL PAVEMENT, ADJACENT TO CONSTRUCTION, AS DIRECTED BY THE PROJECT MANAGER. ONE ORANGE DELINEATOR CONE SHALL BE INSTALLED AT THE MIDPOINT BETWEEN BARRICADES.
- 6. FLASHERS SHALL BE SECURED TO THE BARRICADES, PER MANUFACTURER'S INSTRUCTIONS. ALTERNATE FLASHER LENSES SO THAT EVERY OTHER LENS IS ROTATED 90°.
- 7. LOW -PROFILE BARRICADES SHALL BE OF LOW MASS, EASILY COLLAPSIBLE UPON CONTACT WITH AN AIRCRAFT OR ANY OF IT'S COMPONENTS, AND WEIGHTED OR STURDILY ATTACHED TO THE SURFACE. IF AFFIXED TO THE SURFACE, THE BARRICADE MUST BE FRANGIBLE AT GRADE LEVEL OR AS LOW AS POSSIBLE, NOT TO EXCEED 3 INCHES ABOVE THE GROUND.
- 8. THE CONTRACTOR SHALL PROVIDE BARRICADES AND DELINEATOR CONES WITH RED FLASHING BATTERY OPERATED LIGHTS AS SHOWN IN GOOD WORKING ORDER. CONTRACTOR SHALL MAINTAIN ALL BARRICADES AND ENSURE THEY ARE IN WORKING ORDER TWENTY-FOUR (24) HOURS A DAY, FOR THE DURATION OF THE PROJECT. THE BARRICADE LIGHTING SHALL BE CHECKED NIGHTLY BY THE CONTRACTOR.
- 9. THE LIGHTS SHALL BE OPERATIONAL AT EACH BARRICADE LOCATION AT ALL TIMES. ANY LIGHTS FOUND NON-OPERATIONAL SHALL BE REPAIRED IMMEDIATELY WITH EMERGENCY CONTACT NUMBER 24/7.
- 10. ALL BARRICADES SHALL BE CHECKED VISUALLY FOR SIGNS OF WEAR AND TEAR ON A DAILY BASIS AND SHALL BE REPAINTED OR REPLACED WHEN DEEMED APPROPRIATE BY THE RESIDENT ENGINEER. THE CONDITIONS OF LIGHTING UNITS SHALL BE CHECKED DAILY. ALL LIGHT FIXTURES SHALL BE VERIFIED IN OPERATING CONDITION AND GOOD WORKING ORDER BY THE CONTRACTOR ON A DAILY BASIS, BEFORE THE CONTRACTOR CEASES OPERATIONS FOR THE DAY.
- 11. LOW PROFILE BARRICADES TO BE LOCATED AS IDENTIFIED ON SHEET G-105 AND AS IDENTIFIED IN PHASING NOTES.

	BY APVD	REVISION	NO. DATE	(ADD) TREASE AIRPORT (ADD)		
AUTHORI	TL TM	CONSTRUCTION PLANS	1 2019/07/02	ON NORTHERN AIRPORT BOUNDARY		
DUPAGE AIR				PHASE III- UPGRADE WILDLIFE HAZARD FENCING	(1	NTS FY SO
				CHICAGO, IL 60631	MS I I	
				SUITE 400		
				8735 W. HIGGINS ROAD		

DATE: 2019\07\02

PLOT TIME: 5:32:50 PM

BAR IS ONE INCH ON ORIGINAL DRAWING.

2019/07/02


DPA-4652

12 of 26

G-205

FILENAME: 4652-G-205-CSPP.dgn

CONSTRUCTION -∕ BARRICADE **SECTION**



⁻6" TO 12" WIDE STRIPES AT 45° ANGLE **ELEVATION**

1) LOW-PROFILE BARRICADE DETAIL

DATE

PROJ

DWG

SHEET

FENCING NOTES:

- 1. PROPOSED WORK WILL REQUIRE THE OPENING OF THE AOA FENCE LINE. THE CONTRACTOR WILL BE REQUIRED AT HIS EXPENSE TO RESTORE THE INTEGRITY OF THE AOA FENCE LINE AT THE COMPLETION OF DAILY WORK ACTIVITIES TO THE SATISFACTION OF THE RESIDENT ENGINEER. TEMPORARY FENCE MAY BE REQUIRED AND CONSIDERED A TEMPORARY SECURITY MEASURE FOR THE AOA, THE COST OF THE TEMPORARY FENCE WILL BE INCIDENTAL.
- 2. EXISTING 6' SECURITY FENCING, POSTS, AND FOUNDATIONS SHALL BE REMOVED ALONG THE LOCATION OF THE PROPOSED 8' FENCE WITH 3-STRANDS OF BARBED WIRE, WILDLIFE DETERRENT FENCE BARRIER AND 4' VEGETATION FREE ZONE. EXISTING 6' FABRIC MAY BE REUSED AS WILDLIFE FENCE FABRIC. SEE SHEET C-503, DETAIL 3.
- 3. FOR WILDLIFE DETERRENT CONCRETE PAD SEE SHEET C-502, DETAIL 5.
- 4. THE CONTRACTOR SHALL COMPLETE A THOROUGH UTILITY LOCATE PRIOR TO COMMENCING WITH CONSTRUCTION. THE CONTRACTOR SHALL IDENTIFY TYPE, HORIZONTAL LAYOUT, AND VERTICAL DEPTH OF ALL UTILITIES PRIOR TO COMMENCING CONSTRUCTION. ANY UTILITY LINE OR STRUCTURE TO REMAIN THAT IS DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE, AT NO ADDITIONAL COST TO THE OWNER.
- 5. PRIOR TO FABRICATION AND CONSTRUCTION, THE CONTRACTOR SHALL FIELD VERIFY EXISTING GATE LENGTH, TYPE AND LOCATION. PROPOSED GATE LOCATIONS TO BE COORDINATED WITH RESIDENT ENGINEER.
- 6. ALL SIGNAGE MOUNTED ON EXISTING FENCING AND GATES SHALL BE SALVAGED AND PLACED IN THE SAME LOCATION ON THE NEW FENCE LINE. SALVAGING OF EXISTING SIGNAGE AND INSTALLATION ON NEW FENCING IS INCIDENTAL TO ITEM AR162508.
- 7. ALL EXISTING CATCH BASINS ALONG FENCE ALIGNMENT ARE TO BE PROTECTED. ANY DAMAGE BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- 8. WORK AREA ASSOCIATED WITH FENCING CONSTRUCTION WILL BE RESTORED TO THE SATISFACTION OF THE RESIDENT ENGINEER. RESTORATION MAY REQUIRE GRADING, TOPSOIL, SEEDING AND REMOVAL OF EXISTING GRINDINGS WITH COSTS INCIDENTAL TO THE REMOVAL.
- 9. 2' OF CA-6 SHALL BE PLACED ON EITHER SIDE OF THE PROPOSED FENCE LINE. THE CA-6 SHALL BE 6" DEEP. SEE SHEET C-503.
- 10. CONTRACTOR SHALL INSTALL NEW GATE TO PROVIDE A COMPLETE WORKING UNIT. THE GATE WORK SHALL INCLUDE THE GATE AND ALL OTHER ELEMENTS REQUIRED FOR A FULLY FUNCTIONAL GATE. THE EXISTING POWER SOURCE AND GATE OPERATOR ARE TO BE USED FOR THE NEW GATE.
- 11. NEW GATES TO BE INSTALLED WITH 4" CLEAR ABOVE GRADE WHEREVER POSSIBLE. EXISTING GATES TO BE ADJUSTED TO 4" CLEAR ABOVE GRADE WHEREVER POSSIBLE.
- 12. SEE GENERAL NOTES, SHEET G-102, FOR ADDITIONAL REQUIREMENTS.
- 13. CONTRACTOR TO REMOVE, STORE AND RE AFFIX GATE DESIGNATION PLACARDS TO NEW GATES.
- 14. ALL EXISTING SECURITY GATES WITHIN PROJECT LIMITS TO HAVE 3 STRAND BARBED WIRE ADDED TO FENCE. 3 STRAND BARBED WIRE FOR EXISTING GATES WILL BE PAID PER LINEAR FOOT LIKE THE 3 STRAND BARBED WIRE TO BE ADDED TO EXISTING FENCE. FOR NEW GATES THE BARBED WIRE IS INCLUDED IN THE GATE PRICE.
- 15. CONTRACTOR TO FIELD VERIFY EXISTING GATE DIMENSIONS PRIOR TO COMPLETION AND SUBMISSION OF SHOP DRAWINGS. ALL GATES WILL BE PAID UNDER THE LINE ITEMS IDENTIFIED IN THE GATE SCHEDULE.

EXISTING GATE	PROPOSED GATE		GATE SCHEDULE		
DESIGNATION	DESIGNATION	PROPOSED TYPE	CLEAR OPENING	PAY ITEM(S)	WORK DESCRIPTION
V1	V1	EXISTING	EXISTING	-	REMAIN IN PLACE
M3	M3	EXISTING	EXISTING	AR162948	REMAIN IN PLACE, ADJUST
P3	P3	EXISTING	EXISTING	=	REMAIN IN PLACE
V5	V5	EXISTING	EXISTING	AR162948	REMAIN IN PLACE, ADJUST
P5	P5	EXISTING	EXISTING	-	REMAIN IN PLACE
P26	P26	EXISTING	EXISTING	-	REMAIN IN PLACE
V23	V23	EXISTING	EXISTING	AR162948	REMAIN IN PLACE, ADJUST
P23	P23	EXISTING	EXISTING	-	REMAIN IN PLACE
V25	V25	EXISTING	EXISTING	-	REMAIN IN PLACE
P25	P25	EXISTING	EXISTING	-	REMAIN IN PLACE
M47	-		-	AR162910	REMOVE
V49	V49	EXISTING	EXISTING	-	REMAIN IN PLACE
M51	M51	EXISTING	EXISTING	-	REMAIN IN PLACE
V59	V59	EXISTING	EXISTING	-	REMAIN IN PLACE
P58	P58	EXISTING	EXISTING	-	REMAIN IN PLACE
P56	P56	EXISTING	EXISTING	-	REMAIN IN PLACE
V71	V71	EXISTING	EXISTING	-	REMAIN IN PLACE
V75	V75	EXISTING	EXISTING	AR162948	REMAIN IN PLACE, ADJUST
V77	V77	EXISTING	EXISTING	AR162948	REMAIN IN PLACE, ADJUST
P80	P80	EXISTING	EXISTING	-	REMAIN IN PLACE
P81	P81	EXISTING	EXISTING	-	REMAIN IN PLACE
V83	V83	EXISTING	EXISTING	-	REMAIN IN PLACE
P83	P83	EXISTING	EXISTING	-	REMAIN IN PLACE
V85	V85	EXISTING	EXISTING	-	REMAIN IN PLACE
P85	P85	EXISTING	EXISTING	-	REMAIN IN PLACE
V87	V87	EXISTING	EXISTING	AR162948	REMAIN IN PLACE, ADJUST
P87	P87	EXISTING	EXISTING	-	REMAIN IN PLACE
M89	M89	EXISTING	EXISTING	-	REMAIN IN PLACE
P89	P89	EXISTING	EXISTING	-	REMAIN IN PLACE
M91		-	-	AR162910	REMOVE
V92	V92	EXISTING	EXISTING	<u> </u>	REMAIN IN PLACE
M93	_	_	<u>-</u>	AR162910	REMOVE
V93	V93	EXISTING (COMBINATION)	10-FT (SWING) 20-FT (SLIDE)	AR162908, AR162910, AR162610, AR162720	REMOVE AND REPLACE
V95	V95	EXISTING (COMBINATION)	10-FT (SWING) 20-FT (SLIDE)	AR162908, AR162910, AR162610, AR162720	REMOVE AND REPLACE
M97	M97	EXISTING (SWING-MANUAL)	16-FT	AR162910, AR162616	REMOVE AND REPLACE
V99	V99	EXISTING (CANTALIVER SLIDE)	25-FT	AR162908, AR162725	REMOVE AND REPLACE
V100	V100	EXISTING (CANTALIVER SLIDE)	22-FT	AR162908, AR162722	REMOVE AND REPLACE
P100	P100	EXISTING PED	5-FT	AR162905, AR162531	REMOVE AND REPLACE
V101	V101	EXISTING (CANTALIVER SLIDE)	30-FT	AR162908, AR162730	REMOVE AND REPLACE
P101	P101	EXISTING PED	4-FT	AR162905, AR162531	REMOVE AND REPLACE
V102	V102	EXISTING (COMBINATION)	14-FT (SWING) 16-FT (SLIDE)	AR162908, AR162910, AR162614, AR162716	REMOVE AND REPLACE
P102	P102	EXISTING PED	4-FT	AR162905, AR162531	REMOVE AND REPLACE
M103	M103	EXISTING (CANTALIVER SLIDE-MANUAL)	20-FT	AR162920, AR162220	REMOVE AND REPLACE
P103	P103	EXISTING PED	4-FT	AR162905, AR162531	REMOVE AND REPLACE
V104	V104	EXISTING (CANTALIVER SLIDE)	20-FT	AR162908, AR162720	REMOVE AND REPLACE
5404	D404	EVICTING DED	4 FT	AD40000E AD400E04	DEMOVE AND DEDLACE

NOTE: SEE SHEETS C-301 THRU C-304 FOR PLAN VIEW DETAILS.


P104


EXISTING PED


Ch2M :	8735 W. HIGGINS ROAD SUITE 400 CHICAGO, IL 60631					
FENCING NOTES AND GATE SCHEDULE	PHASE III- UPGRADE WILDLIFE HAZARD FENCING ON NORTHERN AIRPORT BOUNDARY	1 2019/07/02 NO. DATE		CONSTRUCTION PLANS REVISION	TL BY	MT APVD
 	WEST CHICAGO, IL		DR	CHK	APVD	


AR162905, AR162531


REMOVE AND REPLACE
























ROLL FORMED SECTION OF BRACE


3½ (89)

TERMINAL POST		
Section	lbs./ft. (kg/m)	
Pipe 3.0 (76.2) O.D.	3.65 (5.43)	
Roll Formed 3½x3½ (89.0x89.0)	See detail	
Sq. Tubing 2½x2½ (63.5x63.5)	4.32 (6.43)	0.1345 (3.5) THICK -


METHOD OF FASTENING STRETCHER BAR TO POST

METHOD OF TYING FABRIC TO TENSION WIRES CONCRETE





OUTSIDE AIRFIELD (LANDSIDE)	INSIDE AIRFIELD (AIRSIDE)
ON COMPACTED GRADE WITH	FIELD VERIFY WIDTH OF GATE 3'-0" 1'-0" 1'-0" TOOLED EDGE CONCRETE FOOTING BEYOND



NOTE: 1. CONTRACTOR SHALL GRADE AND COMPACT ALL EXISTING BASES TO THE SATISFACTION OF THE ENGINEER PRIOR TO CONCRETE PLACEMENET. (INCIDENTAL TO THE CONTRACT).

5 TYPICAL WILDLIFE DETERRENT

CONCRETE PAD AT GATES

FOOTING FOR LINE POST

FOOTING FOR GATE & TERMINAL POST

1. TOP OF FOOTING SHALL HAVE NEAT EDGES. OVERFLOW OR MUSHROOMED TOPS WILL BE REJECTED.

6 FOOTING DETAILS

GATE FRAMES - SEE ITEM 162 IN PROJECT SPECIAL PROVISIONS FOR DETAILS

4 ROLL FORMED SECTION OF TERMINAL AND GATE POST

	GATE	POSTS *			
Gate Open	ing * ft. (m)	Pipe	Sq. Tı	ubing	
Single	Double	Size (O.D.)	lbs./ft. (kg/m)	Size	lbs./ft. (kg/m)
Up to 6 (1.8)	Up to 12 (3.7)	3.0 (76.2)	4.64 (6.91)	3 (76.2)	5.78 (8.60)
Over 6 (1.8) to 12 (3.7)	Over 12 (3.7) to 25 (7.6)	4.0 (101.6)	6.56 (9.77)	3 (76.2)	8.80 (13.10)

* The $3\frac{1}{2}$ x $3\frac{1}{2}$ (89.0 x 89.0) roll formed section as detailed may be used as gate posts for single gate up to 6' (1.8 m) and double gate up to 12' (3.6 m).

GENERAL NOTES

1. CONSTRUCTION METHOD AND MATERIALS SHOULD BE PER PROJECT SPECIAL PROVISIONS. INFORMATION SHOWN IN PLAN DETAILS TO BE SUPERCEDED BY PROJECT SPECIAL PROVISIONS WHEN IN CONFLICT.

2. ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

NTS **VERIFY SCALE** BAR IS ONE INCH ON ORIGINAL DRAWING. 2019/07/02 PROJ DPA-4652

C-502

19 of 26

Ch2m;

DUPAGE AIRPORT AUTHORITY

CHK MF ME IAL SERVICE, IS THE PR HORIZATION OF CH2M.

FILENAME: 4652-C-502-FENC.dgn


DATE: 2019\07\02

PLOT TIME: 5:37:32 PM


WHEN FENCE LINE HAS A CHANGE IN DIRECTION OF 15° OR MORE, A TERMINAL POST SHALL BE PLACED AS SHOWN ABOVE.

WHERE ANGLE IS LESS THAN 15° AND EXISTING CONDITIONS REQUIRE A TERMINAL POST, THEY SHALL BE PLACED AS DIRECTED BY THE RESIDENT ENGINEER.

1 INSTALLATION AT CORNERS



PROPOSED 8-FT FENCE DETAIL WITH WILDLIFE DETERRENT BARRIER AND 3-STAND BARBED WIRE





(3B) EXISTING 8-FT FENCE DETAIL
WITH WILDLIFE DETERRENT BARRIER AND 3-STAND BARBED WIRE

GENERAL NOTES

1. CONSTRUCTION METHOD AND MATERIALS SHOULD BE PER PROJECT SPECIAL PROVISIONS. INFORMATION SHOWN IN PLAN DETAILS TO BE SUPERCEDED BY PROJECT SPECIAL PROVISIONS WHEN IN CONFLICT.


2. ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.





TYPICAL FENCE DETAILS AND SECTIONS

В




STANDARD GROUND

COUNTERPOISE GROUND (ALTERNATE)

2 PROTECTIVE ELECTRICAL GROUNDS

NOTES:

- 1. MAINTAIN SECURITY FENCE INTEGRITY AT ALL TIMES. DO NOT LEAVE EXCAVATIONS UNDER FENCE FABRIC WHICH WOULD PERMIT ACCESS.
- 2. DEPTH OF EXCAVATION WILL BE INSPECTED AND APPROVED BY THE RESIDENT ENGINEER PRIOR TO PLACEMENT OF THE CHAIN LINK WILDLIFE DETERRENT FENCE BARRIER.
- 3. END JOINTS BETWEEN ADJACENT SECTIONS OF WIRE FABRIC MUST BE LAPPED A MINIMUM OF 4" AND TIED WITH GALVANIZED WIRE TIES AT 2'-0" O.C. AND AT EDGES.
- 4. CONTRACTOR MAY REUSE UNDAMAGED EXISTING 6' CHAIN LINK FABRIC AS WILDLIFE DETERRENT BARRIER FABRIC.
- 5. QUANTIFIED LIMITS OF RESTORATION INCLUDING SEEDING AND MULCHING THE CONTRACTOR SHALL ADHARE TO THE RESTORATION LIMITS. ANY WORK COMPLETED BEYOND THE IDENTIFIED RESTORATION LIMITS WILL NOT BE PAID FOR UNDER THIS CONTRACT UNLESS APPROVED BY THE RESIDENT ENGINEER. ALL OTHER WORK ELEMENTS ASSOCIATED WITH THE RESTORATION INCLUDING EXCAVATION AND TOPSOIL PLACEMENT ARE INCIDENTAL TO THE CONTRACT.
- 6. VERTICAL WILDLIFE DETERRENT BARRIER FABRIC IS TO BE PLACED ONLY IN LIMITED ACCESS AREAS SUCH AS ADJACENT SIDEWALKS, CURBS, CONCRETE PADS, UTILITY CONFLICTS WHERE ANGLED WILDLIFE DETERRENT BARRIER MAY NOT BE USED DUE TO OBSTRUCTION, AS IDENTIFIED IN THE PLANS OR APPROVED BY THE RESIDENT ENGINEER. RESTORATION OF THE SITE TO MATCH EXISTING IN THESE AREAS IS INCIDENTAL TO THE CONTRACT.
- 7. ANGLE ARMS FOR EXISTING FENCE TO BE INSTALLED ON EXISTING LINE POSTS UNLESS OTHERWISE APPROVED BY THE RESIDENT ENGINEER. EXTENSIONS ON GATES FOR ADDITION OF 3-STAND BARBED WIRE TO BE FIELD WELDED USING A KIT AS APPROVED BY THE RESIDENT ENGINEER. ANY DAMAGE TO EXISTING FENCE DUE TO INSTALLATION TO BE REPAIRED TO THE SATISFACTION OF THE RESIDENT ENGINEER.




SPECIAL CASE SECTIONS
SEE NOTE 6.

Ch2M :	8735 W. HIGGINS ROAD SUITE 400 CHICAGO, IL 60631					
FENCE DETAILS 3	PHASE III- UPGRADE WILDLIFE HAZARD FENCING ON NORTHERN AIRPORT BOUNDARY	3 1 2019/07/02		CONSTRUCTION PLANS		7
	DUPAGE AIRPORT (DPA)	NO. DATE		REVISION		BY APVD
	WEST CHICAGO, IL	DSGN TL	DR TL	CHK	APVD	Σ ⊢

DUPAGE AIRPORT AUTHORITY

DATE 2019/07/02
PROJ DPA-4652
DWG C-503
SHEET 20 of 26



THIS PLAN HAS BEEN PREPARED TO COMPLY WITH IEPA'S GENERAL NPDES PERMIT NO. ILR10 FOR STORMWATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

SITE DESCRIPTION

THE FOLLOWING IS A DESCRIPTION OF THE NATURE OF THE CONSTRUCTION ACTIVITY OR DEMOLITION WHICH IS THE SUBJECT OF THIS PLAN:

THE PROPOSED PROJECT INVOLVES UPGRADING EXISTING SECURITY FENCING ALONG THE NORTHERN BOUNDARY OF THE AIRPORT. THE PROPOSAL INVOLVES REMOVING EXISTING 6-FOOT HIGH FENCING AND REPLACING WITH AN 8-FOOT HIGH FENCE WITH BARBED WIRE (3-STRANDS), 4-FOOT ANGLED WILDLIFE DETERRENT BARRIER AND 4-FOOT-WIDE VEGETATION-FREE ZONE. IN AREAS WHERE THE EXISTING FENCING IS ALREADY 8-FEET-HIGH, THE WORK WILL INVOLVE INSTALLATION OF BARBED WIRE (3-STRANDS) ON TOP OF FENCE, ANGLED WILDLIFE DETERRENT BARRIER AND 4-FOOT-WIDE VEGETATION FREE ZONE (WHERE APPLICABLE) ONLY.

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOIL ON MAJOR PORTIONS OF THE CONSTRUCTION SITE. THE CONSTRUCTION ACTIVITIES MAY BE AS FOLLOWS: (GRUBBING, CLEARING, EXCAVATION, GRADING, BUILDING INFRASTRUCTURE, ETC.).

- 1. EROSION CONTROL
- 2. FENCE REMOVAL
- 3. FENCE INSTALLATION
- 4. INSTALLATION OF WILDLIFE DETERRENT BARRIER
- 5. SITE RESTORATION
- 6. SEEDING AND MULCHING

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 1.0 ACRES. THE TOTAL AREA OF THE SITE THAT IS ESTIMATED TO BE DISTURBED BY EXCAVATION, GRADING OR OTHER ACTIVITIES IS 1.6 ACRES. THE ESTIMATED RUNOFF COEFFICIENT OF THE SITE WILL BE .40 AFTER CONSTRUCTION ACTIVITIES ARE COMPLETED. THE EXISTING SOIL IS DETAILED IN THE SOIL BORING SHEETS WITHIN THE CONTRACT DOCUMENTS.

THE RECEIVING WATER BODY FOR THIS PROJECT IS KRESS CREEK.

THE AERIAL EXTENT OF WETLAND ACREAGE AT THE SITE IS 0.00 ACRE.

CONTROLS:

THIS SECTION OF THE PLAN ADDRESSES THE VARIOUS CONTROLS THAT MUST BE IMPLEMENTED FOR EACH OF THE MAJOR CONSTRUCTION ACTIVITIES DESCRIBED ABOVE. FOR EACH MEASURE DISCUSSED, THE CONTRACTOR WILL BE RESPONSIBLE FOR ITS IMPLEMENTATION AS INDICATED. EACH SUCH CONTRACTOR HAS SIGNED THE REQUIRED CERTIFICATION ON FORMS WHICH ARE ATTACHED TO, AND ARE A PART OF THIS PLAN. THE EROSION CONTROL PLAN DRAWINGS INCLUDED DEFINE THE SIZE AND LOCATION OF THE MEASURES TO BE INSTALLED DURING THE CONSTRUCTION OF THIS PROJECT. UNLESS OTHERWISE SPECIFIED IN THE ILLINOIS URBAN MANUAL, THE STORM WATER POLLUTION PREVENTION PLAN MUST BE DESIGNED FOR A STORM EVENT EQUAL TO OR GREATER THAN A 25-YEAR 24 HOUR RAINSTORM EVENT.

AT A MINIMUM, SITE EROSION AND SEDIMENT CONTROLS AND OVERALL SITE MANAGEMENT

- * CONTROL STORM WATER VOLUME WITHIN THE SITE TO MINIMIZE SOIL EROSION;
- * CONTROL STORM WATER DISCHARGES, INCLUDING BOTH PEAK FLOW RATES AND TOTAL STORM WATER VOLUME, TO MINIMIZE EROSION AT OUTLETS AND TO MINIMIZE DOWNSTREAM CHANNEL AND STREAM BANK EROSION;
- * MINIMZE THE AMOUNT OF SOIL EXPOSED DURING CONSRUCTION ACTIVITY;
- * MINIMIZE THE DISTURBANCE OF STEEP SLOPES;
- * MINIMIZE SEDIMENT DISCHARGES FROM THE SITE:
- * ADDRESS FACTORS SUCH AS THE AMOUNT, FREQUENCY, INTENSITY, AND DURATION OF PRECIPITATION, THE NATURE OF RESULTING STORM WATER RUNOFF, AND SOIL CHARACTERISTICS, INCLUDING THE RANGE OF SOIL PARTICLE SIZES EXPECTED TO BE PRESENT ON SITE:
- * PROVIDE AND MAINTAIN NATURAL BUFFERS AROUND SURFACE WATERS, DIRECT STORM WATER TO VEGETATED AREAS TO INCREASE SEDIMENT REMOVAL AND MAXIMIZE STORM WATER INFILTRATION (UNLESS INFEASIBLE);
- * MINIMZE SOIL COMPACTION AND UNLESS INFEASIBLE, PRESERVE TOPSOIL.

EROSION AND SEDIMENT CONTROLS

STABILIZATION PRACTICES: THE FOLLOWING INTERIM AND PERMANENT STABILIZATION PRACTICES, AS A MINIMUM, MUST BE IMPLEMENTED TO STABILIZE THE DISTURBED AREA OF THE SITE:

- MULCHING
- PERMANENT SEEDING

INTERIM AND PERMANENT STABILIZATION PRACTICES, INCLUDING SITE-SPECIFIC SCHEDULING OF THE IMPLEMENTATION OF THE PRACTICES ARE INCLUDED IN THIS STORMWATER POLLUTION PREVENTION PLAN. SITE PLANS MUST ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES MAY INCLUDE: TEMPORARY STABILIZATION WITH STRAW MULCH, TEMPORARY PRESERVATION OF EXISTING VEGETATION, AND OTHER APPROPRIATE MEASURES. THE SURFACE OF STRIPPED AREAS MUST BE PERMANENTLY OR TEMPORARILY PROTECTED FROM SOIL EROSION WITHIN 7 DAYS AFTER FINAL GRADING IS REACHED. TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES MUST BE MAINTAINED CONTINUOUSLY UNTIL PERMANENT COVER IS ESTABLISHED. ANY OPEN DITCH OR SWALE MUST BE STABILIZED 24 HOURS AFTER REACHING FINAL GRADE AND BEFORE CONCENTRATED FLOWS ARE DIVERTED TO THOSE DITCHES. NO PART OF THE DITCH OR SWALE MUST BE LEFT UNSTABLE FOR MORE THAN 7 DAYS.

STABILIZATION PRACTICES - IMPLEMENTATION REQUIREMENTS

• STABILIZATION OF DISTURBED AREAS MUST, AT A MINIMUM, BE INITIATED IMMEDIATELY WHENEVER ANY CLEARING, GRADING, EXCAVATING, OR OTHER EARTH DISTURBING ACTIVITIES HAVE PERMANENTLY CEASED ON ANY PORTION OF THE SITE AND WILL NOT RESUME FOR A PERIOD EXCEEDING 14 CALENDAR DAYS.

STABILIZATION PRACTICES - IMPLEMENTATION REQUIREMENTS (CONTINUED)

• STABILIZATION OF DISTURBED AREAS MUST BE INITIATED WITHIN 1 WORKING DAY OF PERMANENT OR TEMPORARY CESSATION OF EARTH DISTURBING ACTIVITIES AND SHALL BE COMPLETED AS SOON AS POSSIBLE BUT NOT LATER THAN 14 DAYS FROM THE INITIATION OF STABILIZATION WORK IN AN AREA. EXCEPTIONS TO THESE TIME FRAMES ARE SPECIFIED AS FOLLOWS:

- WHERE THE INITIATION OF STABILIZATION MEASURES IS PRECLUDED BY SNOW COVER. STABILIZATION MEASURES SHALL BE INITIATED A SOON AS PRACTICABLE.
- ON AREAS WHERE CONSTRUCTION ACTIVITY CEASED AND WILL RESUME AFTER 14 DAYS, A TEMPORARY STABILIZATION METHOD CAN BE USED.
- TEMPORARY STABILIZATION WITH POLYMER, STRAW MULCH AT A RATE OF 2 TON/ACRE, OR TEMPORARY SEEDING MUST BE USED TO STABILIZE CONSTRUCTION AREAS WHERE CONSTRUCTION ACTIVITY IS HALTED FOR MORE THAN 14 DAYS. TEMPORARY STABILIZATION MUST BE INITIATED WITHIN 1 DAY OF PERMANENT OR TEMPORARY CESSATION OF EARTH DISTURBING ACTIVITIES. BOTH MULCH AND/OR TEMPORARY SEEDING MUST INCLUDE POLYMER IN ADDITION TO THE MIX.
- STOCKPILES TO REMAIN IN PLACE MORE THAN 3 DAYS MUST BE SURROUNDED WITH SILT FENCE AND "TRACK WALKED" UP AND DOWN THE SLOPE TO PREVENT FURTHER EROSION. STOCKPILES TO REMAIN UNDISTURBED MORE THAN 14 DAYS MUST RECEIVE TEMPORARY STABILIZATION. STOCKPILES OF SOIL MUST NOT BE LOCATED IN FLOODPLAINS, RIPARIAN AREAS (VEGETATIVE FLOODPLAINS), WETLANDS, AND WATER OF THE U.S.
- REMOVAL OF EXISTING VEGETATION /TOPSOIL AND GRADING ACTIVITIES MUST BE CONDUCTED IN A MANNER THAT LIMITS THE AMOUNT OF EXPOSED AREA AT ANY ONE TIME. WHEN GRADING IS FINAL, PERMANENT SITE STABILIZATION MUST BE COMPLETED USING PERMANENT SEEDING AND EROSION BLANKET ON SLOPES 4:1 OR STEEPER AND HYDROMULCH ON SLOPES FLATTER THAN 4:1.
- DUST CONTROL MUST BE ACCOMPLISHED USING WATERING TRUCKS.

STRUCTURAL PRACTICES: THE FOLLOWING STRUCTURAL PRACTICES, AS A MINIMUM, MUST BE IMPLEMENTED TO CONTROL SEDIMENT FROM THE DISTURBED AREAS ON SITE:

- PERIMETER EROSION BARRIER (SILT FENCE)
- STRAW WATTLE (DITCH PROTECTION)
- INLET PROTECTION

STRUCTURAL PRACTICES MUST BE IMPLEMENTED, TO THE DEGREE ATTAINABLE, TO DIVERT FLOWS FROM EXPOSED SOILS, STORE FLOWS OR OTHERWISE LIMIT RUNOFF AND THE DISCHARGE OF POLLUTANTS FROM EXPOSED AREA OF THE SITE. THE INSTALLATION OF THESE DEVICES MAY BE SUBJECT TO SECTION 404 OF THE CLEAN WATER ACT.

STRUCTURAL PRACTICES - IMPLEMENTATION REQUIREMENTS

- WATERS OF THE U.S. WITHIN OR ADJACENT TO THE PROJECT MUST BE PROTECTED WITH PERIMETER EROSION BARRIER.
- ALL STORM SEWER INLET STRUCTURES MUST BE PROTECTED WITH STORM SEWER INLET PROTECTION (I.E. INLET FILTERS) PER INLET PROTECTION DETAILS IN THE PLANS. ALTERNATE TYPES OF PROTECTION MAY BE SUBMITTED FOR REVIEW AND APPROVAL BY THE OWNER OR KDSWCD.
- TEMPORARY CONSTRUCTION ENTRANCES AND EXITS MUST BE CONSTRUCTED AT ALL LOCATIONS WHERE CONSTRUCTION TRAFFIC ENTERS OR LEAVES THE SITE. RUNOFF FROM HAUL ROADS MUST NOT DRAIN DIRECTLY TO WATERS OF THE U.S.

USE OF TREATMENT CHEMICALS:

IF POLYMERS, FLOCCULATES, OR OTHER TREATMENT CHEMICALS ARE USED AT THE SITE, THEIR USE MUST COMPLY WITH THE FOLLOWING MINIMUM REQUIREMENTS:

- SELECT APPROPRIATE TREATMENT CHEMICALS. CHEMICALS MUST BE SELECTED THAT ARE APPROPRIATELY SUITED TO THE TYPES OF SOILS LIKELY TO BE EXPOSED DURING CONSTRUCTION AND DISCHARGED TO LOCATIONS WHERE CHEMICALS WILL BE APPLIED, AND TO THE EXPECTED TURBIDITY, PH, AND FLOW RATE OF STORM WATER FLOWING INTO THE CHEMICAL TREATMENT SYSTEM OR AREA.
- MINIMIZE DISCHARGE RISK FROM STORED CHEMICALS. STORE ALL TREATMENT CHEMICALS IN LEAK-PROOF CONTAINERS THAT ARE KEPT UNDER STORM-RESISTANT COVER AND SURROUNDED BY SECONDARY CONTAINMENT STRUCTURES (E.G. SPILL BERMS, DECKS, SPILL CONTAINMENT PALLETS), OR PROVIDED EQUIVALENT MEASURES, DESIGNED AND MAINTAINED TO MINIMIZE THE POTENTIAL DISCHARGE OF TREATMENT CHEMICALS IN STORM WATER OR BY ANY OTHER MEANS (E.G. STORING CHEMICALS IN COVERED AREA OR HAVING A SPILL KIT AVAILABLE ON SITE).
- COMPLY WITH ILLINOIS URBAN MANUAL, 2012 POLYACRYLAMIDE PRACTICE STANDARDS

USE OF TREATMENT CHEMICALS (CONTINUED):

- TREATMENT CHEMICALS AND CHEMICAL TREATMENT SYSTEMS SHOULD BE USED IN ACCORDANCE WITH GOOD ENGINEERING PRACTICES, AND WITH DOSING SPECIFICATIONS AND SEDIMENT REMOVAL DESIGN SPECIFICATIONS PROVED BY THE PROVIDED/SUPPLIER OF THE APPLICABLE CHEMICALS, OR DOCUMENT SPECIFIC DEPARTURES FROM THESE PRACTICES OR SPECIFICATIONS AND HOW THEY REFLECT GOOD ENGINEERING PRACTICE.
- MAINTAIN ASSOCIATED MSDS ON SITE.
- ENSURE THAT ALL PERSONS WHO HANDLE AND USE TREATMENT CHEMICALS AT THE CONSTRUCTION SITE ARE PROVIDE WITH APPROPRIATE, PRODUCT-SPECIFIC TRAINING. THE TRAINING MUST COVER PROPER DOSING REQUIREMENTS.

BMPS - POST-CONSTRUCTION STORM WATER MANAGEMENT

PROVIDED BELOW IS A DESCRIPTION OF MEASURES THAT WILL BE INSTALLED DURING THE CONSTRUCTION PROCESS TO CONTROL THE POLLUTANTS IN STORM WATER DISCHARGES THAT WILL OCCUR AFTER THE CONSTRUCTION OPERATIONS HAVE BEEN COMPLETED. THE INSTALLATION OF THESE DEVICES MAY BE SUBJECT TO SECTION 404 OF THE CLEAN WATER ACT.

THE PRACTICES SELECTED FOR IMPLEMENTATION WERE DETERMINED ON THE BASIS OF THE TECHNICAL GUIDANCE CONTAINED IN THE ILLINOIS URBAN MANUAL, 2012 AND OTHER ORDINANCES LISTED IN THE SPECIFICATIONS. POST CONSTRUCTION STORM WATER CONTROL MEASURES SHALL INCLUDE:

• INFILTRATION OF ONSITE RUNOFF

VELOCITY DISSIPATION DEVICES MUST BE PLACED AT DISCHARGE LOCATIONS AND ALONG THE LENGTH OF ANY OUTFALL CHANNEL AS NECESSARY TO PROVIDE A NON-EROSIVE VELOCITY FLOW FROM THE STRUCTURE TO A WATER COURSE SO THAT THE NATURAL PHYSICAL AND BIOLOGICAL CHARACTERISTICS AND FUNCTIONS ARE MAINTAINED AND PROTECTED (I.E., MAINTENANCE OF HYDROLOGIC CONDITIONS, SUCH AS THE HYDROPERIOD AND HYDRODYNAMICS PRESENT PRIOR TO THE INITIATION OF CONSTRUCTION ACTIVITIES).

PROVIDE AN EXPLANATION OF THE TECHNICAL BASIS USED TO SELECT PRACTICES TO CONTROL POLLUTION PREVENTION WHERE POST-CONSTRUCTOIN FLOWS WILL EXCEED PREDEVELOPMENT LEVELS HERE:

 POST CONSTRUCTION FLOWS WILL NOT EXCEED PRE-DEVELOPMENT LEVELS. NO GRADE CHANGES BEING CONSTRUCTED AND FINAL SURFACE WILL MATCH EXISTING SURFACE.

OTHER CONTROLS

WASTE DISPOSAL: THE SOLID WASTE MATERIALS INCLUDING TRASH, CONSTRUCTION DEBRIS, EXCESS CONSTRUCTION MATERIALS, MACHINERY, TOOLS AND OTHER ITEMS MUST BE COLLECTED AND DISPOSED OFF-SITE BY THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR THE ACQUISITION OF THE NECESSARY DISPOSAL PERMITS. BURNING ON THE SITE WILL NOT BE PERMITTED. NO SOLID MATERIALS, INCLUDING BUILDING MATERIALS, MUST BE DISCHARGED INTO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

CONCRETE WASTE OR WASHOUT SHOULD NOT BE ALLOWED IN THE STREET OR ALLOWED TO REACH A STORM WATER DRAINAGE SYSTEM OR WATERCOURSE. CONCRETE WASHOUT SHOULD BE COMPLETED OFF SITE, OR IF ALLOWED ON SITE BY THE PRIMARY CONTACT, WASHOUT SHOULD BE CONTAINED AND COMPLETED IN A LOCATION DESIGNATED BY THE PRIMARY OR SECONDARY CONTACT.

ON SITE CONCRETE WASHOUT CONTAINMENT FACILITIES SHOULD BE OF SUFFICIENT VOLUME TO COMPLETELY CONTAIN ALL LIQUID AND CONCRETE WASTE MATERIALS INCLUDING ENOUGH CAPACITY FOR ANTICIPATED LEVELS OF RAINWATER. CONTAINMENT FACILITIES SHALL BE LINED WITH A 30-MIL IMPERMEABLE LINER. THE DRIED CONCRETE WASTE MATERIAL SHOULD BE PICKED UP AND DISPOSED OF PROPERLY WHEN TWO-THIRDS CAPACITY IS REACHED.

THE PROVISIONS OF THIS PLAN MUST ENSURE AND DEMONSTRATE COMPLIANCE WITH APPLICABLE STATE AND/OR LOCAL WASTE DISPOSAL, SANITARY SEWER OR SEPTIC SYSTEM REGULATIONS.

VEHICLE/EQUIPMENT STORAGE, MAINTENANCE, & WASHING:

WHENEVER POSSIBLE, VEHICLE AND EQUIPMENT MAINTENANCE AND WASHING SHOULD OCCUR OFF SITE AT APPROPRIATE AREAS. IF VEHICLE AND EQUIPMENT MAINTENANCE MUST OCCUR ON SITE, (INCLUDING BOTH ROUTINE MAINTENANCE) REPAIRS AND MAINTENANCE SHOULD BE MADE WITHIN A DESIGNATED CONTAINMENT AREA TO PREVENT THE MIGRATION OF MECHANICAL FLUIDS (OIL, ANTIFREEZE, ETC.) INTO WATERCOURSES, WETLANDS OR STORM DRAINS. DRIP PANS OR ABSORBENT PADS SHOULD BE USED FOR ALL VEHICLE AND EQUIPMENT MAINTENANCE ACTIVITIES THAT INVOLVE GREASE, OIL, SOLVENTS, OR OTHER VEHICLE FLUIDS. CONSTRUCTION VEHICLES SHOULD BE INSPECTED FREQUENTLY TO IDENTIFY ANY LEAKS; LEAKS SHOULD BE REPAIRED IMMEDIATELY OR THE VEHICLE SHOULD BE REMOVED FROM SITE. DISPOSE OF ALL USED OIL, ANTIFREEZE, SOLVENTS AND OTHER VEHICLE RELATED CHEMICALS IN ACCORDANCE WITH USEPA AND IEPA REGULATIONS AND PER MATERIAL SAFETY DATA SHEET (MSDS) AND/OR MANUFACTURER INSTRUCTIONS. CONTRACTORS SHOULD IMMEDIATELY REPORT SPILLS TO THE OWNER.

VEHICLE/EQUIPMENT WASH WATER SHOULD BE TREATED IN A SEDIMENT TRAP OR OTHER BMP THAT WILL PROVIDE EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE. BLOWERS OR VACUUMS SHOULD BE USED INSTEAD OF RINSE WATER TO REMOVE DRY MATERIALS FROM VEHICLES WHENEVER POSSIBLE. IF DETERGENTS ARE REQUIRED TO CLEAN VEHICLES OR EQUIPMENT, BIODEGRADABLE DETERGENTS AND WASH PRODUCTS FREE OF HALOGENATED SOLVENTS SHOULD BE USED. THE LOCATION OF WASH AREAS SHOULD BE DOCUMENTED ON THE SITE MAP, AND WORKERS SHOULD BE NOTIFIED OF THE WASH AREAS. DO NOT PERFORM OTHER ACTIVITIES, SUCH AS VEHICLE REPAIRS, IN A WASH AREA. WHEN NOT IN USE, VEHICLES UTILIZED ON SITE FOR CONSTRUCTION OPERATIONS SHOULD BE STORED IN A DESIGNATED AREA OUTSIDE OF THE REGULATORY FLOODPLAIN, AWAY FROM ANY NATURAL OR CREATED WATERCOURSE, POND, DRAINAGE-WAY OR STORM DRAIN.

JPA(WE

STORMWATER POLI
PREVENTION PLA

O

BAR IS ONE INCH ON ORIGINAL DRAWING.

1"

DATE 2019/07/02

PROJ DPA-4652

DWG CG-100

SHEET 22 of 26

MATERIAL STORAGE AND GOOD HOUSEKEEPING:

SOLID WASTE MATERIALS INCLUDING TRASH, CONSTRUCTION DEBRIS, EXCESS CONSTRUCTION MATERIALS, MACHINERY, TOOLS AND OTHER ITEMS WILL BE COLLECTED AND DISPOSED OF OFFSITE. THE TRADE/CONTRACTOR IS RESPONSIBLE TO ACQUIRE THE PERMIT REQUIRED FOR SUCH DISPOSAL. BURNING ON SITE WILL NOT BE PERMITTED. NO SOLID MATERIALS, INCLUDING BUILDING MATERIALS, SHALL BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT. ALL WASTE MATERIALS SHOULD BE COLLECTED AND STORED IN APPROVED RECEPTACLES. NO WASTES SHOULD BE PLACED IN ANY LOCATION OTHER THAN IN THE APPROVED CONTAINERS APPROPRIATE FOR THE MATERIALS BEING DISCARDED. THERE SHOULD BE NO LIQUID WASTES DEPOSITED INTO DUMPSTERS OR OTHER CONTAINERS WHICH MAY LEAK. RECEPTACLES WITH DEFICIENCIES SHOULD BE REPLACED AS SOON AS POSSIBLE AND THE APPROPRIATE CLEAN-UP PROCEDURE SHOULD TAKE PLACE, IF NECESSARY. CONSTRUCTION WASTE MATERIAL IS NOT TO BE BURIED ON SITE. WASTE DISPOSAL SHOULD COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS. CONTRACTORS SHOULD IMMEDIATELY REPORT ALL SPILLS TO THE PRIMARY CONTACT, WHO SHOULD NOTIFY THE APPROPRIATE AGENCIES, IF NEEDED.

THE FOLLOWING GOOD HOUSEKEEPING PRACTICES SHOULD BE FOLLOWED ON SITE DURING THE CONSTRUCTION PROJECT:

- * MINIMIZE THE EXPOSURE OF BUILDING MATERIALS, BUILDING PRODUCTS, CONSTRUCTION WASTE, TRASH, LANDSCAPE MATERIALS, FERTILIZERS, PESTICIDES, HERBICIDES, DETERGENTS, SANITARY WASTE AND OTHER MATERIALS ONSITE TO PRECIPITATION AND STORM WATER.
- * AN EFFORT SHOULD BE MADE TO STORE ONLY ENOUGH PRODUCT REQUIRED TO DO THE JOB.
- * ALL MATERIALS STORED ON SITE SHOULD BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND ADEQUATELY PROTECTED FROM THE ENVIRONMENT.
- * PRODUCTS SHOULD BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL.
- * SUBSTANCES SHOULD NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER.
- * OPERATIONS SHOULD BE OBSERVED AS NECESSARY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS ON SITE.
- * WHENEVER POSSIBLE, ALL OF A PRODUCT SHOULD BE USED UP BEFORE DISPOSING OF THE CONTAINER.
- * MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL SHOULD BE FOLLOWED.

FOR BUILDING PRODUCTS:

STORE IN DESIGNATED STORAGE AREAS AND PROVIDE EITHER A COVER (E.G., PLASTIC SHEETING OR TEMPORARY ROOFS) TO PREVENT THESE PRODUCTS FROM COMING INTO CONTACT WITH RAINWATER, OR A SIMILARLY EFFECTIVE MEANS DESIGNED TO PREVENT THE DISCHARGE OF POLLUTANTS FROM THESE AREAS.

FOR PESTICIDES, HERBICIDES, INSECTICIDES, FERTILIZERS, AND LANDSCAPE

STORE IN DESIGNATED STORAGE AREAS AND PROVIDE EITHER A COVER (E.G., PLASTIC SHEETING OR TEMPORARY ROOFS) TO PREVENT THESE CHEMICALS FROM COMING INTO CONTACT WITH RAINWATER, OR A SIMILARLY EFFECTIVE MEANS DESIGNED TO PREVENT THE DISCHARGE OF POLLUTANTS FROM THESE AREAS. PULTE MUST ALSO COMPLY WITH ALL APPLICATION AND DISPOSAL REQUIREMENTS INCLUDED ON THE REGISTERED PESTICIDE, HERBICIDE, INSECTICIDE. AND FERTILIZER LABEL.

FOR DIESEL FUEL, OIL, HYDRAULIC FLUIDS, OTHER PETROLEUM PRODUCTS, AND

OTHER CHEMICALS:
STORE CHEMICALS IN WATER-TIGHT CONTAINERS, AND PROVIDE EITHER A COVER
(E.G., PLASTIC SHEETING OR TEMPORARY ROOFS) TO PREVENT THESE CONTAINERS
FROM COMING INTO CONTACT WITH RAINWATER, OR A SIMILARLY EFFECTIVE MEANS
DESIGNED TO PREVENT THE DISCHARGE OF POLLUTANTS FROM THESE AREAS (E.G.,
SPILL KITS), OR PROVIDE SECONDARY CONTAINMENT (E.G., SPILL BERMS, DECKS, SPILL
CONTAINMENT PALLETS). SPILLS MUST BE CLEANED UP IMMEDIATELY, USING DRY CLEAN-UP
METHODS WHERE POSSIBLE. DO NOT CLEAN THE SURFACES OR SPILLS BY HOSING THE
AREA DOWN. ELIMINATE THE SOURCE OF THE SPILL TO PREVENT A DISCHARGE OR A
CONTINUATION OF AN ONGOING DISCHARGE.

APPROVED STATE OR LOCAL PLANS

THE MANAGEMENT PRACTICES, CONTROLS, AND OTHER PROVISIONS CONTAINED IN THIS PLAN ARE AT LEAST AS PROTECTIVE AS THE REQUIREMENTS CONTAINED IN THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY'S STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, MOST RECENT VERSION. ILLINOIS PROCEDURES AND STANDARDS FOR URBAN SOIL EROSION AND SEDIMENTATION PLAN THAT ARE APPLICABLE TO PROTECTING SURFACE WATER RESOURCES ARE, UPON SUBMITTAL OF A NOTICE OF INTENT TO BE AUTHORIZED TO DISCHARGE UNDER THIS PERMIT, INCORPORATED BY REFERENCE AND ARE ENFORCEABLE UNDER THIS PERMIT EVEN IF THEY ARE NOT SPECIFICALLY INCLUDED IN THE PLAN.

MAINTENANCE

VEGETATION, EROSION AND SEDIMENT CONTROL MEASURES AND OTHER PROTECTIVE MEASURES IDENTIFIED IN THIS PLAN MUST BE MAINTAINED IN GOOD AND EFFECTIVE OPERATING CONDITIONS.

FOR EACH SPECIFIC EROSION AND SEDIMENT CONTROL MEASURE, MAINTENANCE AND INSPECTION, CONTRACTOR MUST REFER TO THE ILLINOIS URBAN MANUAL STANDARD PRACTICE.

INSPECTIONS

THE OWNER AND CONTRACTOR MUST PROVIDE QUALIFIED PERSONNEL TO INSPECT DISTURBED AREAS OF THE CONSTRUCTION SITE WHICH HAVE NOT BEEN FINALLY STABILIZED, STRUCTURAL CONTROL MEASURES, DISCHARGE POINTS, AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE. SUCH INSPECTIONS MUST BE CONDUCTED AT LEAST ONCE EVERY 7 DAYS AND WITHIN 24 HOURS OF THE END OF A STORM, OR BY THE END OF THE FOLLOWING BUSINESS OR WORK DAY, THAT IS 0.5 INCHES OR GREATER. INSPECTIONS MAY BE REDUCED TO ONCE PER MONTH WHEN CONSTRUCTION ACTIVITIES HAVE CEASED DUE TO FROZEN CONDITIONS. INSPECTIONS MUST COMMENCE WHEN CONSTRUCTION ACTIVITIES ARE CONDUCTED, OR IF THERE IS A 0.5 INCHES OR GREATER RAIN EVENT, OR DISCHARGE DUE TO SNOWMELT OCCURS.

DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION MUST BE INSPECTED FOR EVIDENCE OF OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN MUST BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY MUST BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATERS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE MUST BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING.

AT THE DISCRETION OF THE OWNER, KDSWCD, OR UNITED STATES ARMY CORPS OF ENGINEERS (USACE), VIOLATIONS FOUND DURING INSPECTIONS MUST BE CORRECTED WITHIN SEVEN (7) DAYS IF MINOR, THREE (3) DAYS IF MODERATE, AND IMMEDIATELY IF SEVERE.

THE CONTRACTOR MUST PREPARE REPORT SUMMARIZING THE SCOPE OF THE INSPECTION, NAME(S) AND QUALIFICATIONS OF PERSONNEL MAKING THE INSPECTION, THE DATE(S) OF THE INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THIS STORMWATER POLLUTION PREVENTION PLAN, AND ACTIONS TAKEN. THE REPORT MUST BE MADE AND RETAINED AS PART OF THE PLAN FOR AT LEAST THREE (3) YEARS AFTER THE DATE OF THE INSPECTION. THE REPORT MUST BE SIGNED IN ACCORDANCE WITH PART VI.G OF THE ILR10 GENERAL PERMIT.

IF ANY VIOLATION OF THE PROVISIONS OF THIS PLAN IS IDENTIFIED DURING THE CONDUCT OF THE CONSTRUCTION WORK COVERED BY THIS PLAN, THE RESIDENT ENGINEER OR OWNER'S REPRESENTATIVE MUST NOTIFY THE APPROPRIATE AGENCY FIELD OPERATIONS OFFICE OF THE IEPA BY EMAIL, TELEPHONE OR FAX WITHIN 24 HOURS OF ANY INCIDENCE OF NON-COMPLIANCE (ION) OR FOR VIOLATIONS OF ANY CONDITION OF THE PERMIT. ADDITIONALLY, THE OWNER'S REPRESENTATIVE MUST FILE WITHIN 5 DAYS, FORMS PROVIDED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY AND WILL INCLUDE SPECIFIC INFORMATION ON THE CAUSE OF NONCOMPLIANCE, ACTIONS WHICH WERE TAKEN TO PREVENT FURTHER CAUSES OF NONCOMPLIANCE, AND A STATEMENT DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE NONCOMPLIANCE. ALL REPORTS OF NONCOMPLIANCE MUST BE SIGNED BY A RESPONSIBLE AUTHORITY IN ACCORDANCE WITH PART VI.G OF THE GENERAL PERMIT. THE REPORT OF NONCOMPLIANCE MUST BE MAILED TO THE FOLLOWING ADDRESS:

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL ATTN: COMPLIANCE ASSURANCE SECTION 1021 NORTH GRAND AVENUE EAST POST OFFICE BOX 19276 SPRINGFIELD, IL 62794-9276

NON-STORMWATER DISCHARGES

THE FOLLOWING NON-STORM WATER DISCHARGES MAY BE AUTHORIZED PROVIDED THE NON-STORM WATER COMPONENT OF THE DISCHARGES IS IN COMPLIANCE WITH PART IV.D.5 OF THE ILR10 PERMIT:

- DISCHARGES FROM FIREFIGHTING ACTIVITES
- FIRE HYDRANT FLUSHING
- WATERS USED TO WASH VEHICLES WHERE DETERGENTS ARE NOT USED
- WATERS USED TO CONTROL DUST
 POTABLE WATER SOURCES INCLUDING UNCONTAMINATED WATERLINE FLUSHINGS
- LANDSCAPE IRRIGATION DITCHES
- PAVEMENT WASHWATERS WHERE SPILLS OR LEAKS
 OF TOXIC OR HAZARDOUS MATERIALS MAY HAVE NOT OCCURRED
 (UNLESS ALL MATERIAL HAS BEEN REMOVED) AND DETERGENTS
 ARE NOT USED
- UNCONTAMINATED GROUND WATER

THE FOLLOWING NON-STORM WATER DISCHARGES ARE PROHIBITED:

- CONCRETE AND WASTEWATER FROM WASHOUT OF CONCRETE (UNLESS MANAGED BY
- AN APPROPRIATE CONTROL)

 DRYWALL COMPOUND
- WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO AND PAINT
 FORM RELEASE OILS
- FORM RELEASE OILS
 CURING COMPOUNDS
- CONSTRUCTION MATERIALS, FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE
- SOAPS, SOLVENTS, OR DETERGENTS
- TOXIC OR HAZARDOUS SUBSTANCES FROM A SPILL OR OTHER RELEASE
 OR ANY OTHER POLLUTANT THAT COULD CAUSE OR TEND TO CAUSE WATER POLLUTION

THE PLAN MUST IDENTIFY AND ENSURE THE IMPLEMENTATION OF APPROPRIATE POLLUTION PREVENTION AND EROSION AND SEDIMENT CONTROL MEASURES FOR THE NON-STORMWATER COMPONENTS OF THE DISCHARGE.

DURING DEWATERING OPERATIONS, WATER MUST BE PUMPED INTO FILTER BAGS, SEDIMENT TRAPS OR SILT TRAPS. FILTERED WATER MUST BE DISCHARGED ONTO STABILIZED SURFACE TO PREVENT ADDITIONAL EROSION AND SEDIMENTATION.

	8735 W. HIGGINS ROAD							
	SUITE 400							
	CHICAGO, IL 60631							
	PHASE III- UPGRADE WILDLIFE HAZARD FENCING							
	ON NORTHERN AIRPORT BOUNDARY	_	2019/07/02	Ö	CONSTRUCTION PLANS		7	M
PREVENTION PLAN 2	DUPAGE AIRPORT (DPA)	Ö	DATE		REVISION		BY APVD	δ
	WEST CHICAGO, IL	DSGN		DR TL	CHK	APVD	Ψ⊢	

AIRPOF HORITY

PROJ

SHEET

DATE: 2019\07\02

BAR IS ONE INCH ON ORIGINAL DRAWING.

2019/07/0

23 of 26

DPA-4652 CG-10

	CONTROL MEASURE GROUP	X APPLICABLE	KEY	CONTROL MEASURE	CONTROL MEASURE CHARACTERISTICS	TEMPORARY	PERMANENT
		A		AGGREGATE COVER	PROVIDES SOIL COVER ON ROADS AND PARKING LOTS AND AREAS WHERE VEGETATION CANNOT BE ESTABLISHED. PREVENTS MUD FROM BEING PICKED UP AND TRANSPORTED OFF-SITE.	Х	х
			EB	EROSION BLANKET	PROTECTS THE SOIL SURFACE FROM RAINDROP IMPACTS AND OVERLAND FLOW DURING THE ESTABLISHMENT OF VEGETATION. REDUCES SOIL MOISTURE LOSS DUE TO EVAPORATION.	X	X
	NON- VEGETATIVE SOIL		GT	GEO-TEXILE FABRIC	A PERMEABLE GEOSYNTHETIC FABRIC USED TO ENHANCE WATER MOVEMENT AND RETARD SOIL MOVEMENT; AND AS A BLANKET TO ADD REINFORCEMENT AND SEPARATION	X	X
	COVER	X	M	MULCHING	ADDED INSURANCE OF A SUCCESSFUL TEMPORARY OR PERMANENT SEEDING. CONTROLS UNWANTED VEGETATION AND PRESERVES MOISTURE. PROVIDES COVER WHERE VEGETATION CANNOT BE ESTABLISHED.	Х	Х
CONTRO			P	PAVING	PROVIDES PERMANENT COVER ON PARKING LOTS AND ROADS OR OTHER AREAS WHERE VEGETATION CANNOT BE ESTABLISHED.	_	Х
8			PM	POLYMER (POWDERED FORM)	A WATER SOLUBLE POLYACRYLAMIDE (PAM) IN POWDER FORM, USED FOR EROSION CONTROL WHEN BROADCASTED ON DISTURBED SOIL.	X	-
<u>N</u>	OUTLETS		LA	LINED APRON	PROTECTS DOWNSTREAM CHANNELS AND FLAT AREAS FROM HIGH VELOCITY OF FLOW DISCHARGING FROM STRUCTURES.	Х	Х
EROSION			DS	DORMANT SEEDING	SAME AS PERMANENT SEEDING EXCEPT IS DONE DURING DORMANT SEASON. HIGHER RATES OF SEED APPLICATION ARE REQUIRED.	X	X
Ш		X	PS	PERMANENT SEEDING	PROVIDES PERMANENT VEGETATIVE COVER TO CONTROL EROSION, FILTERS SEDIMENT FROM WATER. MAY BE PART OF FINAL LANDSCAPE PLAN.	-	Х
	VEGETATIVE SOIL		PTS	PLANTS, TREES, & SHRUBS	PROVIDES GROUND COVER, SHRUBS AND TREES IN ADDITION TO PERMANENT VEGETATION. MAY BE USED AS PART OF A FINAL LANDSCAPE PLAN ALONG WITH SHRUBS AND TREES.	-	Х
	COVER		SO	SODDING	QUICK PERMANENT COVER TO CONTROL EROSION. QUICK WAY TO ESTABLISH VEGETATION FILTER STRIP. CAN BE USED ON STEEP SLOPES OR IN DRAINAGEWAYS WHERE SEEDING MAY BE DIFFICULT.	Х	X
			(TS)	TEMPORARY SEEDING	PROVIDES QUICK TEMPORARY COVER TO CONTROL EROSION WHEN PERMANENT SEEDING IS NOT DESIRED OR TIME OF YEAR IS INAPPROPRIATE.	X	<u> </u> -
			(VF)	VEGETATIVE FILTER	USED ALONG DRAINAGEWAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. SIZE MUST BE INCREASED IN PROPORTION TO DRAINAGE AREA.	X	X
			JN	JUTE NETTING	A NATURAL FIBER MESH USED FOR EROSION AND SEDIMENT CONTROL. MAY BE USED IN COMBINATION WITH POLYMERS AND FLOC LOGS TO REMOVE SUSPENDED SEDIMENT FROM STORM WATER.	Х	<u>-</u>
	DEWATERING		(FL)	POLYMER (FLOC LOG FORM)	A WATER SOLUBLE POLYACRYLAMIDE (PAM) USED IN FLOWING CONDITIONS TO REMOVE SUSPENDED SEDIMENT FROM STORM WATER.	X	<u> </u>
	DEWATERING		PM	POLYMER (POWDERED FORM)	A WATER SOLUBLE POLYACRYLAMIDE (PAM) IN POWDER FORM, USED IN CONJUNCTION WITH FLOC LOGS AND JUTE IN FLOWING CONDITIONS, TO REMOVE SUSPENDED SEDIMENT.	Х	-
			SP	SUMP PIT AND FILTER BAG	TEMPORARY PRACTICE TO REMOVE EXCESSIVE WATER FROM EXCAVATION WITH IMPROVED WATER QUALITY AND WITHOUT SEDIMENT	Х	_
7			(IPA)	ABOVE GROUND INLET PROTECTION	TEMPORARY PRACTICE TO CONTROL SEDIMENT AT STORM DRAIN INLET FOR INSIDE DISTURBED DRAINAGE AREAS.	X	-
CONTROL	INLET PROTECTION	X	(IPB)	BELOW GROUND INLET PROTECTION (INLET BASKET)	TEMPORARY PRACTICE TO CONTROL SEDIMENT AT STORM DRAIN INLET FOR ALL CONCRETE AND PAVED SURFACES.	Х	-
			(IPC)	CULVERT INLET PROTECTION - STONE	TEMPORARY PRACTICE TO CONTROL SEDIMENT AT CULVERT INLETS.	Х	-
SEDIMENT			(RS)	CONSTRUCTION ROAD STABILIZATION	STABILIZATION OF TEMPORARY CONSTRUCTION ACCESS ROUTES TO REDUCE EROSION OF TEMPORARY ROADBEDS AND PARKING AREAS.	Х	-
ED	MUD & DUST CONTROL	X	(DT)	DUST AND TRAFFIC CONTROL	PREVENTS DUST FROM LEAVING CONSTRUCTION SITE.	Х	Х
ഗ			(SE)	STABILIZED CONST. ENTRANCE	PREVENT MUD FROM BEING PICKED UP AND CARRIED OFF-SITE.	X	Х
	PERIMETER CONTROL	X	(SF)	SILT FENCE	USED FOR SINGLE LOTS OR DRAINAGE AREAS LESS THAN 1/2 ACRE TO CONTROL SEDIMENT FROM RUNOFF.	X	-
	TEMPORARY SEDIMENT		xs	EXCAVATED SEDIMENT BASIN	A TEMPORARY PONDING BASIN, WITH OUTLET STRUCTURE, FORMED BY CONSTRUCTION OF AN EMBANKMENT OR EXCAVATED BASIN TO TEMPORARILY DETAIN SEDIMENT-LADEN RUNOFF FROM LARGER DISTURBED AREAS. USED	Х	-
	BASINS/ TRAPS		ST	TEMPORARY SEDIMENT TRAPS	WHEN DRAINAGE AREA IS GREATER THAN 5 ACRES. A TEMPORARY PONDING BASIN FORMED BY CONSTRUCTION OF AN EMBANKMENT OR EXCAVATED BASIN TO TEMPORARILY DETAIN SEDIMENT-LADEN RUNOFF FROM SMALL. DISTURBED AREAS. USED WHEN DRAINAGE AREA IS LESS THAN 5 ACRES.	X	-
			(CD)	CHANNEL DIVERSION	TYPICALLY USED AT TOP OR BASE OF SLOPES. USED WHEN EXCESS SOIL IS NOT AVAILABLE.	X	Х
	DIVERSIONS		(RD)	RIDGE DIVERSION	TYPICALLY USED ABOVE SLOPES. USED WHERE AN EXCESS OF SOIL IS AVAILABLE.	X	X
ROL			(SD)	TEMPORARY SLOPE DRAIN	A TUBING OR CONDUIT TO CONVEY CONCENTRATED RUNOFF DOWN A SLOPE WITHOUT CAUSING EROSION ON OR BELOW THE SLOPE.	X	-
CONTROL			(GC)	GEOSYNTHETIC CHECK STRUCTURE	TEMPORARY PRACTICE TO REDUCE VELOCITY AND TRAP SEDIMENT.	X	-
RUNOFF C	CHECK DAMS		RC	ROCK CHECK DAM - COARSE AGGREGATE	A ROCK DAM CONSTRUCTED ACROSS A SWALE OR DITCH TO REDUCE THE VELOCITY OF CONCENTRATED STORM WATER FLOWS. TO BE USED WHEN EACH DAM HAS A DRAINAGE AREA OF LESS THAN 2 ACRES.	Х	-
RU	DITCH CHECKS		RR	ROCK CHECK DAM - RIP RAP	A ROCK DAM CONSTRUCTED ACROSS A SWALE OR DITCH TO REDUCE THE VELOCITY OF CONCENTRATED STORM WATER FLOWS. TO BE USED WHEN EACH DAM HAS A DRAINAGE AREA OF LESS THAN 10 ACRES.	Х	_
			SL	SEDIMENT LOG	TEMPORARY PRACTICE TO REDUCE VELOCITY AND TRAP SEDIMENT	Х	
	ENOLOGES		(SS)	STORM SEWER	CAN BE USED TO CONVEY SEDIMENT LADEN WATER TO SEDIMENT BASIN OR IN CONJUNCTION WITH A WATERWAY.	Х	X
	ENCLOSED DRAINAGE			UNDERDRAIN	USED TO LOWER WATER TABLE AND INTERCEPT GROUNDWATER FOR BETTER VEGETATION GROWTH AND SLOPE STABILITY. USED TO CARRY BASE FLOW IN WATERWAYS AND TO DEWATER SEDIMENT BASINS.	Х	Х
<u>S</u>	OTHER		(CW)	TEMPORARY CONCRETE WASHOUT	A DEVICE USED TO MANAGE LIQUID AND SOLID WASTES FROM CONCRETE USAGE ON CONSTRUCTION SITES.	Х	
SCELLANEOUS	UINEK	X	ТО	TOPSOILING	METHODS OF PRESERVING AND USING TOPSOIL TO PROVIDE A SUITABLE GROWTH MEDUIM FOR SITE STABILIZATION WITH VEGETATION.	Х	Х
-LAN			LC	LINED CHANNEL	USED WHEN VEGETATION WILL NOT PROTECT THE CHANNEL AGAINST HIGH VELOCITIES OF FLOW OR WHERE VEGETATION CANNOT BE ESTABLISHED.	Х	X
CEI			(SSS)	STRUCTURAL STREAMBANK STABILIZATION - RIPRAP/GABIONS	PROTECTS STREAMBANKS FROM EROSIVE FORCE OF FLOWING WATER	-	Х
ഗ) AVA TEDIAVA VO		(cc)	TEMPORARY CREEK CROSSING	A TEMPORARY STRUCTURE INSTALLED ACROSS A WATERCOURSE TO ALLOW CONSTRUCTION VEHICLES TO CROSS WITHOUT CAUSING SEDIMENTATION, STREAMBED DAMAGE, OR FLOODING.	X	-
MIS	WATERWAYS					_	-
	WATERWAYS		(vc)	VEGETATIVE CHANNEL	PROVIDED ADDED STABILITY TO CHANNEL. USED WHEN VELOCITY OF FLOW IS NOT EXTREMELY FAST.	Х	Х

INSPECTION AND	MAINTENANCE	SCHEDIIIE
INOPECTION AND	/ IVIAIIN I EINAINGE	

ACTIVITY	RESPONSIBLE PARTY	DURATION
STABILIZATION DURING CONSTRUCTION MAINTENANCE	CONTRACTOR	AT LEAST ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A RAIN EVENT, OR BY THE END OF THE FOLLOWING BUSINESS OR WORK DAY, THAT IS 0.5 INCHES OR GREATER.
STABILIZATION DURING CONSTRUCTION-OBSERVATION	CONTRACTOR	AT LEAST ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A RAIN EVENT, OR BY THE END OF THE FOLLOWING BUSINESS OR WORK DAY, THAT IS 0.5 INCHES OR GREATER.
VEGETATION MAINTENANCE	CONTRACTOR	COMPLETION OF CONTRACT
VEGETATION AND STABILIZATION MAINTENANCE	OWNER	ONGOING AFTER CONSTRUCTION COMPLETION

PROPOSED WORK SCHEDULE

MOBILIZATION / IMPLEMENT EROSION CONTROL	DESCRIPTION OF CONSTRUCTION ACTIVITIES	FINAL STABILIZATION
10 DAYS	57 DAYS	5 DAYS

SOIL PROTECTION SCHEDULE

STABILIZATION TYPE	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
TEMPORARY SEEDING												
EROSION BLANKET / HYDROMULCH												
MULCH												
POLYMERS	*											

* OR UNTIL GROUND FREEZES FOR PURPOSES OF THIS NOTE, SWPPP INCLUDES:

1. ALL SOIL EROSION AND SEDIMENT CONTROL PLAN SHEETS AND DETAIL
2. GRADING PLANS
COPY OF THE SWPPP
4. UTILITY PLANS SHOWING DRAINAGE AND STORM SEWER SYSTEMS
5. ILR10 NPDES INSPECTION REPORTS
6. ASSOCIATED SPECIFICATIONS

NOTE:
CONTRACTOR MUST RETAIN A SIGNED
AND APPROVED COPY OF THE SWPPP
ON THE JOB SITE AT ALL TIMES.

WPPP OPERATOR CERTIFICATION STATEMENT
CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM
ESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS
HO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF
RUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND
IPRISONMENT FOR KNOWING VIOLATIONS."
SIGNATURE TITLE
COMPANY

COM.	TRACT	OR CE	RTIFI	CATIO

"I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT ILR10 THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION."

	TERRO THAT AGTHORIZED THE GTORIAL WATER BIOCHAROLO AGGOGIATED WITH INDOCTRIAL AGTIVITY TROIN THE GOACHAGOTION	
ERAL ACTOR	SIGNATURE	TITLE
GENERAL CONTRACTOR	COMPANY	DATE
⊕ ~		
WITNESSED BY OWNER	SIGNATURE	TITLE
	COMPANY	DATE
TOR		
SUB-CONTRACTOR	SIGNATURE	TITLE
SUB-C	COMPANY DESCRIPTION OF THE POP	DATE
	RESPONSIBLE FOR	

STORMWATER POLLUTION
PREVENTION PLAN 3

SUITE 400
CHICAGO, IL 60631

PHASE III- UPGRADE WILDLIFE HAZARD FENCING
ON NORTHERN AIRPORT BOUNDARY
1
NO.
DUPAGE AIRPORT (DPA)
NEST CHICAGO, IL
NO.
DUPAGE AIRPORT (DPA)
DEGN

DPA-4652

CG-102

24 of 26

VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING.

SOIL EROSION CONTROL AND SEDIMENT CONTROL NOTES


- 1. THE CONTRACTOR SHALL CONTACT THE KANE-DUPAGE SOIL AND WATER CONSERVATION DISTRICT (KDSWCD), ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO LAND DISTURBING ACTIVITY, AS SOON AS THE INITIAL EROSION CONTROL ITEMS ARE INSTALLED AND ONE WEEK PRIOR TO FINAL INSPECTION.
- 2. THE OWNER IS REQUIRED TO SUBMIT A NOTICE OF INTENT (NOI) TO THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY (IEPA) FOR THE PROJECT. THE CONTRACTOR IS NOT PERMITTED TO BEGIN WORK UNTIL 30 DAYS FOLLOWING OWNER'S SUBMITTAL OF THE NOI
- 3. SOIL EROSION AND SEDIMENT CONTROL (SESC) FEATURES MUST BE CONSTRUCTED PRIOR TO THE COMMENCEMENT OF UPLAND DISTURBANCE. SOIL DISTURBANCE MUST BE PHASED OR ENACTED IN SUCH A MANNER AS TO MINIMIZE EROSION. SOIL STABILIZATION MEASURES MUST CONSIDER THE TIME OF YEAR, SITE CONDITIONS AND THE USE OF TEMPORARY AND/OR PERMANENT MEASURES. DISTURBANCE OF AREAS NOT INCLUDED IN THE DESIGN WILL REQUIRE NOTIFICATION OF THE KDSWCD IN ACCORDANCE WITH THE 404 PERMIT SPECIAL CONDITIONS.
- 4. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE INSTALLED AT MINIMUM ACCORDING TO THE STANDARDS AND SPECIFICATIONS IN THE ILLINOIS URBAN MANUAL, REVISED TO LATEST VERSION AS AMENDED. A COPY OF THE APPROVED STORMWATER POLLUTION PREVENTION PLAN MUST BE MAINTAINED ON THE SITE AT ALL TIMES.
- 5. THE EROSION CONTROL SHOWN ON THE PLANS ARE THE MINIMUM REQUIREMENTS. ADDITIONAL MEASURES MAY BE REQUIRED AS DIRECTED BY THE OWNER'S REPRESENTATIVE, THE KDSWCD, OR USACE. ALL ADDITIONAL MEASURES MUST BE IN PLACE WITHIN 3 DAYS OF DISTURBANCE AND ANY EMERGENCY SESC MEASURES MUST BE INSTALLED IMMEDIATELY AT THE DISCRETION OF KDSWCD. OR USACE.
- 6. PRIOR TO COMMENCING LAND-DISTURBING ACTIVITIES OTHER THAN THOSE INDICATED ON THE PLANS (INCLUDING BUT NOT LIMITED TO ADDITIONAL PHASES OF THE DEVELOPMENT AND OFF-SITE BORROW OR WASTE AREAS), A SUPPLEMENTAL EROSION CONTROL PLAN MUST BE SUBMITTED TO THE OWNER FOR REVIEW BY KDSWCD. THE CONTRACTOR BASED ON THE CONSTRUCTION SCHEDULE WEEKLY MEETING, WILL MODIFY STORM WATER POLLUTION PREVENTION PLAN IF NECESSARY. DEPENDING ON MODIFICATION TO THE WORK SCHEDULE, THE CONTRACTOR MUST SUBMIT DRAWINGS TO THE KDSWCD FOR REVIEW.
- 7. THE CONTRACTOR MUST CLEAN UP, GRADE THE WORK AREA AS THE PROJECT PROGRESSES, AND INSTALL EROSION PROTECTION TO ELIMINATE THE CONCENTRATION OF RUNOFF, OR MUST INSTALL APPROPRIATE SEDIMENT CONTROL DEVICES TO TRAP SEDIMENT. PAVEMENT MUST BE CLEANED DAILY OR AS NECESSARY TO REMOVE EARTHEN MATERIAL TO THE SATISFACTION OF THE OWNER, KDSWCD.
- 8. ALL CONTROL MEASURES NECESSARY TO MEET THE REQUIREMENTS OF THE DUPAGE COUNTY COUNTYWIDE STORMWATER AND FLOOD PLAIN ORDINANCE OR THE WAIVER COMMUNITY ORDINANCE MUST BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SEDIMENT AND EROSION CONTROL MEASURES ARE OPERATIONAL.
- 9. THE CONTRACTOR AND SUBCONTRACTORS MUST SUBMIT A WRITTEN AND SIGNED (BY CONTRACTOR) STORM WATER POLLUTION PREVENTION PLAN (SWPPP), MEETING THE REQUIREMENTS OF THE IEPA'S CURRENT NPDES STORM WATER PERMIT FOR CONSTRUCTION SITE ACTIVITIES, INCLUDING DETAILS OF SPECIFIC DEVICES SUCH AS SILT FENCE, DITCH CHECK, ETC. TO BE UTILIZED FOR EROSION AND SEDIMENT CONTROL. THE PLAN MUST BE SUBMITTED AND APPROVED BY THE OWNER A MINIMUM OF TEN (10) DAYS PRIOR TO INITIATION OF CONSTRUCTION ACTIVITIES. A COPY OF THE APPROVED SWPPP MUST BE GIVEN TO THE OWNER'S REPRESENTATIVE FIVE DAYS PRIOR TO THE START OF CONSTRUCTION ACTIVITIES.
- 10. THE CONTRACTOR AND OWNER MUST MAKE INSPECTIONS A MINIMUM OF ONCE EVERY SEVEN DAYS OF THE FOLLOWING:
 1) DISTURBED AREAS OF THE PROJECT SITE THAT HAVE NOT BEEN FULLY STABILIZED, 2) STRUCTURAL CONTROL MEASURES (SILT FENCES, ETC.), AND 3) LOCATIONS WHERE VEHICLES ENTER AND EXIT THE SITE. AN ADDITIONAL INSPECTION OF THE ITEMS LISTED ABOVE MUST BE MADE WITHIN TWENTY-FOUR (24) HOURS OF A 0.5-INCH OR GREATER RAINFALL OR EQUIVALENT SNOWFALL.
- 11. THE CONTRACTOR AND OWNER MUST KEEP A WRITTEN REPORT SUMMARIZING THE REQUIRED INSPECTION EACH TIME AN INSPECTION TAKES PLACE. THE REPORTS MUST BE KEPT AT THE SITE DURING CONSTRUCTION. THE REPORTS MUST ALSO BE RETAINED FOR THREE YEARS FROM THE DATE THE SITE IS FINALLY STABILIZED.
- 12. THE OWNER'S REPRESENTATIVE MUST NOTIFY THE APPROPRIATE AGENCY FIELD OPERATIONS OFFICE OF THE IEPA BY EMAIL, TELEPHONE OR FAX WITHIN 24 HOURS OF ANY INCIDENCE OF NONCOMPLIANCE AND MUST FILL OUT AND FILE WITHIN FIVE (5) DAYS WITH THE EPA AN INCIDENCE OF NONCOMPLIANCE (ION) FORM WHEN REQUIRED BY THE PERMIT.
- 13. THE CONTRACTOR MUST COOPERATE WITH THE OWNER'S REPRESENTATIVES WHO WILL MAKE SITE VISITS TO REVIEW COMPLIANCE WITH THE PLAN IN THE FIELD AND AUDIT THE LOGS AND RECORDS REQUIRED BY THE PERMIT.
- 14. THE INSTALLATION, MAINTENANCE, REMOVAL AND RESTORATION OF THE AREA DISTURBED BY THE PLACEMENT OF THE PERIMETER EROSION BARRIER ARE INCLUDED IN THE CONTRACT UNIT PRICE FOR PERIMETER EROSION BARRIER. AFTER ALL PERIMETER EROSION BARRIER IS REMOVED, THE AREAS DAMAGED BY THE PERIMETER EROSION BARRIER MUST BE RESTORED.
- 15. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO FILTER BAGS, SEDIMENT TRAPS, SILT TRAPS, OR POLYMER TREATMENT CHANNELS. FILTERED WATER SHOULD BE DISCHARGED ONTO STABILIZED SURFACE TO PREVENT ADDITIONAL EROSION AND/OR SEDIMENTATION. DEWATERING DIRECTLY INTO FIELD TILES, STORM WATER STRUCTURES, OR "WATERS OF THE U.S." IS PROHIBITED.
- 16. THE CONTRACTOR MUST CONSULT WITH A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC) FOR THE DESIGN AND MAINTENANCE OF SEDIMENTATION BASINS WITH BAFFLE SYSTEM AND TRAPS AS WELL AS POLYMERS AND FLOC LOGS. IF REQUIRED.
- 17. ALL STORM SEWER INLET STRUCTURES MUST BE PROTECTED WITH STORM SEWER INLET PROTECTION (I.E. INLET FILTERS) PER INLET PROTECTION DETAILS IN THE PLANS. ALTERNATE TYPES OF PROTECTION MAY BE SUBMITTED FOR REVIEW AND APPROVAL BY THE OWNER OR KDSWCD.
- 18. THE CONTRACTOR MUST MAINTAIN AND PRESERVE ANY EXISTING SUB-SURFACE DRAINAGE SYSTEMS (I.E. FIELD TILES) ACCORDING TO THE RELEVANT DESIGN AND CONSTRUCTION STANDARDS.
- 19. CONSTRUCTION ACTIVITIES MUST BE SCHEDULED TO MINIMIZE THE TIME SOIL IS EXPOSED AND UNPROTECTED. IN NO CASE WILL THE EXISTING VEGETATION BE DESTROYED, REMOVED, OR DISTURBED MORE THAN FOURTEEN (14) DAYS PRIOR TO THE INITIATION OF IMPROVEMENTS.
- 20. TEMPORARY CONSTRUCTION ENTRANCES WILL BE CONSTRUCTED AT ALL LOCATIONS WHERE CONSTRUCTION TRAFFIC ENTERS OR LEAVES THE SITE VIA EXISTING HARD SURFACES. CONTRACTOR TO DETERMINE APPROPRIATE LOCATIONS BASED ON HAULING AND STAGING PLAN.
- 21. GRAVELED ROADS, ACCESS DRIVES, PARKING AREAS OF SUFFICIENT WIDTH AND LENGTH, AND VEHICLE WASH DOWN FACILITIES IF NECESSARY, MUST BE PROVIDED TO PREVENT THE DEPOSIT OF SOIL FROM BEING TRACKED ONTO PUBLIC OR PRIVATE ROADWAYS ANY SOIL REACHING PUBLIC OR PRIVATE ROADWAY MUST BE REMOVED IMMEDIATELY.
- 22. STOCK PILES OF SOIL MUST NOT BE LOCATED IN FLOOD PLAINS, RIPARIAN AREAS (VEGETATED FLOOD PLAINS), WETLANDS AND WATERS OF THE U.S. UNLESS OTHERWISE AUTHORIZED BY THE RELEVANT PERMITTING AUTHORITY. IF A STOCKPILE IS TO REMAIN IN PLACE FOR MORE THAN THREE DAYS, PERIMETER EROSION BARRIER MUST BE PROVIDED. IF THE STOCKPILE IS INACTIVE FOR MORE THAN 14 DAYS, SOIL STABILIZATION MUST BE PROVIDED BY THE 7TH DAY AFTER ACTIVITY HAS STOPPED.
- 23. WHEN FILLING A WETLAND ADJACENT TO A W.U.S., EROSION CONTROL MEASURES MUST BE IN PLACE SO THAT WHEN FILL MATERIAL IS PLACED, OVERLAND FLOW IS NOT ALLOWED TO ACCUMULATE SEDIMENT AND ENTER WATERS OF THE U.S.
- 24. IF THE VOLUME, VELOCITY, SEDIMENT LOAD, OR PEAK FLOW RATE OF STORMWATER RUNOFF ARE TEMPORARILY INCREASED DURING CONSTRUCTION, THEN PROPERTIES AND SPECIAL MANAGEMENT AREAS DOWNSTREAM FROM SUCH DEVELOPMENT SITES MUST BE PROTECTED FROM EROSION.


- 25. WHEN THE CONSTRUCTION IS COMPLETED, THE SITE HAS BEEN FULLY STABILIZED AND ALL DISCHARGES OF STORMWATER AUTHORIZED BY THE PERMIT HAVE BEEN ELIMINATED, THE CONTRACTOR MUST PROVIDE A LETTER TO THE OWNER OR OWNER'S REPRESENTATIVE STATING THESE FACTS.
- 26. AFTER THE SITE HAS BEEN PERMANENTLY STABILIZED AND ANY/ALL STORMWATER DISCHARGES, AUTHORIZED UNDER THE ILR10 PERMIT ARE ELIMINATED, THE OWNER WILL SUBMIT A COMPLETED NOTICE OF TERMINATION (NOT) SIGNED IN ACCORDANCE WITH PART VI.G (SIGNATORY REQUIREMENTS) OF THE ILR10 PERMIT TO IEPA.
- 27. NO SILT FENCE TO BE INSTALLED WITHIN OBJECT FREE AREAS OF ACTIVE TAXIWAYS OR RUNWAYS.
- 28. EXISTING EROSION CONTROL MEASURES IN PLACE AT THE BEGINNING ON THIS CONTRACT DONE BY OTHERS SHALL BE MAINTAINED IN AREAS NOT DISTURBED BY THE PROPOSED WORK WITHIN THESE DOCUMENTS. FOR LOCATIONS AND DESCRIPTIONS OF PREVIOUS EROSION CONTROL MEASURES DONE BY OTHERS, SEE EXISTING EROSION CONTROL SHEETS.
- 29. LOCATIONS OF SEDIMENT LOGS SHOWN ON THESE PLANS ARE APPROXIMATE. EXACT LOCATIONS SHALL BE DETERMINED IN THE FIELD, BASED ON ACTUAL CONDITIONS. SEDIMENT LOGS SHALL BE INSTALLED TO ENCIRCLE ALL PROPOSED OPEN-GRATE DRAINAGE STRUCTURES UNTIL GROUND HAS BEEN STABILIZED. LOGS SHALL BE INSTALLED AT MAXIMUM 100' SPACING WITHIN ALL DITCHES OR OTHER AREAS OF CONCENTRATED FLOW, OR AS DIRECTED BY THE KDSWCD.
- 30. TEMPORARY SOIL STOCKPILE EMBANKMENT SLOPES SHALL NOT EXCEED 10 FEET IN HEIGHT WITHOUT THE PLACEMENT OF SLOPE STABILIZATION, SUCH AS TEMPORARY SEEDING OR SLOPE POLYMER EROSION CONTROL.
- 31. RESTORE ALL PROPOSED UTILITY TRENCHES NOT SHOWN WITHIN THE LIMITS OF THESE EROSION CONTROL PLANS WITH PERMANENT SEEDING OR AS DIRECTED BY THE OWNER.
- 32. CONTRACTOR SHALL INSTALL PERIMETER EROSION BARRIER AT ANY LOCATION IN WHICH SHEET FLOWS MAY RESULT IN SEDIMENT RUNOFF OUTSIDE THE LIMITS OF CONSTRUCTION ACTIVITIES. LOCATIONS SHOWN ON THESE PLANS ARE SUGGESTED. ACTUAL LOCATIONS TO BE DETERMINED IN THE FIELD BY THE ENGINEER BASED ON FIELD CONDITIONS.

ST35 W. HIGGINS ROAD SUITE 400 CHICAGO, IL 60631 CHICAGO,	1 2019/07/02 CONSTRUCTION PLANS NO. DATE REVISION DSGN TL TL TL THE CHK MF APVD TN	8735 W. HIGGINS ROAD SUITE 400 CHICAGO, IL 60631 ANO. ANO. DATE ANO. DATE ANO. DATE ANO. DATE ANO.
1 2019/07/02 CONSTRUCTION PLANS NO. DATE REVISION DSGN TL CHK MF	SUITE 400 CHICAGO, IL 60631 PHASE III- UPGRADE WILDLIFE HAZARD FENCING ON NORTHERN AIRPORT BOUNDARY DUPAGE AIRPORT (DPA) WEST CHICAGO, IL DSGN TL CHICAGO CHI	STORMWATER POLLUTION PLAN 4 PREVENTION PLAN 4 POLITION PLAN 5 P
1 2019/07/02 NO. DATE DSGN TL TL	SUITE 400 CHICAGO, IL 60631 DIATE	STORMWATER POLLUTION PREVENTION PLAN 4 PREVENTION PLAN 4 PREVENTION PLAN 4 PHASE III- UPGRADE WILDLIFE HAZARD FENCING ON NORTHERN AIRPORT (DPA) WEST CHICAGO, IL 60631 TO 12019/07/02 TO 12019/07/07 TO 12019/07 TO 12019/07 TO 12019/07 TO 12019/07
NO. DSGN	8735 W. HIGGINS ROAD SUITE 400 CHICAGO, IL 60631 PHASE III- UPGRADE WILDLIFE HAZARD FENCING ON NORTHERN AIRPORT BOUNDARY 1 DUPAGE AIRPORT (DPA) NO. DUPAGE AIRPORT (DPA) DSGN	STORMWATER POLLUTION PREVENTION PLAN 4 B735 W. HIGGINS ROAD SUITE 400 CHICAGO, IL 60631
NO.	8735 W. HIGGINS ROAD SUITE 400 CHICAGO, IL 60631 PHASE III- UPGRADE WILDLIFE HAZARD FENCING ON NORTHERN AIRPORT BOUNDARY 1 DUPAGE AIRPORT (DPA) NO. DUPAGE AIRPORT (DPA) DSGN	STORMWATER POLLUTION PREVENTION PLAN 4 B735 W. HIGGINS ROAD SUITE 400 CHICAGO, IL 60631
8735 W. HIGGINS ROAD SUITE 400 CHICAGO, IL 60631 PHASE III- UPGRADE WILDLIFE HAZARD FENCING ON NORTHERN AIRPORT BOUNDARY DUPAGE AIRPORT (DPA) WEST CHICAGO, IL		STORMWATER POLLUTION PREVENTION PLAN 4
	STORMWATER POLLUTION PREVENTION PLAN 4	VERIFY SCALE

DATE 2019/07/02
PROJ DPA-4652
DWG CG-103
SHEET 25 of 26

DATE: 2019\07\02






DIRECTION OF FLOW UNDISTURBED GROUND LINE COMPACTED BACKFILL FABRIC ANCHOR DETAIL

NOTES:

- 1. TEMPORARY SEDIMENT FENCE MUST BE INSTALLED PRIOR TO ANY GRADING WORK IN THE AREA TO BE PROTECTED. THEY MUST BE MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD AND REMOVED IN CONJUNCTION WITH THE FINAL GRADING AND SITE STABILIZATION.
- 2. FILTER FABRIC MUST MEET THE REQUIREMENTS OF MATERIAL SPECIFICATION P-629 GEOTEXTILE.
- 3. FENCE POSTS MUST BE EITHER STANDARD STEEL POST OR WOOD POST WITH A MINIMUM CROSS-SECTIONAL AREA OF 3.0 SQ. IN.



NOTES:

SECTION


1. PLACE THE END POST OF THE SECOND FENCE INSIDE THE END POST OF THE FIRST FENCE.

ATTACHING TWO SILT FENCES

2. ROTATE BOTH POSTS AT LEAST 180 DEGREES IN A CLOCKWISE DIRECTION TO CREATE A TIGHT SEAL WITH THE FABRIC MATERIAL.

3. DRIVE BOTH POSTS A MINIMUM OF 18 INCHES INTO THE GROUND AND BURY THE FLAP.





OR WIDTH "W" AND HEIGHT "H" OF FILTER FRAMES OR

ADDITIONAL INFORMATION

CASTING GRATES. REFER TO CASTING CROSS REFERENCE GUIDE FOR IDOT STANDARDS. SEE SPECIFICATIONS FOR



STORMWATER POLLUTION PREVENTION PLAN DETAILS VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING.

PROJ

DWG

2019/07/02

DPA-4652

26 of 26

CG-104