

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2007-003 I	WILL	44	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SPEC. ITEM	CODE NO.	ITEM	UNIT	** TOTAL QUANTITY	ROADWAY LIGHTING	
					Y026-3A	Y030-1E
*	81603190	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.4 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	150		150
*	81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	1300		1300
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1482		1482
*	81900300	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	534		534
*	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	13		13
*	83050760	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 8 FT. MAST ARM	EACH	5		5
*	83050880	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-8 FT. MAST ARMS	EACH	4		4
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	152		152
	X0300019	REMOVE AND REINSTALL PARKING BLOCKS	EACH	71	71	
*	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6		6
	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	3163	3163	
	X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	1120	1120	
	X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	3	3	
	X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	756	756	
	X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	756	756	
	X0696100	PARKING BLOCKS	EACH	150	150	
*	X8160395	UNIT DUCT, WITH 3-1/C NO. 2 AND 1/C NO. 4 GROUND, 600V (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE	FOOT	700		700
	XX000362	PAVEMENT REMOVAL AND BITUMINOUS REPLACEMENT, SPECIAL	SQ YD	14	14	
	XX001011	BICYCLE RACKS	EACH	6	6	
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	7803	7803	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
⊙	Z0076600	TRAINEES	HOUR	1000	1000	
	X0325800	PARKING LOT SEAL COAT	SQ YD	4572	4572	
	XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	9		9

NOTE:

ALL TYPE 3 SIGN PANELS REQUIRE TYPE ZZ SHEETING AND WILL BE 100% PAID FOR BY STATE FUNDS.

PLOT DATE = 05/15/07
 FILE NAME = S:\PROJECTS\2007\8262\8262.DWG
 PLOT SCALE = AS SHOWN
 USER NAME = USER*

- ⊙ Y080
- * SPECIALTY ITEMS
- ** URBAN, 80% FEDERAL, 20% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (U.S. 6 TO U.S. 30)
PARK AND RIDE LOTS

SUMMARY OF QUANTITIES II

SCALE: N.T.S. DRAWN BY JFS
DATE 05/15/07 CHECKED BY DDH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS