CONTRACT NO. 60C22

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 55 | 2007-003 I | WILL | 44 | 6 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

SIGN PANEL - TYPE 3 — TOTAL 396

| Station | Direction | "Mile Post Marker" | "Sign Description" | "Sign Description" | Width | Height | "NO. OF SIGNS" | Subtotals SQ FT |
|---|---|---|---|---|---|---|---|---|
| | | (Per Sign Log) | | | ft | ft | | |
| 60+00 | NB | 247.47 | "PARK & RIDE EXIT 248" | DETAIL | 9 | 11 | 1 | 99 |
| 148+96 | SB | 249.15 | "PARK & RIDE EXIT 248" | DETAIL | 9 | 11 | 1 | 99 |
| 300+78 | NB | 252.09 | "PARK & RIDE EXIT 253" | DETAIL | 9 | 11 | 1 | 99 |
| 375+98 | SB | 253.61 | "PARK & RIDE EXIT 25" | DETAIL | 9 | 11 | 1 | 99 |

SIGN PANEL - TYPE 1 — TOTAL 134

| LOCATION | SIGN DESCRIPTION | "SIGN DESCRIPTION" | WIDTH | HEIGHT | AREA | "NO. OF SIGNS" | SQ FT |
|---|---|---|---|---|---|---|---|
| | | (Per MUTCD) | FT | FT | SQ FT | | |
| U.S. 6 | RESERVED PARKING | R7-8 | 1 | 1.5 | 1.5 | 3 | 4.5 |
| U.S. 6 | $250 FINE | R7-I101 | 1 | 0.5 | 0.5 | 3 | 1.5 |
| U.S. 6 | "PARK & RIDE (left or right arrow)" | D4-2 | 2.5 | 3 | 7.5 | 8 | 60 |
| U.S. 6 | STOP | R1-1 | 2.5 | 2.5 | 5.2 | 1 | 5.2 |
| U.S.52 | RESERVED PARKING | R7-8 | 1 | 1.5 | 1.5 | 3 | 4.5 |
| U.S.52 | $250 FINE | R7-I101 | 1 | 0.5 | 0.5 | 3 | 1.5 |
| U.S.52 | "PARK & RIDE (left or right arrow)" | D4-2 | 2.5 | 3 | 7.5 | 7 | 52.5 |
| U.S. 30 | RESERVED PARKING | R7-8 | 1 | 1.5 | 1.5 | 2 | 3 |
| U.S. 30 | $250 FINE | R7-I101 | 1 | 0.5 | 0.5 | 2 | 1 |

STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY — TOTAL 3051

| Station | Direction | "Sign Description" | "Sign Description" | "Support Size" | "# of Supports" | "Estimated Length" | Conversion | Subtotals POUND |
|---|---|---|---|---|---|---|---|---|
| | | | | | | ft | lbs/ft | |
| 60+00 | NB | "EXIT 248 PARK & RIDE" | DETAIL | W8x18 | 2 | 44 | 18 | 792 |
| 148+96 | SB | "EXIT 248 PARK & RIDE" | DETAIL | W8x18 | 2 | 44 | 18 | 792 |
| 300+78 | NB | "EXIT 253 PARK & RIDE" | DETAIL | W8x18 | 2 | 46.5 | 18 | 837 |
| 375+98 | SB | "EXIT 253 PARK & RIDE" | DETAIL | W6x15 | 2 | 42 | 15 | 630 |

METAL POSTS — TOTAL 84

| LOCATION | LOCATION | "SIGN DESCRIPTON" | "SUPPORT LENGTH (ESTIMATE)" | "# OF SUPPORTS" | "# OF LOCATIONS" | | Subtotals FOOT |
|---|---|---|---|---|---|---|---|
| | | | FT | | | | |
| U.S. 6 | "PARKING LOT" | "RESERVED PARKING" | 9.58 | 1 | 3 | | 28.74 |
| | | $250 FINE | | | | | |
| | | STOP | 13.5 | 1 | 1 | | 13.5 |
| U.S. 52 | "PARKING LOT" | "RESERVED PARKING" | 9.58 | 1 | 2 | | 19.16 |
| | | $250 FINE | | | | | |
| U.S. 52 | "U.S. 52 MEDIAN" | "PARK & RIDE (left or right arrow)" | 13.5 | 1 | 1 | | 13.5 |
| U.S. 30 | "PARKING LOT" | "RESERVED PARKING" | 9.58 | 1 | 1 | | 9.58 |
| | | $250 FINE | | | | | |

WOOD SIGN SUPPORT — TOTAL 176

| LOCATION | "SIGN DESCRIPTON" | "SUPPORT LENGTH (ESTIMATE)" | "# OF SUPPORTS" | "# OF LOCATIONS" | | Subtotals FOOT |
|---|---|---|---|---|---|---|
| U.S. 6 | "PARK & RIDE (left or right arrow)" | 16 | 1 | 7 | | 112 |
| U.S. 52 | "PARK & RIDE (left or right arrow)" | 16 | 1 | 4 | | 64 |

CONCRETE FOUNDATIONS — TOTAL 5.6

| Station | Direction | "Sign Description" | "Post Size" | "# of Posts" | "Concrete Foundations per Post" | Subtotals CU YD |
|---|---|---|---|---|---|---|
| 60+00 | NB | "EXIT 248 PARK & RIDE" | W8x18 | 2 | 0.7 | 1.4 |
| 148+96 | SB | "EXIT 248 PARK & RIDE" | W8x18 | 2 | 0.7 | 1.4 |
| 300+78 | NB | "EXIT 253 PARK & RIDE" | W8x18 | 2 | 0.7 | 1.4 |
| 375+98 | SB | "EXIT 253 PARK & RIDE" | W6x15 | 2 | 0.7 | 1.4 |

REINFORCEMENT BARS — TOTAL 624

| STATION | DIRECTION | SIGN DESCRIPTION | POST SIZE | # OF POSTS | CONVERSION LBS/POST | SUBTOTALS POUNDS |
|---|---|---|---|---|---|---|
| 60+00 | NB | EXIT 248 PARK & RIDE | W8x18 | 2 | 78 | 156 |
| 148+96 | SB | EXIT 248 PARK & RIDE | W8x18 | 2 | 78 | 156 |
| 300+78 | NB | EXIT 253 PARK & RIDE | W8x18 | 2 | 78 | 156 |
| 375+98 | SB | EXIT 253 PARK & RIDE | W6x15 | 2 | 78 | 156 |

| REVISIONS | |
|---|---|
| NAME | DATE |

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (U.S. 6 TO U.S. 30)
PARK AND RIDE LOTS

## SCHEDULE OF QUANTITIES
## II

SCALE: N.T.S. DRAWN BY JFS
DATE 05/21/07 CHECKED BY DDH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = $DATE$
FILE NAME = $FILEN$
PLOT SCALE = $SCALE$
USER NAME = $USER$

~\BCP0104BRLDCN
5-21-2007,11:59:36 PIETRDJZ S:\DOCUMENT\62361560\CIVIL\DGN\SC11A002.SHT