

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CONTRACT NO. 78011				
ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FA 885	5I-1	HARDIN	11	3
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

CONSTRUCTION TYPE CODE: SAFETY - 2A		100% STATE	
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	14.7
<i>44001005</i>	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	8.9
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ. YD	82.2
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	446
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	128
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	59
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	160
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRP	EACH	6
70300200	TEMPORARY PAVEMENT MARKING	FOOT	250
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	380
70400100	TEMPORARY CONCRETE BARRIER	FOOT	230
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	150
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	989
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	449
X0325326	TEMPORARY TRAFFIC CONTROL REMOVAL	L SUM	1
<i>70106800</i>	CHANGEABLE MESSAGE SIGN	CAL MO	2
Z0030250	IMPACT ATTENUATORS, <i>TEMPORARY</i> (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

\*SPECIALTY ITEMS

Rev.