

90% FED.
10% STATE

90% FED.
10% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		RURAL 0005	URBAN 0005
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7167	4325	2842
40600300	AGGREGATE (PRIME COAT)	TON	143	86	57
40600990	TEMPORARY RAMP	SO YD	120	72	48
40603244	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N105	TON	18065	10913	7152
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	6020	3633	2387
44000173	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	SO YD	71517	43138	28379
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SO YD	8	4	4
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SO YD	295	70	225
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SO YD	19		19
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SO YD	33		33
44213000	PATCHING REINFORCEMENT	SO YD	355	74	281
44213200	SAW CUTS	FOOT	2654	572	2082
44213204	TIE BARS 3/4"	EACH	12		12

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		RURAL 0005	URBAN 0005
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	3	1
67100100	MOBILIZATION	L SUM	1	0.6	0.4
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	6		6
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.6	0.4
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	26	16	10
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1945	1246	699
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	48357	32104	16253
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1501		1501
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	642	411	231
X 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	12901	7786	5115
X 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	48357	32104	16253
X 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	1501		1501

X SPECIALTY ITEM

FILE NAME =	USER NAME = swrtrw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTEL	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\swrtrw\d0298200\077	570-shl-soq.dgn	DRAWN -	REVISED -		SCALE: NA	SHEET 1 OF 2 SHEETS	STA.	TO STA.	70	D7 HMA RESURF 2012-4	Fayette	21	3
	PLOT SCALE = 100,0000 1/2 in.	CHECKED -	REVISED -		CONTRACT NO. 74570								
	PLOT DATE = 6/5/2012	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								