

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	95	95					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	899	899					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	340	340					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1040	1040					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	95854	95854					
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	39	39					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1418	1418					
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1					
50105220	PIPE CULVERT REMOVAL	FOOT	82	82					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2					
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	64	64					
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	24	24					
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1	1					
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	7	7					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3					

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5					
60260100	INLETS TO BE ADJUSTED	EACH	25	25					
60262700	INLETS TO BE RECONSTRUCTED	EACH	10	10					
60404950	FRAMES AND GRATES, TYPE 24	EACH	29	29					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	4	4					
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	86.5	86.5					
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1					
63200310	GUARDRAIL REMOVAL	FOOT	96	96					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					

FILE NAME :	USER NAME : nlr/brade	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

SUMMARY OF QUANTITIES

F.A.P. RATE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	544-RS-4	DUPAGE	53	5
CONTRACT NO. 60NS2			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

* SPECIALTY ITEM