

PAVING SCHEDULE				LENGTH	TEMPORARY RAMPS	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0 FG, N90	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-19.0 FG, N90	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, SMA, N80	MATERIAL TRANSFER DEVICE	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	HOT-MIX ASPHALT SHOULDERS	SHOULDER RUMBLE STRIPS, 16 INCH	AGGREGATE WEDGE SHOULDER, TYPE B
STATION	TO	STATION	FEET	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD	POUND	TON	TON	TON	TON	TON	TON	TON	FOOT	TON
EASTBOUND																			
656+13	TO	685+25	2912	-	4691.6	-	7765.3	-	-	9100.0	978.4	978.4	1009.5	2966.3	-	-	394.1	5824	46.1
685+25	TO	688+75	350	-	563.9	373.3	933.3	-	-	1426.3	117.6	117.6	169.4	404.6	-	-	47.4	350	5.5
688+75	TO	688+95	20	-	32.2	41.5	26.7	26.7	99.5	4.2	5.9	12.3	22.4	-	-	2.7	20	0.3	
688+95	TO	690+55	160	236.4	257.8	622.7	213.3	-	-	492.0	26.9	26.9	108.6	162.4	-	-	21.7	160	2.5
690+55	TO	690+75	20	-	43.2	50.1	26.7	26.7	106.9	4.2	5.9	12.7	22.8	-	-	3.6	20	0.3	
690+75	TO	691+52	77	-	204.9	172.0	205.3	-	-	452.2	25.9	25.9	52.3	104.1	-	-	17.2	77	1.2
691+52	TO	712+48	2096	-	3376.9	-	5589.3	-	-	6550.0	704.3	704.3	726.6	2135.2	-	-	283.7	4192	33.2
712+48	TO	713+33	85	-	238.8	132.8	226.7	-	-	428.3	28.6	28.6	46.7	103.9	-	-	20.1	85	1.3
713+33	TO	713+53	20	-	46.5	31.1	26.7	26.7	96.4	4.2	5.9	11.0	21.1	-	-	3.9	20	0.3	
713+53	TO	716+53	300	443.3	483.3	971.4	400.0	-	-	832.5	50.4	50.4	177.7	278.5	-	-	40.6	300	4.7
716+53	TO	716+73	20	-	32.2	31.0	26.7	26.7	90.5	4.2	5.9	11.0	21.1	-	-	2.7	20	0.3	
716+73	TO	723+10	637	-	1026.3	521.7	1698.7	-	-	2468.4	214.0	214.0	289.8	717.8	-	-	86.2	637	10.1
723+10	TO	870+87	14777	-	23807.4	-	39405.3	-	-	46178.1	4965.1	4965.1	5122.7	15052.9	-	-	1999.8	29554	233.7
870+87	TO	877+10	623	-	1330.9	962.0	1661.3	-	-	2670.4	209.3	209.3	301.5	720.1	-	-	111.9	623	9.8
877+10	TO	919+56	4246	-	6840.8	-	11322.7	-	-	13268.8	1426.7	1426.7	1471.9	4325.3	-	-	574.6	8492	67.2
919+56	TO	934+20	1464	-	2986.8	1908.1	3904.0	-	-	6211.9	491.9	491.9	708.4	1692.2	-	-	251.0	1464	23.1
934+20	TO	1043+60	10940	-	17625.6	-	29173.3	-	-	34187.5	3675.8	3675.8	3792.5	11144.1	-	-	1480.5	21880	173.0
EB TOTALS:			38747	680	63589	5818	102605	107	-	124660	12932	12939	14025	39895	0	0	5342	73718	613
WESTBOUND																			
656+13	TO	686+90	3077	-	4957.4	-	8205.3	-	-	9615.6	1033.9	1033.9	1066.7	3134.5	-	-	416.4	6154	48.7
686+90	TO	690+20	330	-	531.7	253.4	880.0	-	-	1212.8	110.9	110.9	140.6	362.4	-	-	44.7	330	5.2
690+20	TO	690+40	20	-	32.2	21.8	26.7	26.7	82.5	4.2	5.9	9.8	19.9	-	-	2.7	20	0.3	
690+40	TO	694+40	400	591.1	644.4	725.0	533.3	-	-	1030.0	67.2	67.2	213.8	348.2	-	-	54.1	400	6.3
694+40	TO	694+60	20	-	37.1	31.1	26.7	26.7	92.2	4.2	5.9	11.0	21.1	-	-	3.1	20	0.3	
694+60	TO	697+49	289	-	666.4	449.9	770.7	-	-	1390.8	97.1	97.1	158.6	352.8	-	-	56.0	289	4.6
697+49	TO	718+85	2136	-	3441.3	-	5696.0	-	-	6675.0	717.7	717.7	740.5	2175.9	-	-	289.1	4272	33.8
718+85	TO	719+25	40	-	102.5	89.6	106.7	-	-	201.1	13.4	13.4	22.5	49.3	-	-	8.6	40	0.6
719+25	TO	719+45	20	-	43.7	49.7	26.7	26.7	100.2	4.2	5.9	11.7	21.8	-	-	3.7	20	0.3	
719+45	TO	721+05	160	236.4	257.8	623.0	213.3	-	-	492.0	26.9	26.9	108.6	162.4	-	-	21.7	160	2.5
721+05	TO	721+25	20	-	32.2	41.2	26.7	26.7	99.5	4.2	5.9	12.3	22.4	-	-	2.7	20	0.3	
721+25	TO	724+65	340	-	547.8	360.9	906.7	-	-	1385.5	114.2	114.2	164.5	392.9	-	-	46.0	340	5.4
724+65	TO	1043+60	31895	-	51386.4	-	85053.3	-	-	99671.9	10716.7	10716.7	11056.9	32490.3	-	-	4316.5	63790	504.5
WB TOTALS:			38747	828	62681	2646	102472	107	-	122049	12915	12922	13718	39554	0	0	5265	75855	613

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw_work\p\dot\stefenmk\d0338930\074255-sht-sch.dgn	DRAWN -	REVISED -	70						(26-3,4)RS-3	FAYETTE	31	16	
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: N/A	SHEET 1 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 74255				
	PLOT DATE = 6/12/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								