

100% STATE
CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE CONSTRUCTION CODE	
				FAP 592 ROADWAY 0005 URBAN	FAU 9190 ROADWAY 0005 URBAN
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2211	939	1272
40600990	TEMPORARY RAMP	SQ YD	370	109	261
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5900	3151	2749
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	114	61	53
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	59438	29497	29941
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	350	218	132
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SQ YD	37	19	18
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SQ YD	61		61
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	545	545	
44201299	DOWEL BARS 1 1/2"	EACH	1354	1354	
44213200	SAW CUTS	FOOT	4134	4134	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	26802	12906	13896
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	242	113	129
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1712	618	1094

* 592/9190

FILE NAME =	USER NAME = phallandesko	DESIGNED -	REVISED -
er\pr_work\p\dot\phallandesko\08355955	D076088-ah-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -
	PLOT DATE = 6/12/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FAP/FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
						*	I21-IRS-1	ST. CLAIR	32	3
						CONTRACT NO. 76680				
						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				