

August 31, 2021

SUBJECT: FAI Route 57 (I-57) Project NHPP--QL8L(443) Section 139 HBR-6 Kankakee County Contract No. 66997 Item No. 19, September 17, 2021 Letting Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.

2. Revised pages i and iii of the Table of Contents to the Special Provisions.

3. Revised pages 2-4 of the Special Provisions.

4. Added pages 163-165 to the Special Provisions.

5. Revised sheets 4, 5, 9, 10, 15, 17, 18, 21, 24, 26-29, 32, 35, 36, 38, 70-72, 74, 75, 77, 85, 167, 169, 170A, 175, 177-183, 185-193, and 196-201 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E. Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
UTILITY RELOCATIONS AND DELAYED START DATE	2
COOPERATION BETWEEN CONTRACTORS	4
EMBANKMENT	5
MULCH METHOD 2	5
AGGREGATE SUBGRADE IMPROVEMENT (DISTRICT 3)	5
WIDTH RESTRICTION SIGN	7
VEHICLE PARKING	7
EQUIPMENT ILLUMINATION	7
SEQUENCE OF OPERATIONS	8
KEEPING ROADS OPEN TO TRAFFIC	8
TRAFFIC CONTROL AND PROTECTION (SPECIAL)	9
CHANGEABLE MESSAGE SIGN	10
PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	10
ALTERNATE ROUTE SIGNING	11
TRAFFIC CONTROL AND PROTECTION, STANDARDS 701400 (SPECIAL) AND 7	01401
(SPECIAL)	11
SMART TRAFFIC MONITORING SYSTEM	12
CHANGEABLE MESSAGE SIGN, SPECIAL	15
CONTROL OF WORK – SMART WORK ZONE	15
TEMPORARY RUMBLE STRIPS (SPECIAL)	16
TEMPORARY BRIDGE TRAFFIC SIGNALS (STANDARD 701316 OR 701321)	17
TEMPORARY INFORMATION SIGNING	18
PINNING TEMPORARY CONCRETE BARRIER	19
TEMPORARY PAVEMENT	19
PLASTIC DRUMS	19
LINEAR DELINEATOR PANELS, 4 INCH	19
LINEAR DELINEATOR PANELS, 6 INCH	22
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (JOB SPECIFIC)	24
REMOVAL OF EXISTING PROTECTIVE SHIELDING	26
Revised August 31	, 2021

STEEL COST ADJUSTMENT (BDE)	115
STEEL PLATE BEAM GUARDRAIL MANUFACTURING (BDE)	117
STRUCTURAL TIMBER (BDE)	118
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	118
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	119
TEMPORARY PAVEMENT MARKING (BDE)	119
TRAFFIC CONTROL DEVICES - CONES (BDE)	121
TRAFFIC SPOTTERS (BDE)	122
TRAINING SPECIAL PROVISIONS (BDE)	123
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL	PROVISION.126
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL WARM MIX ASPHALT (BDE)	
	128
WARM MIX ASPHALT (BDE)	128 129
WARM MIX ASPHALT (BDE) WEEKLY DBE TRUCKING REPORTS (BDE)	128 129 130
WARM MIX ASPHALT (BDE) WEEKLY DBE TRUCKING REPORTS (BDE) WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	128 129 130 131
WARM MIX ASPHALT (BDE) WEEKLY DBE TRUCKING REPORTS (BDE) WORK ZONE TRAFFIC CONTROL DEVICES (BDE) WORKING DAYS (BDE)	
WARM MIX ASPHALT (BDE) WEEKLY DBE TRUCKING REPORTS (BDE) WORK ZONE TRAFFIC CONTROL DEVICES (BDE) WORKING DAYS (BDE) PROJECT LABOR AGREEMENT	

UTILITY RELOCATIONS AND DELAYED START DATE

It is anticipated that utility relocations will be underway when this project is awarded. The Contractor should assume that the start date for work on this project will be April 1, 2022, unless approved by the Engineer, to allow for utility relocations to be completed.

• Work associated with tree removal shall be performed as outlined per the tree removal commitment.

No working days shall be charged, and no additional compensation shall be due the Contractor for delays prior to April 1, 2022.

The remainder of this page has been left blank intentionally.

Revised August 31, 2021

This page has been left blank intentionally.

Revised August 31, 2021

COOPERATION BETWEEN CONTRACTORS

Additional construction activities located nearby I-57 may be under contract during the time this contract is in force.

The Contractor shall cooperate with the contractors on the other sections as described in Article 105.08 of the Standard Specifications.

It is anticipated that a roadway reconstruction project will be under contract at the same time and within the vicinity of I-57 in Kankakee.

The following project is scheduled to start in FY 2021-2022 construction:

• Contract 66F74 – Reconstruction of Structures over Grinnell Rd and Norfolk Southern Railway on I-57 in Kankakee.

Construction work for this contract and contract 66F74 can run concurrently. Traffic control shall

Revised August 31, 2021

STATUS OF UTILITIES TO BE ADJUSTED:

			Estimated Data
Name & Address of Utility	Type	Location	Estimated Date Relocation Complete
ComEd, An Exelon Company Two Lincoln Centre, 8 th Floor Oakbrook Terrace, IL 60181 ComEd Ref# H19081UNV	OH Electric 12kV and 34 kV Underground is 12 kV It should be noted that we are raising Waldron Rd. approx. 4' on the east side near power lines. The final vertical clearance should be approx. 25.2' to the lowest wires.	ComEd has overhead facilities throughout the project area. The pole in the SE quadrant (16+90 32' Rt) of East Duane Blvd is in conflict with the new shared-use path. ComEd also has a 34/12 kV line which runs along the east side of I-57.	ComEd has two conflicts with 12kV poles located at 16+90 32' RT and 231+40 99'LT. There are also four 34/12 kV poles which are very close to conflict at 20+67 44' Lt (Brace pole); 22+29 72' Rt; 230+22 96'Rt; and 231+15 96' Rt (brace pole). A permit will be required.
Nicor Gas 1844 Ferry Road Naperville, IL 60563 Nicor Ref #14821UNV	2", 4", and 6" Gas If there are conflicts with existing gas services please call 1- 888-NICOR- 4-U to schedule a relocation. The gas is 4" on the far west end. Near the east side of Duane Ave it has a 2" main going south and the rest of the main which heads east is 6" in size.		The 6" Nicor gas main located at 24+74 & 43.5'RT is near a 12" storm sewer. At 25+23 & 43.5' RT this main is near a storm sewer manhole. These two locations may require some minor field adjusting during construction. No additional conflicts were found. Permit 17666 was for seven test holes.

ΔΤΩΤ	Duried	AT&T has facilities	ATET has a conflict with
AT&T 1000 Commerce Drive Oak Brook, IL 60523 AT&T Ref #KK4109	Buried Telephone and attachment to bridge AT&T has two manholes located along the south edge of Waldron Road at 16+40 12' Rt and 23+40 13' Rt	which run along the south edge of Waldron Road and then is attached to the bridge. It continues eastward beyond the project limits. It does cross near 24+25 and then goes back west, approx. 26' north of the edge of pavement. At the entrance near 22+30 it extends north.	AT&T has a conflict with the current bridge attachment and will need to be relocated before the structure is removed. The two manholes located at 16+39.4 10.9' RT and 23+39.5 16.4'RT will be removed and replaced with larger ones (10'x10'x7'). They plan to directional bore and cross I-57 near 230+24 RT and 232+24 LT with seven 4" plastic conduits. They plan to be approx. 30' deep under the walls and I-57. Permit 18050 was approved on 5-14-2021.
Comcast Cable 688 Industrial Drive Elmhurst, IL 60126 #53496	Aerial CATV	Comcast has aerial that comes from the far east (but is a few hundred feet south of bridge) but then it follows our NB I-57 ROW, then crosses I- 57 on a diagonal and extends into the subdivision located on the west side of I- 57.	No conflicts are anticipated.
Aqua Illinois 1000 S. Schuyler Ave. Kankakee, IL 60901	8" and 12" Watermain	On the far west end of the project, Aqua has water main which runs along the north side and then it crosses Waldron on the east side of East Duane Blvd, heads south and then turns back towards I-57 and crosses underneath the interstate (approx. 260' from Waldron cl), and then makes its way back to the south side of Waldron Road.	Aqua has conflicts with proposed storm sewer and the proposed walls near the following locations: 16+84 19' Lt with our proposed storm sewer; from 17+65 to 18+30 Rt with proposed storm sewer; they need to extend the 20" steel casing under I-57 near station 232+70 on both ends; and new 12" DI at 24+63 under Waldron Road.

			proposed walls are at 232+66 for Wall A (west side) and 232+75 for Wall B (on the east side). A permit will be required.
Kankakee	8" Sanitary sewer	On the far west end of the project, Kankakee has sanitary sewer which extends down the southbound lane of Waldron Road. At around station 16+30 it turns south and crosses East Duane Blvd. and heads into the nearby subdivision.	We have a proposed 12" storm sewer lateral which crosses Waldron Road near 16+15 and we had to redesign the invert elevation at 21' Right to allow for some clearance between the sewer, which is approximately 5.6' deep in this area. Our Contractor will have to be careful when doing any work above this sanitary sewer so it is not damaged.
CMS 120 West Jefferson St. Springfield, IL 62702	Fiber	CMS has fiber along the east ROW of I-57. It typically runs approximately 5' inside the ROW line. There is a handhole in the SE quadrant, where it jogs east near Waldron Road (approx. 75' east of abutment). On the north side of the road it jogs back to where it is 5' from ROW again.	CMS may have conflicts with the proposed storm sewer along the east side of I-57 and the proposed walls and future noise wall for the interchange. A permit may be required.

The above represents the best information of the Department and is only included for the convenience of the bidder. The applicable provisions of Section 102 and Articles 105.07, 107.20, 107.37, 107.38, 107.39, 107.40, and 108.02 of the Standard Specifications for Road and Bridge Construction shall apply.

The estimated utility relocation dates should be part of the progress schedule submitted by the Contractor.

** Above utility relocation information reflected as of August 10, 2021 and final relocation completion dates are unknown at this time. Per SB 699 (90 day utility relocation law), a notice will be sent to the utility companies instructing them to have their facilities relocated within 90 days. Utility relocations are anticipated to be completed by the end of March 2022.