SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE I-000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24					
40600300	AGGREGATE (PRIME COAT)	TON	120	120					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	45	45					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	417	417					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	557	557					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2501	2501					
42001300	PROTECTIVE COAT	SQ YD	222	222					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	810	810					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	29764	29764					
44000600	SIDEWALK REMOVAL	SQ FT	810	810					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	590	590					
44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SQ YD	2778	2778					
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	132	132					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	406	406					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	240	240					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	2000	2000					
# 55039700	STORM SEWERS TO BE CLEANED	FOOT	516	516					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2					
60253100	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	10	10					
60254330	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1					
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1					
60260100	INLETS TO BE ADJUSTED	EACH	3	3					
60264130	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	3	3					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	49	49					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	76	76					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE I-000					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4837	4837					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	120	120					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10670	10670					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1766	1766					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	120	120					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	318	318					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1613	1613					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	120	120					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10670	10670					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1766	1766					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	318	318					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	641	641					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	513	513					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	930	930					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1172	1172					
# Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	125	125					

*SPECIALITY ITEMS

#NON PARTICIPATING ITEMS
(100% STATE)

FILE NAME = c:\pw_work\PWIDOT\AQUEELFF\d0142870\D176609-sht-plan.dgn	USER NAME = aqueelff	DESIGNED - FFA 6-8-09	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 6/25/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GUNNISON STREET
SUMMARY OF QUANITIES

SCALE: | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1363	0707.4RS	COOK	20	3

CONTRACT NO. 60H68

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT