

F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2903	00-00047-00-FP	LAKE	180	3
SUMMARY OF QUANTITIES				
ILLINOIS				

Sp.	CODE #	DESCRIPTION	UNIT	TOTAL QUANTITY	WASHINGTON ST. ROAD IMP. I 000-2A	WASHINGTON ST. SIGNAL IMP. Y 031-1F	WASHINGTON ST. SH. USE PATH Y 045	WASHINGTON ST. OUTLOT I 000-2A	CEMETERY RD ROAD IMP I 000-2A	CEMETERY RD WATERMAIN Y060	TRI STATE ROAD IMP I 000-2A
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UN	482	251	-	-	-	231	-	-
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UN	1670	471	-	-	-	1033	-	166
	20101000	TEMPORARY FENCE	FT	2380	780	-	-	100	1500	-	-
	20101100	TREE TRUNK PROTECTION	EA	140	40	-	-	8	92	-	-
△	20101200	TREE ROOT PRUNING	EA	77	22	-	-	-	55	-	-
△	20101400	NITROGEN FERTILIZER NUTRIENT	LBS	644	278	-	-	28	336	-	2
△	20101500	PHOSPHORUS FERTILIZER NUTRIENT	LBS	644	278	-	-	28	336	-	2
△	20101600	POTASSIUM FERTILIZER NUTRIENT	LBS	644	278	-	-	28	336	-	2
	20200100	EARTH EXCAVATION	CY	36867	18992	-	-	50	17825	-	-
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CY	3830	1900	-	-	-	1900	-	30
	20400800	FURNISHED EXCAVATION	CY	3345	1885	-	-	-	1460	-	-
*	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CY	3360	1895	-	-	-	1465	-	-
	20800150	TRENCH BACKFILL	CY	2163	788	-	-	13	1336	-	26
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SY	9750	5750	-	-	-	4000	-	-
△	21101625	TOPSOIL FURNISH AND PLACE, 6"	SY	34555	14940	-	-	1510	17855	-	250
*	21301052	EXPLORATION TRENCH, 52" DEPTH	FT	220	78	-	-	-	142	-	-
△	25000210	SEEDING, CLASS 2A	AC	9	4	-	-	1	4	-	-
△	25100115	MULCH, METHOD 2	AC	9	4	-	-	1	4	-	-
△	25200110	SODDING, SALT TOLERANT	SY	250	-	-	-	-	-	-	250
△	25200200	SUPPLEMENTAL WATERING	UN	100	52	-	-	-	48	-	-
△	28000255	TEMPORARY EROSION CONTROL SEEDING	AC	9	4	-	-	1	4	-	-
*	28000300	TEMPORARY DITCH CHECKS	EA	48	25	-	-	-	23	-	-
*	28000400	PERIMETER EROSION BARRIER	FT	21305	8575	-	-	-	12600	-	130
	28000510	INLET FILTERS	EA	228	90	-	-	-	131	-	7
	28100107	STONE RIPRAP, CLASS A4	SY	120	65	-	-	-	55	-	-
	28200200	FILTER FABRIC	SY	180	103	-	-	-	77	-	-
	28500400	ARTICULATED BLOCK REVETMENT MAT	SY	60	38	-	-	-	22	-	-
	35101800	AGGREGATE BASE COURSE, TYPE B, 6"	SY	10065	645	-	2835	190	6315	-	80
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TN	630	154	-	-	-	476	-	-
*	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	21557	13285	-	-	-	7712	-	560
	40600300	AGGREGATE (PRIME COAT)	TN	114	67	-	-	-	36	-	11
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SY	160	40	-	-	-	-	-	120
	40600990	TEMPORARY RAMP	SY	15	-	-	-	-	-	-	15
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TN	938	-	-	320	-	608	-	10
	40603310	HOT-MIX ASPHALT ASPHALT SURFACE COURSE, MIX C, N50	TN	1128	58	-	320	-	740	-	10
	40603340	HOT-MIX ASPHALT ASPHALT SURFACE COURSE, MIX D, N70	TN	660	-	-	-	-	-	-	660
	40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SY	17120	-	-	-	-	17120	-	-
	40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SY	24390	24390	-	-	-	-	-	-
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SF	5450	2290	-	-	1700	1260	-	200
*	42400800	DETECTABLE WARNINGS	SF	340	200	-	-	-	120	-	20
	44000100	PAVEMENT REMOVAL	SY	29300	16395	-	-	-	12530	-	375
*	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SY	5860	260	-	-	-	-	-	5600
	44000200	DRIVEWAY PAVEMENT REMOVAL	SY	2575	745	-	-	-	1830	-	-
	44000500	COMBINATION CURB AND GUTTER REMOVAL	PF	1560	310	-	-	-	675	-	575
	44000600	SIDEWALK REMOVAL	SF	5725	5675	-	-	-	50	-	-
*	44201785	CLASS D PATCHES, TYPE I, 12"	SY	30	-	-	-	-	-	-	30
*	44201789	CLASS D PATCHES, TYPE II, 12"	SY	45	-	-	-	-	-	-	45
*	44201794	CLASS D PATCHES, TYPE III, 12"	SY	140	-	-	-	-	-	-	140
*	44201796	CLASS D PATCHES, TYPE IV, 12"	SY	90	-	-	-	-	-	-	90
	48101600	AGGREGATE SHOULDERS, TYPE B, 8"	SY	1240	1240	-	-	-	-	-	-
	50104400	CONCRETE HEADWALL REMOVAL	EA	1	-	-	-	-	1	-	-
	50105220	PIPE CULVERT REMOVAL	FT	1196	431	-	-	-	765	-	-
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION, 12"	EA	1	-	-	-	-	1	-	-
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTION, 15"	EA	2	-	-	-	-	2	-	-
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION, 18"	EA	3	2	-	-	-	1	-	-
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTION, 24"	EA	1	-	-	-	-	1	-	-
	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTION, 36"	EA	2	1	-	-	1	-	-	-
	54213693	PRECAST REINFORCED CONCRETE FLARED END SECTION, 48"	EA	1	-	-	-	-	1	-	-
	54215442	CAST-IN-PLACE REINFORCED CONCRETE END SECTION, 42"	EA	1	-	-	-	-	1	-	-
	54215448	CAST-IN-PLACE REINFORCED CONCRETE END SECTION, 48"	EA	4	2	-	-	-	2	-	-
	54247090	GRATING FOR CONCRETE FLARED END SECTION, 12"	EA	1	-	-	-	-	1	-	-
	54247100	GRATING FOR CONCRETE FLARED END SECTION, 15"	EA	2	-	-	-	-	2	-	-
	54247110	GRATING FOR CONCRETE FLARED END SECTION, 18"	EA	3	2	-	-	-	1	-	-
	54247130	GRATING FOR CONCRETE FLARED END SECTION, 24"	EA	1	-	-	-	-	1	-	-
	54247170	GRATING FOR CONCRETE FLARED END SECTION, 36"	EA	2	1	-	-	1	-	-	-
	54247190	GRATING FOR CONCRETE FLARED END SECTION, 48"	EA	1	-	-	-	-	1	-	-
	55100100	STORM SEWER REMOVAL, 4"	FT	35	15	-	-	-	20	-	-
	55100200	STORM SEWER REMOVAL, 6"	FT	65	45	-	-	-	20	-	-
	55100400	STORM SEWER REMOVAL, 10"	FT	340	-	-	-	-	340	-	-
	55100500	STORM SEWER REMOVAL, 12"	FT	775	550	-	-	-	205	-	20
	55100700	STORM SEWER REMOVAL, 15"	FT	695	530	-	-	-	165	-	-
	55100900	STORM SEWER REMOVAL, 18"	FT	85	-	-	-	-	85	-	-
	55101400	STORM SEWER REMOVAL, 30"	FT	30	-	-	-	-	30	-	-
	55101600	STORM SEWER REMOVAL, 36"	FT	85	85	-	-	-	-	-	-

△ SPECIALTY ITEMS

PLANS PREPARED BY:		REVISIONS	
GEWALT HAMILTON ASSOCIATES, INC.		NAME	DATE
Consulting Engineers & Surveyors 800 Forest Edge Drive Vernon Hills, IL 60061 (847) 478-9700 (847) 478-9701 Fax		REV.-1 IDOT COMMENTS	02-03-06
		REV. - 2	06-02-06
		REV.-5 PRE-FINAL SUB	02-20-09
		PS&E SUBMITTAL	04-10-09
ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			
PROPOSED ROADWAY WIDENING AND INTERSECTION IMPROVEMENTS CEMETERY ROAD			
DRAWN BY: TAR		DATE: 8/24/05 CHECKED BY: TPG	

3081-212-500-51002E 1-06