

F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2903	00-00047-00-FP	LAKE	180	6
SUMMARY OF QUANTITIES				
CONTRACT NO. 83845		ILLINOIS		

Sp.	CODE #	DESCRIPTION	UNIT	TOTAL QUANTITY	WASHINGTON ST. ROAD IMP. I 000-2A	WASHINGTON ST. SIGNAL IMP. Y 031-1F	WASHINGTON ST. SH. USE PATH Y 045	WASHINGTON ST. OUTLOT I 000-2A	CEMETERY RD ROAD IMP I 000-2A	CEMETERY RD WATERMAIN Y060	TRI STATE ROAD IMP I 000-2A
*	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EA	1	-	1	-	-	-	-	-
Δ	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FT	700	-	700	-	-	-	-	-
Δ	X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FT	450	-	450	-	-	-	-	-
*	XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SF	50	-	-	-	-	50	-	-
*	XX000856	MAILBOX REMOVAL AND RELOCATION	EA	30	9	-	-	-	21	-	-
*	XX008151	TEMPORARY BITUMINOUS SURFACE	SY	550	550	-	-	-	-	-	-
	XX003360	STORM SEWER, PVC SDR 26, 12"	FT	70	70	-	-	-	-	-	-
	XX003503	FLARED END SECTION REMOVAL	EA	30	24	-	-	-	6	-	-
Δ	XX003660	FIBEROPTIC CABLE IN CONDUIT, NO. 62.5/125, MM24F AND SM12F	FT	5226	-	5226	-	-	-	-	-
Δ	XX003668	PRECONSTRUCTION VIDEOTAPING	LS	1	1	-	-	-	-	-	-
*	XX003822	STORM SEWER REMOVAL, SPECIAL	FT	65	-	-	-	-	65	-	-
*	XX004782	TEMPORARY BITUMINOUS PAVEMENT	SY	6490	6490	-	-	-	-	-	-
*	XX004878	MAINTENANCE OF TEMPORARY FROSION CONTROL SYSTEMS	LS	1	1	-	-	-	-	-	-
Δ	A2007122	TREES, QUERCUS RUBRA (RED OAK), 3" CALIPER, BALLED AND BURLAPPED	EA	7	3	-	-	-	2	-	2
Δ	A2006524	TREES, QUERCUS BICOLOR (SWAMP WHITE OAK), 3" CALIPER, BALLED AND BURLAPPED	EA	9	5	-	-	-	1	-	3
	XX005690	STORM SEWER, DUCTILE IRON PIPE, CLASS 52, 12"	FT	28	-	-	-	-	28	-	-
	XX005691	STORM SEWER, DUCTILE IRON PIPE, CLASS 52, 18"	FT	46	-	-	-	-	46	-	-
Δ	XX005723	VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION)	EA	1	-	1	-	-	-	-	-
Δ	XX005931	TRAFFIC SIGNAL POST, 16 FT. (SPECIAL)	EA	4	-	4	-	-	-	-	-
Δ	XX005937	L.E.D. INTERNALLY ILLUMINATED STREET NAME SIGN	EA	36	-	36	-	-	-	-	-
*	XX005940	REMOTE-CONTROLLED VIDEO SYSTEM	EA	1	-	1	-	-	-	-	-
*	XX006338	EROSION CONTROL BLANKET (SPECIAL)	SY	34305	14940	-	-	1510	17855	-	-
Δ	XX006655	LAYER II (DATA LINK) SWITCH	EA	1	-	1	-	-	-	-	-
Δ	XX006658	FLOCCULATION LOGS	EA	20	10	-	-	-	10	-	-
Δ	X8620020	UNINTERRUPTIBLE POWER SUPPLY (UPS)	EA	1	-	1	-	-	-	-	-
Δ	XX006676	FLOCCULATION SOCKS	EA	20	10	-	-	-	10	-	-
Δ	A2006624	TREES, QUERCUS IMBRICARIA (SHINGLE OAK), 3" CALIPER, BALLED AND BURLAPPED	EA	4	2	-	-	-	1	-	1
Δ	XX007343	MULCH, SHREDDED HARDWOOD, 4"	SY	250	250	-	-	-	-	-	-
Δ	A3005210	TREES, ZELKOVA SERRATA (JAPANESE ZELKOVA), 2 1/2" CALIPER, BALLED AND BURLAPPED (SPECIAL)	EA	9	4	-	-	-	-	-	5
*	XX206400	MAILBOX POST	EA	30	9	-	-	-	21	-	-
*	Z0001050	AGGREGATE SUBGRADE 12"	SY	50070	27955	-	-	-	22115	-	-
*	Z0013798	CONSTRUCTION LAY OUT	LS	1	1	-	-	-	-	-	-
*	Z0017400	DRAINAGE AND UTILITY STRUCTURES TO BE ADJUSTED	EA	9	-	-	-	-	8	-	1
*	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EA	249	111	-	-	-	131	-	7
	Z0019600	DUST CONTROL WATERING	UN	60	32	-	-	-	28	-	-
	Z0022800	FENCE REMOVAL	FT	290	-	-	-	-	290	-	-
*	Z0062400	SAWING BITUMINOUS CONCRETE PAVEMENT	FT	910	295	-	-	-	465	-	150
*	Z0064600	SELECTIVE CLEARING	AC	1	-	-	-	-	1	-	-
+	Z0076800	TRAINEES	HRS	4000	2000	-	-	-	2000	-	-
Δ	56106600	ADJUSTING WATERMAIN 12"	FT	250	-	-	-	-	-	250	-
Δ	56106700	ADJUSTING WATERMAIN 16"	FT	100	-	-	-	100	-	-	4
Δ	56400400	FIRE HYDRANT TO BE RELOCATED	EA	16	-	-	-	4	-	12	-
Δ	56500200	DOMESTIC WATER SERVICE BOX TO BE MOVED	EA	25	-	-	-	3	-	22	-
Δ	B2001160	TREES, CERCIIDIPHYLLUM JAPONICUM (KATSURATREE), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EA	20	6	-	-	-	14	-	-
*	XX008117	STORM WATER TREATMENT UNIT	EA	1	-	-	-	-	1	-	-

Δ = SPECIALTY ITEMS
+ = Y080

PLANS PREPARED BY: GEWALT HAMILTON ASSOCIATES, INC. <small>Consulting Engineers & Surveyors 859 Forest Ridge Drive Vernon Hills, IL 60061 (847) 476-9700 (847) 476-9701 Fax</small>	REVISIONS	
	NAME	DATE
	REV.-1 IDOT COMMENTS	02-03-06
	REV.-2	05/02/06
	REV.-5 PRE-FINAL SUB PS&E SUBMITTAL PER IDOT COMMENTS	02-20-09 04-10-09 08-05-09

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PROPOSED ROADWAY WIDENING
AND INTERSECTION IMPROVEMENTS
CEMETERY ROAD

DRAWN BY: TAR
DATE: 8/24/05
CHECKED BY: TPG