

SCHEDULE OF PAVEMENT REMOVAL WASHINGTON STREET

STATION	FROM	TO	SQ. YD.
100+64	108+50		4,065.0
108+50	120+75		5,950.0
120+75	133+50		6,200.0
133+50	134+05		1,80.0
TOTAL			16,395.0

SCHEDULE OF COMB. CONC. CURB AND GUTTER, B-6.24 WASHINGTON STREET

STATION	FROM	TO	FEET
100+64	102+00		275.0
102+00	108+50		1,300.0
108+50	115+00		1,300.0
115+00	120+75		1,180.0
120+75	127+00		1,250.0
127+00	133+50		1,300.0
133+50	134+05		120.0
TOTAL			6,725.0

SCHEDULE OF HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 12" POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX 'F', N90, 2" BITUMINOUS MATERIALS (PRIME COAT) AGGREGATE (PRIME COAT) SURFACE: 0.0560 TONS/SY-IN - BIT PRIME: 0.10 GAL/SY - AGG PRIME: 4 LBS/SY WASHINGTON STREET

STATION	FROM	TO	AREA (SY)	DEPTH (INCHES)	SURFACE (TON)	BIT MAT (GAL)	AGG MAT (TON)
100+64	102+00		870.0	2.0	98.0	87.0	2
102+00	108+50		4,333.0	2.0	486.0	434.0	9
108+50	115+00		4,333.0	2.0	486.0	434.0	9
115+00	120+75		4,277.0	2.0	479.0	428.0	9
120+75	127+00		5,425.0	2.0	608.0	543.0	11
127+00	133+50		4,435.0	2.0	498.0	444.0	9
133+50	138+00		367.0	2.0	42.0	37.0	1
TOTALS			24,040.0		2,697.0	2,407.0	50

SCHEDULE OF HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 12" POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90, 2" HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50, 8" BITUMINOUS MATERIALS (PRIME COAT) BINDER: 0.0560 TONS/SY-IN - BIT PRIME: 0.25 GAL/SY WASHINGTON STREET

STATION	FROM	TO	AREA (SY)	BINDER DEPTH (INCHES)	BINDER (TON)	POLY BINDER DEPTH (INCHES)	POLY BINDER (TON)	BIT MAT (GAL)
100+64	102+00		870.0	8.0	390.0	2.0	98.0	218.0
102+00	108+50		4,333.0	8.0	1942.0	2.0	486.0	1084.0
108+50	115+00		4,333.0	8.0	1942.0	2.0	486.0	1084.0
115+00	120+75		4,277.0	8.0	1917.0	2.0	479.0	1070.0
120+75	127+00		5,425.0	8.0	2430.0	2.0	608.0	1357.0
127+00	133+50		4,435.0	8.0	1987.0	2.0	498.0	1109.0
133+50	138+00		369.0	8.0	165.0	2.0	42.0	92.0
TOTALS			24,040.0		10,773.0		2,697.0	6,014.0

SCHEDULE OF TREE PROTECTION WASHINGTON STREET

STATION	FROM	TO	QTY
100+64	102+00		1
102+00	108+50		19
108+50	115+00		7
115+00	120+75		1
120+75	127+00		2
127+00	133+50		3
133+50	138+00		7
138+00	143+00		
OUTLOT			8
TOTAL			48

SCHEDULE OF 4" PIPE UNDERDRAIN WASHINGTON STREET

STATION	FROM	TO	LENGTH
100+64	102+00		352
102+00	108+50		1460
108+50	115+00		1460
115+00	120+75		1212
120+75	127+00		1010
127+00	133+50		1428
133+50	138+00		133
138+00	143+00		
OUTLOT			
TOTAL			7055

SCHEDULE OF DRIVEWAY PAVEMENT REMOVAL WASHINGTON STREET

STATION	FROM	TO	SQ. YD.
100+64	108+50		360.0
108+50	120+75		70.0
120+75	133+50		180.0
133+50	134+05		135.0
TOTAL			745.0

SCHEDULE OF STORM SEWER END SECTIONS WASHINGTON STREET

STATION	FROM	TO	48" HEADWALL IDOT STND	36" RCP FES
			542106	542301
100+64	102+00		0	0
102+00	108+50		0	1
108+50	115+00		0	0
115+00	120+75		0	0
120+75	127+00		0	0
127+00	133+50		0	0
133+50	138+00		2	0
	OUTLOT		0	0
TOTAL			2	1

SCHEDULE OF TRENCH BACKFILL WASHINGTON STREET

STATION	FROM	TO	TRENCH BACKFILL (CY)
100+64	102+00		48
102+00	108+50		78
108+50	115+00		90
115+00	120+75		119
120+75	127+00		287
127+00	133+50		77
133+50	138+00		78
138+00	143+00		0
500+00	560+00		13
TOTAL			790

SCHEDULE OF THERMOPLASTIC PAVEMENT MARKINGS WASHINGTON STREET

STATION	FROM	TO	4" (LF)	5" (LF)	6" (LF)	8" (LF)	12" (LF)	24" (LF)	LETTERS & SYMBOLS (SF)
100+64	102+00		1,840	272	500	0	110	36	146
102+00	108+50		2,920	1,300	0	0	135	0	0
108+50	115+00		2,740	1,300	135	0	125	0	36
115+00	120+75		1,800	1,180	435	0	230	14	73
120+75	127+00		1,590	850	380	0	40	0	73
127+00	133+50		2,660	1,300	0	0	265	0	0
133+50	138+00		1,200	600	0	0	150	0	0
138+00	143+00		0	0	0	0	0	0	0
500+00	560+00		0	0	0	0	0	0	0
TOTAL			14,750	6,802	1,450	0	1,055	50	328

SCHEDULE OF SIDEWALK REMOVAL WASHINGTON STREET

STATION	FROM	TO	SQ. FT.
100+64	108+50		1,000.0
108+50	120+75		2,160.0
120+75	133+50		775.0
133+50	134+05		1,740.0
TOTAL			5,675.0

SCHEDULE OF BARB WIRE FENCE REMOVAL WASHINGTON STREET

STATION	FROM	TO	LENGTH
100+64	108+50		
108+50	120+75		
120+75	133+50		530.0
133+50	135+05		450.0
TOTAL			980.0

SCHEDULE OF STRUCTURES TO BE REMOVED WASHINGTON STREET

STATION	FROM	TO	MH	CB	INL
100+64	108+50		2	2	1
108+50	120+75				1
120+75	133+50		2		4
133+50	135+05				
TOTAL			4	2	6

SCHEDULE OF PAVING - SHARED USE PATH HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N50, 2" HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N50 2" BINDER: 0.0560 TONS/SY-IN SURFACE: 0.0560 TONS/SY-IN WASHINGTON STREET

STATION	FROM	TO	AGG BASE	BINDER	SURFACE
100+64	102+00		0.0	0.0	0.0
102+00	108+50		150.0	17.0	17.0
108+50	115+00		722.0	83.0	83.0
115+00	120+75		560.0	65.0	65.0
120+75	127+00		560.0	65.0	65.0
127+00	133+50		722.0	83.0	83.0
133+50	138+00		60.0	7.0	7.0
TOTAL			2,774.0	320.0	320.0

SCHEDULE OF STORM SEWER STRUCTURE INSTALLATION WASHINGTON STREET

STATION	FROM	TO	48" MH TY 1 CL	48" MH TY 8 GR	48" MH TY 11 GR	48" MH TY 24 CL	60" MH TY 1 CL	72" MH TY 1 CL	48" CB TY 1 FR	48" CB TY 24 GR	60" CB TY 1 CL	24" INL TY 1 GR	24" INL TY 8 GR	24" INL TY 24 GR
100+64	102+00		3	0	0	0	0	0	1	0	0	0	0	2
102+00	108+50		3	0	0	3	2	2	0	4	0	0	6	3
108+50	115+00		5	0	0	0	0	0	5	0	0	0	1	5
115+00	120+75		1	0	0	0	0	0	1	0	0	1	0	1
120+75	127+00		2	2	1	1	0	0	1	4	0	1	0	3
127+00	133+50		3	1	0	2	0	0	4	0	1	2	2	2
133+50	135+05		2	1	0	0	0	1	1	1	0	0	0	1
	OUTLOT		0	0	0	0	0	0	0	0	1	0	0	0
TOTAL			19	4	1	6	2	3	3	19	1	3	9	17

SCHEDULE OF STRUCTURES TO BE RECONSTRUCTED WASHINGTON STREET

STATION	FROM	TO	MH	TY	FR	VV
100+64	102+00					
102+00	108+50					
108+50	115+00		1			
115+00	120+75					
120+75	127+00					
127+00	133+50					
133+50	138+00					
138+00	143+00					
OUTLOT						
TOTAL			1		0	0

SCHEDULE OF PAVING - DRIVEWAYS HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N50, 2.5" AGGREGATE BASE COURSE, TYPE 'B' 6" BINDER: 0.0560 TONS/SY-IN SURFACE: 0.0560 TONS/SY-IN WASHINGTON STREET

STATION	FROM	TO	AGG BASE (SY)	SURFACE (TONS)
100+64	102+00		30.0	5.0
102+00	108+50		92.0	14.0
108+50	115+00		0.0	0.0
115+00	120+75		36.0	5.0
120+75	127+00		27.0	4.0
127+00	133+50		24.0	4.0
133+50	138+00		165.0	24.0
TOTAL			369.0	56.0

SCHEDULE OF GEOTEXTILE FABRIC WASHINGTON STREET

STATION	FROM	TO	LENGTH (FT)	AVG. WIDTH (FT)	SQ. YD.
100+64	102+00		0.0	0.0	0.0
102+00	108+50		0.0	0.0	0.0
108+50	115+00		0.0	0.0	0.0
115+00	120+75		575.0	83.0	5,300.0
120+75	127+00		0.0	0.0	0.0
127+00	133+50		0.0	0.0	0.0
133+50	135+05		0.0	0.0	450.0
TOTAL					5,750.0

SCHEDULE OF STORM SEWER PIPE INSTALLATION WASHINGTON STREET

STATION	FROM	TO	12 INCH (FT)	15 INCH (FT)	18 INCH (FT)	36 INCH (FT)	48 INCH (FT)
100+64	102+00		164	0	0	0	0
102+00	108+50		654	158	385.0	78	0
108+50	115+00		811	150	0	0	0
115+00	120+75		286	0	0	0	0
120+75	127+00		842	300	0	0	0
127+00	133+50						