

CEMETERY ROAD

SCHEDULE OF QUANTITIES - EARTHWORK

F.A.U. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2903	00-00047-0C-FP	LAKE	180	9
SCHEDULE OF QUANTITIES				
ILLINOIS				

STA	EARTH EXCAVATION (CY)	R&D UNSUITABLE (CY)	EARTH EX ADJUST (CY)	EMBANKMENT (CY)	C/F BALANCE (CY)	STA	EARTH EX (CY)	R&D UNSUITABLE (CY)	EX ADJUSTED (CY)	EMBANKMENT (CY)	BALANCE (CY)
198+00	0.0	0.0	0.0	0.0	0.0	222+50	112.1	0.0	95.3	10.7	84.6
198+50	73.9	0.0	62.8	0.0	62.8	222+84	65.5	0.0	55.7	4.1	51.6
199+00	158.9	0.0	135.1	0.0	135.1	223+00	147.6	0.0	125.5	8.6	116.9
199+50	85.0	0.0	72.3	0.0	72.3	223+35	59.6	0.0	50.6	1.8	48.9
200+00	0.0	0.0	0.0	0.0	0.0	223+50	190.7	0.0	162.1	5.7	156.4
200+50	0.0	0.0	0.0	0.0	0.0	224+00	149.5	0.0	127.1	16.7	110.4
201+00	178.1	0.0	151.4	0.0	151.4	224+50	124.9	0.0	106.2	19.2	87.0
201+50	299.3	0.0	254.4	0.0	254.4	225+00	152.2	0.0	129.4	15.2	114.2
201+92	49.8	0.0	42.4	0.0	42.4	225+50	20.3	0.0	17.3	0.9	16.4
202+00	259.9	0.0	220.9	0.0	220.9	225+55	215.3	0.0	183.0	2.0	181.0
202+50	192.4	0.0	163.5	6.9	156.7	226+00	380.8	0.0	323.7	17.2	306.6
203+00	54.9	0.0	46.6	8.1	38.5	226+37	58.9	0.0	50.1	2.5	47.6
203+25	108.8	0.0	92.5	13.7	78.8	226+50	210.7	0.0	179.1	8.8	170.3
203+50	143.6	0.0	122.1	9.0	113.1	227+00	155.6	0.0	132.2	16.8	115.5
204+00	153.3	0.0	130.3	13.8	116.5	227+50	93.1	0.0	79.2	32.4	46.8
204+50	157.0	0.0	133.5	14.4	119.1	228+00	62.5	0.0	53.1	54.6	-1.5
205+00	169.4	0.0	143.9	13.9	130.1	228+50	79.2	0.0	67.3	46.1	21.2
205+50	162.9	0.0	138.5	18.5	120.0	229+00	120.1	0.0	102.1	26.5	75.6
205+95	18.7	0.0	15.9	1.3	14.6	229+50	152.3	0.0	129.5	13.6	115.9
206+00	88.5	0.0	75.2	0.9	74.4	230+00	166.1	0.0	141.2	6.1	135.1
206+23	106.0	0.0	90.1	1.0	89.1	230+50	169.9	0.0	144.4	8.7	135.7
206+50	90.4	0.0	76.8	6.1	70.8	231+00	154.3	0.0	131.1	15.3	115.8
206+74	56.4	0.0	48.0	3.2	44.8	231+50	126.5	0.0	107.5	36.7	70.8
206+88	52.7	0.0	44.8	0.0	44.8	232+00	49.5	0.0	42.1	35.5	6.6
207+00	204.5	0.0	173.9	0.5	173.4	232+28	37.1	0.0	31.5	24.0	7.6
207+50	175.7	0.0	149.4	8.3	141.0	232+50	114.9	0.0	97.7	28.1	69.6
208+00	166.0	0.0	141.1	13.0	128.2	233+00	179.2	0.0	152.3	10.0	142.3
208+50	187.0	0.0	159.0	10.4	148.6	233+50	291.4	0.0	247.7	0.0	247.7
209+00	194.4	0.0	165.2	18.6	146.6	234+00	359.8	0.0	305.8	0.0	305.8
209+50	61.5	0.0	52.2	7.4	44.8	234+50	362.8	0.0	308.4	0.0	308.4
209+67	56.3	0.0	47.9	6.4	41.5	235+00	251.4	0.0	213.7	0.4	213.3
209+83	58.8	0.0	50.0	4.0	46.0	235+39	74.4	0.0	63.3	0.1	63.2
210+00	80.5	0.0	68.4	5.5	62.9	235+50	305.8	0.0	260.0	0.0	260.0
210+27	55.3	0.0	47.0	10.1	36.9	236+00	240.8	0.0	204.7	0.0	204.7
210+50	107.3	0.0	91.2	23.6	67.6	236+50	256.3	0.0	217.9	0.5	217.4
211+00	74.4	0.0	63.2	20.7	42.6	237+00	223.1	0.0	189.6	2.9	186.7
211+41	14.6	0.0	12.4	5.8	6.6	237+50	168.9	0.0	143.6	9.8	133.7
211+50	40.0	0.0	34.0	13.6	20.4	238+00	152.8	0.0	129.9	14.3	115.6
211+74	46.3	0.0	39.4	8.3	31.0	238+50	143.6	0.0	122.1	29.5	92.5
212+00	5.5	0.0	4.7	1.1	3.6	239+00	35.1	0.0	29.9	36.7	-6.8
212+03	78.9	0.0	67.0	24.7	42.3	239+12	141.7	0.0	120.4	166.8	-46.4
212+50	86.5	0.0	73.5	29.2	44.3	239+50	292.3	0.0	248.5	90.0	158.5
213+00	17.3	0.0	14.7	3.4	11.3	240+00	285.2	0.0	242.4	0.6	241.8
213+08	112.9	0.0	96.0	38.1	57.9	240+50	133.1	0.0	113.1	0.1	113.1
213+50	146.2	0.0	124.3	118.8	5.5	240+84	64.5	0.0	54.8	0.1	54.7
214+00	144.4	0.0	122.7	84.6	38.1	241+00	206.9	0.0	175.9	0.5	175.4
214+50	52.1	0.0	44.3	3.0	41.3	241+50	182.7	0.0	155.3	3.4	151.9
214+67	117.3	0.0	99.7	2.4	97.2	242+00	159.5	0.0	135.6	8.9	126.7
215+00	41.2	0.0	35.0	2.8	32.1	242+50	135.2	0.0	114.9	16.7	98.2
215+12	125.0	0.0	106.2	9.0	97.2	243+00	92.6	0.0	78.7	35.3	43.4
215+50	167.1	0.0	142.1	13.0	129.1	243+50	69.4	0.0	59.0	54.9	4.1
216+00	23.1	0.0	19.6	1.5	18.1	244+00	73.0	17.1	62.0	60.3	1.7
216+06	203.1	0.0	172.7	0.0	172.7	244+50	100.8	34.7	85.7	54.3	31.4
216+50	49.4	0.0	42.0	2.4	39.6	245+00	129.5	36.1	110.1	49.5	60.6
216+62	136.6	0.0	116.1	13.2	102.9	245+50	130.6	37.5	111.1	56.4	54.7
216+96	17.9	0.0	15.2	0.8	14.4	246+00	102.2	38.9	86.9	83.1	3.8
217+00	226.9	0.0	192.9	0.0	192.9	246+50	86.9	39.8	73.9	101.9	-27.9
217+50	234.4	0.0	199.2	10.4	188.8	247+00	96.9	39.8	82.3	90.7	-8.4
218+00	77.0	0.0	65.4	6.2	59.3	247+50	124.7	39.8	106.0	65.9	40.1
218+16	179.0	0.0	152.2	6.0	146.1	248+00	139.4	39.8	118.4	40.9	77.5
218+50	287.8	0.0	244.6	0.0	244.6	248+50	78.0	19.6	66.3	10.0	56.3
219+00	326.2	0.0	277.3	0.0	277.3	248+74	100.5	21.7	85.5	5.4	80.0
219+50	329.4	0.0	279.9	0.0	279.9	249+00	187.8	41.7	159.6	10.6	149.0
220+00	23.6	0.0	20.0	0.0	20.0	249+50	157.8	41.7	134.1	11.7	122.4
220+04	57.1	0.0	48.6	0.0	48.6	250+00	139.9	41.7	118.9	11.6	107.3
220+14	206.1	0.0	175.2	0.0	175.2	250+50	45.6	14.2	38.7	3.3	35.4
220+50	174.2	0.0	148.1	0.9	147.1	250+67	89.8	28.1	76.4	4.7	71.7
220+84	68.4	0.0	58.2	0.6	57.6	251+00	196.9	43.5	167.4	3.2	164.2
221+00	134.1	0.0	114.0	5.6	108.4	251+50	104.5	39.4	88.8	0.2	88.6
221+35	52.4	0.0	44.6	3.4	41.2	251+93	0.0	3.4	0.0	0.0	0.0
221+50	80.5	0.0	68.4	6.4	62.0	252+00	0.0	0.0	0.0	0.0	0.0
221+75	77.5	0.0	65.9	7.0	58.9	252+50	0.0	0.0	0.0	0.0	0.0
222+00	153.5	0.0	130.5	15.1	115.4						
Totals							18,658.4	618.4	15,859.6	2,279.0	13,580.6

**SCHEDULE OF 6" CHAIN LINK FENCE
CEMETERY ROAD**

STATION	FROM	TO	LENGTH
198+45	204+25	0	
204+25	210+50	0	
210+50	216+50	0	
216+50	223+00	0	
223+00	229+50	300	
229+50	236+00	530	
236+00	242+50	650	
242+50	247+50	250	
247+50	253+00	0	
TOTAL			1730

**SCHEDULE OF CHAIN LINK FENCE RELOCATION
CEMETERY ROAD**

STATION	FROM	TO	LENGTH
198+45	210+45		
210+45	222+92		
222+92	235+40	875.0	
235+40	247+90	861.0	
247+90	253+00		
TOTAL			1,736.0

**SCHEDULE OF 4" UNDERDRAIN PIPE
CEMETERY ROAD**

STATION	FROM	TO	LENGTH
198+45	204+25	32.0	
204+25	210+50	176.0	
210+50	216+50	112.0	
216+50	223+00	228.0	
223+00	229+50	192.0	
229+50	236+00	128.0	
236+00	242+50	128.0	
242+50	247+50	192.0	
247+50	253+00	80.0	
TOTAL			1268.0

**STRUCTURES TO BE ADJUSTED
CEMETERY ROAD**

STATION	FROM	TO	CB	VV
198+45	204+25	2.0	4.0	
204+25	210+50	1.0	0.0	
210+50	216+50	0.0	1.0	
216+50	223+00	0.0	1.0	
223+00	229+50	1.0	0.0	
229+50	236+00	4.0	2.0	
236+00	242+50	3.0	0.0	
242+50	247+50	0.0	0.0	
247+50	253+00	1.0	4.0	
TOTAL			12.0	12.0

**SCHEDULE OF TREE REMOVAL
CEMETERY ROAD**

STATION	FROM	TO	6" TO 15"	15"+
198+45	210+45	24.0	200.0	
210+45	222+92	120.0	310.0	
222+92	235+40	18.0	391.0	
235+40	247+90	82.0	132.0	
247+90	253+00	0.0	265.0	
TOTAL			244.0	1298.0

**STRUCTURES TO BE RECONSTRUCTED
CEMETERY ROAD**

STATION	FROM	TO	MH	MH TY 1 FR	VV
198+45	204+25	0.0	0.0		
204+25	210+50	0.0	0.0	0.0	
210+50	216+50	0.0	0.0	0.0	
216+50	223+00	0.0	0.0	0.0	
223+00	229+50	0.0	0.0	0.0	
229+50	236+00	1.0	0.0	1.0	
236+00	242+50	0.0	0.0	0.0	
242+50	247+50	0.0	0.0	0.0	
247+50	253+00	1.0	0.0	0.0	