

CONTRACT NO. 60E99

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3					
40600300	AGGREGATE (PRIME COAT)	TON	14	14					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	21	21					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	619	619					
40600340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	759	759					
40603595	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	515	515					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	6701	6701					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	36	36					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	146	146					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5006	5006					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	58	58					
*78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	80	80					
*78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	468	468					
*78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	300	300					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	50	50					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50	50					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	29	29					

SUMMARY OF QUANTITIES			1000-2A		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	26	26					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	115	115					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	100	100					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37	37					
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	175	175					
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	230	230					
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	170	170					
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50					
78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	840	840					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	40	40					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	40	40					

* SPECIALTY ITEMS

Rev. 9-2-08
Rev. 7-22-08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 6/25/2008