

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	12	12			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.5	7.5			
40600300	AGGREGATE (PRIME COAT)	TON	37.6	37.6			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	982	982			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	318	318			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	257	257			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2019	2019			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	23401	23401			
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	1491	1491			
44004250	PAVED SHOULDER REMOVAL	SO YD	54	54			
44201725	CLASS D PATCHES, TYPE I, 7 INCH	SO YD	150	150			
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SO YD	450	450			
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SO YD	290	290			
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SO YD	239	239			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	11581	11581			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	48.4	48.4			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	54	54			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1248	1248			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15754	15754			

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	41	41			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15754	15754			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	41	41			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	329	329			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	245	245			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	256	256			
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	1	1			
* Specialty Items							