

	CODE NO.	DESCRIPTION	UNIT	TOTAL QTY	ROADWAY 1000-2A	Y030-1E	Y031-1F	100% NORTH CHICAGO Y060
*	X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	17,917			17,917	
*	X0323449	REMOVE EXISTING WATER VALVE	EACH	3				3
*	X0324636	WATER VALVE BOXES TO BE ABANDONED	EACH	22				22
*	X0350800	BOLLARDS	EACH	2		2		
	X4420500	TEMPORARY PAVEMENT PATCH	SQ YD	8,198	4,705			3,493
*	X5640175	FIRE HYDRANT COMPLETE	EACH	14				14
*	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	2			2	
*	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	2			2	
*	X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	17,917			17,917	
*	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,322			1,322	
*	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	832			832	
*	X8950115	RELOCATE LIGHT DETECTOR	EACH	2				2
*	X8950120	RELOCATE LIGHT DETECTOR AMPLIFIER	EACH	2				2
	XX001244	RETAINING WALL	FOOT	212	212			
*	XX002256	PLUG WATER MAIN, 6"	EACH	2				2
*	XX002982	GATE VALVES, 6"	EACH	2				2
*	XX003032	GATE VALVES, 12"	EACH	10				10
*	XX003338	TEST HOLE	EACH	65		65		
*	XX003516	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE)-8"	EACH	2				2
*	XX003517	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE)-6"	EACH	19				19
*	XX003553	VIDEO TRANSMISSION SYSTEM	EACH	2			2	
*	XX003662	ELECTRIC CABLE IN CONDUIT, VIDEO, NO. 20 3C	FOOT	314			314	
*	XX003803	SANITARY SEWER SERVICE 6"	FOOT	960				960
*	XX004051	LIGHT POLE, ORNAMENTAL	EACH	82		82		
*	XX004680	PEDESTRIAN SIGNAL HEAD, L.E.D., 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	14			14	
*	XX002356	REOPTIMIZE TRAFFIC SIGNAL SYSTEM	L SUM	1			1	

	CODE NO.	DESCRIPTION	UNIT	TOTAL QTY	ROADWAY 1000-2A	Y030-1E	Y031-1F	100% NORTH CHICAGO Y060
*	XX005107	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE)-12"	EACH	7				7
*	XX005280	DUCTILE IRON WATER MAIN, 8" (POLYETHYLENE WRAPPED)	FOOT	74				74
*	XX005485	STEEL CASING PIPE BORED AND JACKED 30"	FOOT	240				240
	XX005656	INLET FILTER CLEANING	FOOT	178	178			
*	XX005723	VIDEO DETECTION SYSTEM COMPLETE INTERSECTION	EACH	2			2	
*	XX005922	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 16 5-1/2 PAIR	FOOT	1,725			1,725	
*	XX005928	TRAFFIC SIGNAL POST, 10 FOOT, (SPECIAL)	EACH	1			1	
*	XX005931	TRAFFIC SIGNAL POST, 16 FOOT, (SPECIAL)	EACH	5			5	
*	XX005937	L.E.D. INTERNALLY ILLUMINATED STREET NAME SIGN	EACH	8			8	
*	XX005940	REMOTE CONTROLLED VIDEO SYSTEM	EACH	2			2	
*	XX006217	SANITARY SEWER SERVICE 8"	FOOT	60				60
*	XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	90		90		
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	45,530	45,530			
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
	Z0022800	FENCE REMOVAL	FOOT	1,087	1,087			
*	Z0044500	PRESSURE CONNECTION 6" X 6"	EACH	2				2
*	Z0045000	PRESSURE CONNECTION 12" X 6"	EACH	1				1
*	Z0045100	PRESSURE CONNECTION 12" X 12"	EACH	2				2
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
*	Z0056900	SANITARY SEWER 8"	FOOT	1,256				1,256
*	Z0057100	SANITARY SEWER 12"	FOOT	980				980
*	Z0057200	SANITARY SEWER 15"	FOOT	1,623				1,623

CONSTRUCTION TYPE CODE: * = SPECIALTY ITEM
(1) = Y080

REVISIONS	
NAME	DATE

Clorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014 Email: chicago@clorba.com

CITY OF NORTH CHICAGO
MARTIN LUTHER KING JR. DRIVE IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BWS
DATE: APRIL, 2008 CHECKED BY: MJL

DATE: 7/11/2008
TIME: 1:55:41 PM
FILENAME: N:\PROJ\05161\Design\Misc\Sheets\5161-SQC-05.dgn