

LOCATION	STATION	STAGE II						STAGE III							
		20200100	20200100		66900205	66900210	20201200	20200100	20200100		66900205	66900210	20201200		
		EARTH EXCAVATION (CU YD)	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	SPECIAL WASTE (CU YD)	HAZARDOUS WASTE (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	SPECIAL WASTE DISPOSAL (CU YD)	HAZARDOUS WASTE DISPOSAL (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)
	KRISTAN AVENUE	80	68	0	68	0	0	3	80	68	0	68	0	3	
	239+51 TO 240+00	20	17	0	17	0	0	0	16	13	0	13	0	0	
	240+00 TO 240+50	19	17	1	16	0	0	0	14	12	1	11	0	0	
	239+51 TO 240+00	19	16	1	15	0	0	0	14	12	1	11	0	0	
	240+00 TO 240+50	17	14	1	13	0	0	0	13	11	1	10	0	0	
	241+50 TO 241+93	16	14	2	12	0	0	0	10	8	2	7	0	0	
	HERVEY AVENUE	65	55	0	55	0	0	6	65	55	0	55	0	6	
	242+89 TO 243+00	6	5	0	5	0	0	0	6	5	0	5	0	0	
	243+00 TO 243+50	32	28	0	28	0	0	0	31	27	0	27	0	0	
	243+50 TO 244+00	40	34	0	34	0	0	0	39	33	0	33	0	0	
	244+00 TO 244+50	46	39	0	39	0	0	0	50	43	0	43	0	0	
	244+50 TO 245+00	49	42	0	42	0	0	0	55	46	0	46	0	0	
	245+00 TO 245+17	16	14	0	14	0	0	0	17	14	0	14	0	0	
	GROVE AVENUE	98	83	0	83	0	0	6	98	83	0	83	0	6	
	246+14 TO 246+50	21	18	1	17	0	0	0	21	18	0	18	0	0	
	246+50 TO 247+00	44	37	1	36	0	0	0	42	35	0	35	0	0	
	247+00 TO 247+50	54	46	1	45	0	0	0	44	37	0	37	0	0	
	247+50 TO 248+00	48	41	1	40	0	0	0	22	19	2	17	0	0	
	248+00 TO 248+50	30	25	1	24	0	0	0	6	6	9	-4	0	0	
	248+50 TO 248+53	1	1	0	1	0	0	0	0	0	1	-1	0	0	
	SEYMOUR AVENUE	36	31	0	31	0	0	8	36	31	0	31	0	8	
	249+35 TO 249+50	7	6	0	6	0	0	0	6	6	0	6	0	0	
	249+50 TO 250+00	33	28	0	28	0	0	0	34	29	0	29	0	0	
	250+00 TO 250+50	43	36	0	36	0	0	0	40	34	0	34	0	0	
	250+50 TO 251+00	42	35	1	34	0	0	0	44	37	0	37	0	0	
	251+00 TO 251+50	35	30	2	28	0	0	0	44	38	0	38	0	0	
	251+50 TO 252+00	34	29	1	28	0	0	0	39	33	0	33	0	0	
	252+00 TO 252+50	33	28	1	27	0	0	0	36	31	0	31	0	0	
	252+50 TO 253+00	34	29	2	27	0	0	0	35	30	0	30	0	1	
	253+00 TO 253+50	39	33	2	31	0	0	0	38	32	0	32	0	2	
	253+50 TO 254+00	44	37	1	36	0	0	0	38	32	0	32	0	2	
	254+00 TO 254+50	41	35	1	34	0	0	0	34	29	0	29	0	2	
	254+50 TO 255+00	31	26	3	23	0	0	0	31	26	0	26	0	2	
	255+00 TO 255+50	33	28	3	25	0	0	0	32	27	0	27	0	2	
	255+50 TO 256+00	39	33	2	31	0	0	0	38	32	0	32	0	2	
	256+00 TO 256+50	51	43	2	41	0	0	0	52	44	0	44	0	2	
	256+50 TO 257+00	65	55	1	54	0	0	0	65	55	0	55	0	2	
	257+00 TO 257+43	47	40	0	40	0	0	0	47	40	0	40	0	1	
	COMMONWEALTH	332	282	0	282	11	11	33	332	282	0	282	11	33	
	259+27 TO 259+50	0	0	1	-1	11	0	0	9	8	0	8	17	2	
	259+50 TO 260+00	1	1	1	0	25	0	0	10	9	0	9	40	0	
	260+00 TO 260+50	2	2	0	2	33	0	0	2	2	0	2	40	0	
	260+50 TO 261+00	2	2	0	2	46	0	0	2	2	0	2	46	0	
	261+00 TO 261+50	4	3	0	3	51	0	0	4	3	0	3	53	0	
	261+50 TO 262+00	28	24	0	24	25	0	0	3	2	0	2	49	0	
	262+00 TO 262+50	47	40	0	40	0	0	0	2	2	0	2	43	0	
	262+50 TO 263+00	44	38	0	38	0	0	0	5	4	0	4	21	0	
	263+00 TO 263+50	42	35	0	35	0	0	0	4	3	0	3	35	0	
	263+50 TO 264+00	37	31	0	31	0	0	0	0	0	1	-1	29	0	
	264+00 TO 264+50	35	30	0	30	0	0	0	3	2	1	3	0	0	
	264+50 TO 265+00	47	40	0	40	0	0	0	4	3	0	3	45	0	
	265+00 TO 265+50	58	50	0	50	0	0	0	5	4	0	4	58	0	
	265+50 TO 266+00	56	47	0	47	0	0	0	5	4	0	4	61	0	
	266+00 TO 266+50	49	42	0	42	0	0	0	2	2	1	1	53	1	
	266+50 TO 267+00	41	35	0	35	0	0	0	2	2	0	2	45	1	
	267+00 TO 267+41	29	24	0	24	0	0	0	1	1	0	1	0	1	
	TOTAL	2,259	1,920	31	1,888	202	11	55	1,723	1,464	22	1,442	435	318	77

DATE: 6/30/2008  
 TIME: 1:35:56 PM  
 FILENAME: N:\PROJ\5161\Design\MiscSheets\5161-Earthwork-02.dgn

REVISIONS	
NAME	DATE

**Ciorba Group, Inc.**  
 CONSULTING ENGINEERS  
 5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656  
 Tel. 773.775.4009 Fax 773.775.4014 Email chicago@ciorba.com

CITY OF NORTH CHICAGO  
 MARTIN LUTHER KING JR. DRIVE IMPROVEMENTS

SCHEDULE OF QUANTITIES  
 EARTHWORK

SCALE: N.T.S. DRAWN BY: JCC  
 DATE: APRIL, 2008 CHECKED BY: MJL