

CITY OF SULLIVAN STOCKPILE EXISTING AGGREGATE (Aggregate Removal 4" Depth in Parkway)		
LT or RT	Station to Station	CU YD
LT	145+13 - 146+34	4
RT	145+46 - 145+62	.5
RT	146+06.5 - 146+35.5	0.7
LT	146+40 - 146+53	0.5
LT	540+16 - 541+65	4
RT	540+66 - 541+72	5
LT	541+70 - 541+87	0.3
LT	110+41 - 112+16	6
RT	542+66 - 543+43	2
LT	542+79 - 543+37	2
LT	543+66 - 544+00	2
TOTAL		27

CITY OF SULLIVAN P.C.C. SIDEWALK 4", SPECIAL (STENCILED)		
LT or RT	Station to Station	Sq. Ft.
LT	138+15.6 - 138+34.5	95
RT	138+16 - 138+34.7	99
LT	138+99 - 139+02.9	16
LT	139+11.7 - 140+01	413
RT	139+14.8 - 139+73.9	276
RT	140+55.7 - 141+09.6	255
LT	140+64.9 - 141+18.6	250
RT	141+84.5 - 141+89.3	41
LT	141+96.5 - 142+85	409
RT	142+03 - 142+64.8	260
RT	143+10.4 - 143+97.8	384
LT	143+11.2 - 143+97.8	402
RT	90+28.5 - 90+33.6	23
RT	117+54.4 - 117+61.8	104
RT	117+66.8 - 118+55.7	546
RT	118+83.1 - 119+84.7	447
RT	543+95.3 - 544+11.6	27
LT	544+00 - 544+56.7	228
RT	544+51.1 - 544+56.1	7
RT	544+61.3 - 544+67.3	13
LT	544+62.2 - 544+65.9	5
LT	545+12.4 - 545+20.6	15
RT	545+11.8 - 545+39	81
LT	545+61 - 545+72.2	37
RT	545+96.9 - 546+40.8	123
LT	546+16 - 547+20.8	381
RT	547+01.3 - 547+13.7	32
RT	547+23.1 - 547+25.8	17
RT	547+79.2 - 547+89.8	56
RT	117+54.4 - 117+61.8	104
RT	117+66.9 - 118+55.7	546
RT	118+83.1 - 119+84.7	447
LT	145+13 - 146+34	337
RT	145+46 - 145+62	32
RT	146+06.5 - 146+35.5	55
LT	146+40 - 146+53	32
LT	540+16 - 541+65	341
RT	540+66 - 541+72	408
LT	541+70 - 541+87	18
RT	542+66 - 543+43	153
LT	542+79 - 543+37	185
LT	543+66 - 544+00	136
TOTAL		7834

CITY OF SULLIVAN DRAINAGE STRUCTURES											
No.	LT or RT	Distance Feet	Station	Existing Type Grate or Lid	Existing Lid or F.L. Elevation	Proposed Lid or F.L. Elevation	PAY ITEMS				
							Manhole Adjust	Inlet Adjust	Inlet W/T-11, F&G	Inlet Type A W/Type-11, F&G	Inlet Adjust w/Type 10 F&G
1	LT	23	138+85	Lid	669.23	669.23					1
2	RT	29	139+06	11	668.59	668.59					1
3	LT	25	139+14		670.09	670.09	1				
4	LT	24	141+11				1				
5	RT	32	141+21	11	671.55	671.55		1			
6	LT	32	141+32								
7	RT	23	144+46	11	673.79	673.79		1			
8	LT	24	144+56		674.34	674.12	1				
9	LT	21	144+58	11	673.73	673.73		1			
10	RT	26	544+53		674.49	674.49	1				
11	RT	22	544+62	11	674.14	674.14					
12	LT	24	544+64	11	673.94	673.94		1			
13	RT	23	547+16	11	671.69	671.69		1			
14	LT	23	547+28	11	671.65	671.65		1			
15	RT	25	547+93	15	671.62	671.62		1			
16	LT	30	119+63	9	671.54	671.54			1		
17	RT	28	119+59			671.78				1	
TOTAL							4	8	1	1	2

\*Elevations shown are for estimating purposes only. Actual elevation to be determined in the field.  
\*Inlet #6 does not need adjusted

Storm Sewers, Rubber Gasket, Class A, Type 1, 10"					
PT	Invert Elev.	PT	Invert Elev.	Length	Trench Backfill
17	668.78	15	667.93	17'	4 CY

CITY OF SULLIVAN DETECTIBLE WARNINGS AND RAMP SCHEDULE				
LT or RT	Station	Sq. Ft.	Ramp Type	A or B
LT	138+42	10	B	
RT	138+40	25	A	
LT	138+57	14	A & B	
LT	138+93	14	A & B	
LT	139+09	10	B	
RT	139+09	21	A	
RT	141+17	14	B	
LT	141+26	14	A & B	
LT	141+83	14	A	
LT	141+91	10	A & B	
RT	141+94	20	A & B	
RT	144+04	24	A	
LT	144+05	25	A & B	
RT	144+43	13	A	
LT	144+48	16	A & B	
RT	144+50	10	A	
RT	544+59	10	A & B	
LT	544+59	12	A	
RT	544+67	14	A & B	
LT	544+68	14	A	
RT	545+05	16	A & B	
LT	545+05	14	A & B	
RT	547+22	10	B	
LT	547+23	10	A & B	
LT	547+32	12	A	
LT	547+91	16	A	
RT	548+04	16	A	
RT	117+55	10	A & B	
RT	117+65	12	B	
RT	119+68	12	A & B	
TOTAL		432		

CITY OF SULLIVAN COMBINATION CONCRETE CURB & GUTTER TYPE B-6.12		
LT or RT	Station to Station	Feet
RT	117+55 - 118+61.9	140
RT	118+78.6 - 119+77.1	148
TOTAL		288

CITY OF SULLIVAN SURFACE REMOVAL		
LT or RT	Station to Station	Sq. Ft.
LT	138+16 - 138+57.3	347
LT	138+92.5 - 141+25.9	1273
RT	139+19 - 141+21.3	1094
RT	141+88.6 - 142+71.5	507
RT	143+05.6 - 144+07.7	620
RT	142+71 - 143+05	155
LT	141+81.5 - 142+89.6	703
LT	143+06 - 144+08	511
LT	144+45 - 144+75	163
LT	145+06.5 - 145+52	100
RT	144+40 - 145+23	482
RT	145+40 - 145+64	132
LT	543+89.1 - 544+70.2	446
RT	543+91 - 544+12.5	125
RT	544+50.2 - 544+65	93
RT	545+01.8 - 545+48.8	172
LT	545+02.4 - 545+21.2	89
LT	545+57 - 545+76.4	97
RT	545+88.3 - 546+49.6	242
LT	546+12 - 547+32	588
RT	546+92.6 - 547+25.7	230
LT	547+91.6 - 548+03	90
RT	117+53 - 118+63	1162
RT	118+77 - 119+80	997
LT	145+14 - 145+52	135
RT	145+47 - 145+62	32
LT	544+62 - 544+65	4
LT	546+14 - 547+27	483
RT	117+53 - 118+45	550
RT	118+87 - 119+80	560
RT	118+69.5	254
RT	140+14	641
LT	140+35	660
RT	142+79 - 142+92	60
RT	142+73 - 142+79	295
LT	110+70-112+06	680
RT	117+53-119+80	300
RT	117+70-119+48	178
TOTAL		15,250

CITY OF SULLIVAN PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"		
LT OR RT	STATION TO STATION	SQ YD
LT	140+04.5 - 140+62.6	63
RT	139+82.9 - 140+46.8	70
RT	142+71.5 - 143+06	37
RT	118+61.5 - 118+79.1	28
TOTAL		198

CITY OF SULLIVAN PORTLAND CEMENT CONCRETE SIDEWALK, 4"		
LT or RT	Station to Station	Sq. Ft.
LT	138+15.6 - 138+58.2	348
RT	138+16.7 - 138+45.5	172
LT	138+90.3 - 140+04.5	654
RT	139+08.2 - 139+82.9	382
RT	140+46.8 - 141+21.5	465
LT	140+62.6 - 141+29.2	351
LT	141+80.8 - 142.88.8	654
RT	141+87.9 - 142+71.5	500
LT	143+05 - 144+08.1	545
RT	143+06 - 144+08.8	601
RT	144+40.7 - 145+21.5	490
LT	144+45.8 - 144+73.6	161
LT	145+07.4 - 145+51.8	208
RT	145+40 - 145+64.5	124
RT	543+88.7 - 544+12.8	132
LT	543+89 - 544+69.2	450
RT	544+51.6 - 544+67.7	165
RT	545+01.5 - 545+50	248
LT	545+02.2 - 545+21.7	116
LT	545+56.7 - 545+75.5	134
RT	545+87.3 - 546+52.3	352
LT	546+11.7 - 547+33.8	661
RT	546+92.4 - 547+25	228
LT	547+88.9 - 548+02.6	75
RT	117+55.4 - 118+61.5	706
RT	118+79.1 - 119+74.4	587
TOTAL		9,509

CITY OF SULLIVAN SCHEDULE OF SIGN REPLACEMENT							
EXISTING LOCATION	LT OR RT	DESCRIPTION	PROPOSED LOCATION SIGN POST	PROPOSED LOCATION LIGHT POLE	LT OR RT	POLE #	MOUNTING HEIGHT
138+99.77	23.90 LT	Jefferson Street Under Hamilton Street Over	138+99.77		23.90 LT		7
139+17.05	21.39 RT	Speed Limit 30 30"x36"	**	139+55	22.00 RT	9	8
139+57.25	21.39 RT	No Parking (anytime) R7-100-18		139+55	22.00 RT	9	6
139+53.55	23.60 LT	Little Theatre on the Square 48" x 18"		139+55	22.00 LT	7	7
90+30.87	31.26 LT	Stop Sign R1-1-36"	**	90+30.87	31.26 LT		7
138+53.39	33.27 LT	Stop Sign R1-1-36"	**	138+53.39	32.27 LT		7
141+02.79	21.89 LT	No Parking (anytime) R7-100-18		141+05	22.00 LT	19	7
141+28.15	32.23 LT	Stop Sign R1-1-36"	**	141+28.15	32.23 LT		7
141+84.90	32.36 LT	Harrison Street Under Hamilton Street Over	141+84.90		32.36 LT		POST TOP
142+07.92	22.96 LT	Business District		142+05	22.00 LT	20	7
141+86.96	46.39 RT	Stop Sign R1-1-36"	**	141+86.96	46.39 RT		7
142+82.71	22.87 LT	Fire Station Warning 36" x 36"		142+60	22.00 LT	21	6
143+19.39	21.66 RT	No Parking (anytime) R7-100-18		143+15	22.00 RT	14	7
143+88.75	21.53 RT	School Warning S3-2-36		143+55	22.00 RT	15	7
143+96.31	23.04 RT	Monroe Street Under Hamilton Street Over		143+95	22.00 RT	16	POST TOP
143+99.12	23.61 LT	No Parking (anytime) R7-100-18		143+95	22.00 RT	16	7
144+07.16	32.53 LT	Stop Sign R1-1-36"	**	144+07.16	32.53 LT		7
144+95.32	22.10 RT	Lincoln Trail		145+06	22.00 RT	17	7
144+42.65	33.51 RT	Stop Sign R1-1-36"	**	144+42.65	33.51 RT		7
546+12.94	23.89 RT	Library Direction 24" x 24"	**	546+35	23.19 RT	38	7
544+54.03	21.92 LT	No Parking R7-100-18		544+54	22.00 LT	29	7
544+66.71	31.49 LT	Stop Sign R1-1-36"	**	544+66.71	31.49 LT		7
546+15.60	22.78 LT	School Crossing S3-2-36		546+25	22.13 LT	26	7
545+06.84	30.48 LT	Van Buren Street Under Jackson Street Over Main Street Under	545+06.84		30.48 LT		POST TOP
547+98.45	22.84 LT	Jackson Street Over		547+96	22.96 LT	35	POST TOP
548+02.60	23.03 LT	Sullivan Schools 24" x 18"		547+96	22.96 LT	35	7
119+70.81	35.36 RT	Stop Sign R1-1-36"	**	119+62.27	20.02 RT		7
118+14.22	33.05 RT	Handicap Parking		118+14.22	33.05 RT		7
117+62.96	33.61 RT	Monroe Street Under Main Street Over	117+58.08		27.08 RT		POST TOP
117+58.08	40.28 RT	Stop Sign R1-1-36"	**	117+58.08	40.28 RT		7
TOTAL			14				

\*The Contractor must measure all the signs before ordering the sign brackets to coordinate the size.  
\*\* The Contractor shall coordinate these sign measurement with the Illinois Department of Transportation Traffic Department. IDOT is providing these signs.