

ADA  
INDEX OF SHEETS

SHEET NO.	ITEM
1	ADA BILL OF MATERIALS AND NOTES
2-3	SCHEDULE OF QUANTITIES
4-5	CONTROL POINTS
6-22	ADA SIDEWALK PLAN (FREEBURG)
23-25	CONSTRUCTION DETAILS ADA SIDEWALK (FREEBURG)

ADA  
GENERAL NOTES

- ALL EXISTING RIGHT OF WAY LINES SHOWN ON THE PLAN SHEETS ARE GRAPHICAL REPRESENTATIONS AND SHALL NOT BE USED AS A MEANS TO ESTABLISH OWNERSHIP. IN ALL MATTERS RELATING TO RIGHT OF WAY, THE PLAT OF HIGHWAYS SHALL BE THE CONTROLLING DOCUMENT.
- ALL TURF AREAS ADJACENT TO THE PROPOSED SIDEWALK CONSTRUCTION SHALL HAVE CLEAN EARTHEN BACKFILL MATERIAL PLACED AND SHALL BE FERTILIZED, SEEDED WITH CLASS 1A SEED MIXTURE AND MULCHED. THERE IS AN ESTIMATED QUANTITY OF 0.05 ACRE OF SEEDING REQUIRED FOR TURF RESTORATION IN THE PROPOSED SIDEWALK CONSTRUCTION AREAS.
- EARTH EXCAVATION WILL BE REQUIRED FOR CONSTRUCTION OF THE IMPROVEMENTS.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- ALL CURB AND GUTTER SHALL BE CONSTRUCTED IN ACCORDANCE WITH HIGHWAY STANDARD 606001 UNLESS SHOWN OTHERWISE.
- SIDEWALK CLOSURE:

THE CONTRACTOR SHALL PROVIDE FOR THE SAFE ACCOMMODATION OF PEDESTRIAN TRAFFIC THROUGH THE WORK ZONE DURING CONSTRUCTION. THE CONTRACTOR SHOULD PLAN HIS/HER CONSTRUCTION SO THE DISRUPTION TO THE PEDESTRIAN FACILITIES WILL OCCUR IN THE SHORTEST PRACTICAL TIME POSSIBLE. IF SIDEWALKS ARE TO BE CLOSED FOR MORE THAN 5 CONTINUOUS DAYS, TEMPORARY SIDEWALK SHALL BE CONSTRUCTED, AS DIRECTED BY THE ENGINEER AND IN COMPLIANCE WITH HIGHWAY STANDARD 701801.

HIGHWAY STANDARDS

- 000001 - STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 420001 - PAVEMENT JOINTS
- 424001 - PERPENDICULAR CURB RAMPS FOR SIDEWALKS
- 424006 - DIAGONAL CURB RAMPS FOR SIDEWALKS
- 424011 - CORNER PARALLEL CURB RAMPS FOR SIDEWALKS
- 424016 - MID-BLOCK CURB RAMPS FOR SIDEWALKS
- 424021 - DEPRESSED CORNER FOR SIDEWALKS
- 424031 - MEDIAN PEDESTRIAN CROSSINGS
- 606001 - CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
- 606301 - PC CONCRETE ISLANDS AND MEDIANS
- 701501 - URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
- 701502 - URBAN LANE CLOSURE, 2L, 2W, WITH BIDIRECTIONAL LEFT TURN LANE
- 701801 - SIDEWALK, CORNER OR CROSSWALK CLOSURE
- 701901 - TRAFFIC CONTROL DEVICES



**BENTON & ASSOCIATES, INC.**  
Consulting Engineers / Land Surveyors  
1970 West Lafayette Ave. Jacksonville, IL 62650  
Phone: 217-245-4146 Fax: 217-245-4149  
IL Design Firm Registration No. 184-000852



WILLIAM J. SLEEMAN  
DATE 2/25/19  
LICENSE EXPIRES 11-30-2019  
SHEET RANGE 52-76

BILL OF MATERIAL

CODE NUMBER	ITEM	UNIT	ADA QUANTITY
35101400	AGGREGATE BASE COURSE, TYPE B	TON	9
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	2489
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	128
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	407
40600990	TEMPORARY RAMP	SQ YD	407
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	310
40800050	INCIDENTAL HOT-MIX SURFACING	TON	2
42000400	PORTLAND CEMENT CONCRETE PAVEMENT 9"	SQ YD	12
42400800	DETECTABLE WARNINGS	SQ FT	624
44000100	PAVEMENT REMOVAL	SQ YD	49
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	3542
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	23
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	942
44000600	SIDEWALK REMOVAL	SQ FT	7127
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2
60300405	VALVE BOXES FRAMES TO BE ADJUSTED	EACH	6
60604500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (ABUTTING EXISTING PAVEMENT)	FOOT	815.5
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	107.0
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	18
X4230710	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH, SPECIAL	SQ YD	20
X4240420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	8261
X4240440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	83
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	146
X6060068	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL) (ABUTTING EXISTING PAVEMENT)	FOOT	46.5
Z0007430	TEMPORARY SIDEWALK	SQ FT	1782
Z0012455	CONCRETE STEP REMOVAL	EACH	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1

ADA SIDEWALK (FREEBURG)

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>ADA BILL OF MATERIALS AND NOTES FAP ROUTE 103 (IL RTE 13 /15)</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
P:\1062166-34\FAP 103 (IL 13-IL 15) Sec 02	25,38,561RS 76J16\CADD Sheets\0876J16-sh1-drawn-500.dgn	MGM				103	(27,25,38,56)RS	ST. CLAIR	87	52	
Default	PLOT SCALE = 48.0000' / in.	CHECKED - WJS	REVISED -			CONTRACT NO. 76J16					
	PLOT DATE = 2/14/2019	DATE - 2/2019	REVISED -			SCALE:	SHEET 1 OF 25 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	