	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					ROADWAY	BRIDGE	
					0004	0010	
					RURAL	S.N. 048-0095	
					KNOX	KNOX	
*	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4138	4138		
*	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	12	12		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	16		
*	78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	9	9		
*	78200010	BARRIER WALL REFLECTORS, TYPE B	EACH	4	4		
	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2903	2903		
	X4810200	AGGREGATE SHOULDER REMOVAL	CU YD	14	14		
	58600101	GRANULAR BACKFILL FOR STRUCTURES	CU YD	70		70	
	X6060097	CLASS SI CONCRETE (OUTLET), SPECIAL	CU YD	25	25		
	X6062700	CONCRETE GUTTER, TYPE A (SPECIAL)	FOOT	830	830		
	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
	Z0001002	GUARDRAIL AGGREGATE EROSION CONTROL	TON	218	218		
	Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	24		24	
	Z0004638	PAVEMENT BREAKING	SQ YD	634	634		

*= SPECIALTY ITEM