



* CONCRETE GUTTER, TYPE A (SPECIAL)
 HMA SHOULDERS (8")
 POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50, 1 1/2"
 POLYMERIZED HMA LEVELING BINDER, (MACHINE METHOD) N50, 3/4"
 HMA SURFACE REMOVAL (VARIABLE DEPTH)
 PG
 * CONCRETE GUTTER, TYPE A (SPECIAL)
 HMA SHOULDERS (8")
 PAINT PAVEMENT MARKING LINE, 4" (TYPICAL ALL)
 TOPSOIL FURNISH AND PLACE, 4", SEEDING CLASS 2A, EROSION CONTROL BLANKET

* SEE PLAN AND SCHEDULES FOR STATIONS OF GUTTER AND CLASS 'SI' CONCRETE OUTLET

PROPOSED TYPICAL ROADWAY SECTION (MILL AND OVERLAY)

LT STA 1429+05 TO STA 1431+75
 RT STA 1429+50 TO STA 1431+75
 NOT TO SCALE

FEHR GRAHAM ILLINOIS
 ENGINEERING & ENVIRONMENTAL IOWA
 WISCONSIN
ILLINOIS DESIGN FIRM NO. 184-003525

| | | | |
|---|------------------------------|------------|-----------|
| FILE NAME = | USER NAME = jacobsmr | DESIGNED - | REVISED - |
| p:\planroom\dot.illinois.gov\PIDOT\Documents\IDOT Offices\District 4\Projects\04.68758\to\CAD\Sheets\Fehr_Graham - IDOT | | | |
| Default | PLOT SCALE = 100.0000' / in. | CHECKED - | REVISED - |
| FEHR GRAHAM PROJECT NUMBER: 09004-3 | PLOT DATE = 5/9/2019 | DATE - | REVISED - |

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

| | |
|---|--|
| TYPICAL SECTIONS ILLINOIS ROUTE 78 | |
| SCALE: | SHEET 3 OF 3 SHEETS STA. 1429+05.00 TO STA. 1431+75.00 |

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|--|---------------|--------|--------------|-----------|
| 22 | 48(B-1)BR(CR) | KNOX | 94 | 13 |
| CONTRACT NO. 68758 | | | | |
| <small>ILLINOIS FED. AID PROJECT</small> | | | | |