

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
502	54BR-1	ADAMS	28	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	% FEDERAL		% STATE	
					X080-2A	CONSTRUCTION AND SAFETY TYPE CODE		
* 78001120	PAINT PAVEMENT MARKING - LINE 5"		FOOT	1600	1600			
* 78001180	PAINT PAVEMENT MARKING - LINE 24"		FOOT	18	18			
* 78200410	GUARDRAIL MARKERS, TYPE A	✓	EACH	10	10			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	✓	EACH	4	4			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	✓	SQ FT	50	50			
X5030305	CONCRETE WEARING SURFACE, 5"	✓	SQ YD	157	157			
X7200201	WIDTH RESTRICTION SIGNING	✓	L SUM	1	1			
* XX005496	TRAFFIC BARRIER TERMINAL TYPE 6A (SPECIAL)	✓	EACH	1	1			
Z0001900	ASBESTOS BEARING PAD REMOVAL	✓	EACH	24	24			
Z001379B	CONSTRUCTION LAYOUT	✓	L SUM	1	1			
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	✓	EACH	2	2			
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	✓	EACH	2	2			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	✓	EACH	2	2			
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	✓	EACH	2	2			
Z0073500	TEMPORARY SUPPORT SYSTEM	✓	L SUM	1	1			

\* SPECIALTY ITEMS

PLOT DATE = 7/2/2007  
 PLOT TIME = 10:55:59 AM  
 PLOT SCALE = 1/8"=1'-0"

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 FAP 502 (IL 57)  
 SECTION 54BR-1  
 ADAMS COUNTY

SCALE: VERT. NONE  
 HORIZ. NONE  
 DATE 6/28/2007

DRAWN BY SEB  
 CHECKED BY EBB