

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
502	54BR-1	ADAMS	28	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

GUARDRAIL SCHEDULE

LOCATION	63000000	63100087	63100167	63100169	XX005496	78201000	78200410
	STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL TYPE 6A	TRAFFIC BARRIER TERMINAL TYPE 1, SP (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 1, SP (FLARED)	TRAFFIC BARRIER TERMINAL TYPE 6A (SPECIAL)	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL MARKERS, TYPE A
	FOOT	EACH	EACH	EACH	EACH	EACH	EACH
STA 112+60.2 TO STA 113+10.2 LT	-	-	1	-	-	1	3
STA 113+10.2 TO STA 114+22.7 LT	112.5	-	-	-	-	-	
STA 114+22.7 TO STA 114+67.9 LT	-	1	-	-	-	-	
STA 112+62.1 TO STA 113+12.1 RT	-	-	-	1	-	1	3
STA 113+12.1 TO STA 113+99.6 RT	87.5	-	-	-	-	-	
STA 113+99.6 TO STA 114+44.8 RT	-	1	-	-	-	-	
STA 114+82.1 TO STA 115+17.9 RT	-	-	-	-	1	-	2
STA 115+17.9 TO STA 115+67.9 RT	-	-	-	1	-	1	
STA 115+05.2 TO STA 115+50.4 LT	-	1	-	-	-	-	2
STA 115+50.4 TO STA 115+94.2 LT	43.8	-	-	-	-	-	
STA 115+94.2 TO STA 116+44.2 LT	-	-	-	1	-	1	
TOTALS:	243.8	3	1	3	1	4	10

REMOVAL SCHEDULE

LOCATION		44000100	44000155	44000200	44004250
		PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	DRIVEWAY PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL
		SO YD	SO YD	SO YD	SO YD
112+00.0 TO 114+17.6	LT	-	460.7	-	123.8
	RT	-	376.8	-	47.9
114+17.6 TO 114+53.6	LT	59.2	-	-	8.2
	RT	62.5	-	-	-
114+90.4 TO 115+26.4	LT	58.8	-	-	5.1
	RT	60.6	-	-	-
115+26.4 TO 119+10.0	LT	-	845.6	-	252.2
	RT	-	681.2	30.8	95.2
TOTALS:		241	2364	31	532

PAVING SCHEDULE

LOCATION		31100300	35501324	25000400	40600200	40600300	40603540	42001400	42001430	48101200
		SUB-BASE GRANULAR MATERIAL, TYPE A 4"	HOT-MIX ASPHALT BASE COURSE, 10"	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLY HOT-MIX ASPHALT SURFACE, MIX "D", N70	BRIDGE APPROACH PAVEMENT (SPECIAL)	BRIDGE APPROACH PVMT CONNECTOR (FLEXIBLE)	AGGREGATE SHOULDERS, TYPE B
		SO YD	SO YD	SO YD	TON	TON	TON	SO YD	SO YD	TON
112+00.0 TO 114+17.6	LT	-	107.9	32.0	0.2	0.9	38.7	-	-	2.8
	RT	-	-	69.1	0.2	0.8	31.7	-	-	15.9
114+17.6 TO 114+53.6	LT	53.0	-	-	-	-	-	55.0	11.0	1.5
	RT	53.0	-	-	-	-	-	55.0	11.0	0.8
114+90.4 TO 115+26.4	LT	53.0	-	-	-	-	-	55.0	11.0	0.7
	RT	53.0	-	-	-	-	-	55.0	11.0	1.6
115+26.4 TO 119+10.0	LT	-	204.5	38.7	0.3	1.7	70.9	-	-	4.2
	RT	-	-	129.2	0.3	1.5	57.2	-	-	9.5
TOTALS:		212	312	269	1.0	4.9	199	220	44	37

EARTHWORK SCHEDULE

LOCATION		20200100	20200500
		EARTH EXCAVATION	EARTH EXCAVATION (WIDENING)
		CU YD	CU YD
112+00 TO 114+27 LT		-	10.8
NORTH APPROACH LT		7.5	-
SOUTH APPROACH LT		7.5	-
115+41 TO 119+10 LT		-	18.8
112+00 TO 114+08 RT		-	36.0
NORTH APPROACH RT		7.5	-
SOUTH APPROACH RT		7.5	-
115+23 TO 119+10 RT		-	69.6
TOTALS:		30	135

SEEDING SCHEDULE

LOCATION		25000200	25000300	25000400	25000500	25000600	25000700	25100105	28000250
		SEEDING, CLASS 2	SEEDING, CLASS 3	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 1	TEMPORARY EROSION CONTROL SEEDING
		ACRE	ACRE	POUND	POUND	POUND	TON	ACRE	POUND
112+00 TO 114+63 LT		0.06	-	5.4	5.4	5.4	0.12	0.06	6
114+63 TO 1115+13 LT		-	0.05	4.5	4.5	4.5	0.10	0.05	5
115+13 TO 119+10 LT		0.09	-	8.1	8.1	8.1	0.18	0.09	9
112+00 TO 114+39 RT		0.05	-	4.5	4.5	4.5	0.10	0.05	5
114+39 TO 114+85 RT		-	0.05	4.5	4.5	4.5	0.10	0.05	5
114+85 TO 119+10 RT		0.10	-	9.0	9.0	9.0	0.20	0.10	10
TOTALS:		0.3	0.1	36	36	36	0.8	0.4	40

TEMPORARY RAMP SCHEDULE

LOCATION	20200100
	TEMPORARY RAMP
	SO YD
STA 112+00	20.2
NORTH BRIDGE APPROACH	22.1
SOUTH BRIDGE APPROACH	22.1
STA 119+10	20.0
SOUTH 12TH STREET	20.4
TOTALS:	105

PAVEMENT STRIPING SCHEDULE

LOCATION		78001120	78001180	70300100	70300230	70300280	70300280
		PAINT PAVEMENT MARKING - LINE 5"		SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 5"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL
		WHITE	YELLOW	FOOT	FOOT	FOOT	SO FT
112+00.0 TO 119+10.0	LT	-	710	18	-	710	18
	RT	180	-	-	72	180	-
	RT	-	710	-	-	710	-
STAGE CONSTRUCTION		-	-	-	-	-	1482.5
TOTALS:		1600	18	72	1600	18	2209

ENTRANCE SCHEDULE

LOCATION		40200100	40800050
		AGGREGATE SURFACE COURSE, TYPE A	INCIDENTAL HOT-MIX ASPHALT SURFACING
		TON	TON
112+37.5 RT	AGG CE	10.0	10.9
115+90.4 RT	BIT PE	20.0	12.5
116+47.3 RT	AGG PE	17.0	4.0
TOTALS:		47	27

GUARDRAIL REMOVAL SCHEDULE

LOCATION		63200310
		GUARDRAIL REMOVAL
		FOOT
112+64 TO 114+42 RT		178
113+62 TO 114+65 LT		103
114+84 TO 115+63 RT		79
115+07 TO 116+10 LT		103
TOTALS:		463

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 502 (IL 57)
 SECTION 54BR-1
 ADAMS COUNTY

SCALE: VERT. NONE
 HORIZ. 6/28/2007
 DATE: 6/28/2007

DRAWN BY: SEB
 CHECKED BY: EBB

PLOT DATE = 7/2/2007
 PLOT SCALE = 1/8"=1'-0"
 PLOT SIZE = 18" x 24"