

EARTHWORK QUANTITIES				
LOCATION	THEORETICAL		FURNISHED EXCAVATION SHORTAGE (-) OR EXCESS (+)	REMARKS
	CUT	FILL		
	CU YD	CU YD	CU YD	
			[(A)0.75]-(B)	
	(A)	(B)	(C)	
15+80.6 TO 17+05	50	1752	-1715	
TOTAL	50	1752	-1715	
	PAY ITEM	INFO ONLY	PAY ITEM	

PAVEMENT SCHEDULE		
LOCATION (STA. TO STA.)	AGGREGATE BASE COURSE, TYPE A, 12"	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"
15+88.13 TO 17+05.00	495	427
TOTAL	495	427

PORTLAND CEMENT CONCRETE SIDEWALK, 4"	
LOCATION (STA. TO STA.)	SQ FT
16+04.00 TO 17+14.06	544
TOTAL	544

COMBINATION CURB AND GUTTER REMOVAL	
LOCATION (STA. TO STA.)	FOOT
15+88.13 TO 16+02.97 LT.	15
16+97.49 TO 17+05.00 LT.	8
15+88.13 TO 16+11.20 RT.	23
16+88.15 TO 17+05.00 RT.	17
TOTAL	63

COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12	
LOCATION (STA. TO STA.)	FOOT
15+88.13 TO 16+98.36 LT.	114
16+98.36 TO 17+05.00 LT.	4
15+88.13 TO 17+05.00 RT.	117
TOTAL	235

PAVEMENT REMOVAL	
LOCATION (STA. TO STA.)	SQ YD
15+88.13 TO 16+15.90	75
16+78.13 TO 17+05.00	107
TOTAL	182

SIDEWALK REMOVAL	
LOCATION (STA. TO STA.)	SQ FT
16+03.98 TO 16+15.72 RT.	66
16+88.15 TO 17+14.06 RT.	120
TOTAL	186