

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004 FED. 90% STATE 10%					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004 FED. 90% STATE 10%					
20200100	EARTH EXCAVATION	CU YD	391	391					35501317	HOT-MIX ASPHALT BASE COURSE, B 1/4"	SO YD	1115	1115					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	162	162					40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	9					
20400800	FURNISHED EXCAVATION	CU YD	216	216					40600300	AGGREGATE (PRIME COAT)	TON	42	42					
20800150	TRENCH BACKFILL	CU YD	42	42					40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	16	16					
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	586	586					40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	427	427					
25000210	SEEDING, CLASS 2A	ACRE	0.45	0.45					40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	41	41					40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	126	126					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	41	41					40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	19	19					
25100630	EROSION CONTROL BLANKET	SQ YD	2196	2196					40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1014	1014					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	45	45					44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	9230	9230					
28000305	TEMPORARY DITCH CHECKS	FOOT	192	192					44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	226	226					
28000315	AGGREGATE DITCH CHECKS	TON	8	8					44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2-1/2"	SO YD	136	136					
28000400	PERIMETER EROSION BARRIER	FOOT	1428	1428														
28000510	INLET FILTERS	EACH	2	2														
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	1739	1739														
* SPECIALTY ITEM									* SPECIALTY ITEM									