

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE	0005 50% CITY WHITE HALL 50% STATE	0005 50% CITY ROODHOUSE 50% STATE
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	429	429		
20800150	TRENCH BACKFILL	CU YD	6	6		
28000400	PERIMETER EROSION BARRIER	FOOT	25	25		
28000500	INLET AND PIPE PROTECTION	EACH	1	1		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	70	60	5.3	4.7
40600300	AGGREGATE (PRIME COAT)	TON	338	291	25	22
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4668	4024	330	314
40600990	TEMPORARY RAMP	SQ YD	1637	1637		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9865	8531	706	628
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	112684	96815	8395	7474
44200156	PAVEMENT PATCHING, TYPE II, 13"	SQ YD	60	60		
44200162	PAVEMENT PATCHING, TYPE IV, 13"	SQ YD	32	32		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	586	586		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE	0005 50% CITY WHITE HALL 50% STATE	0005 50% CITY ROODHOUSE 50% STATE
48203100	HOT-MIX ASPHALT SHOULDERS	TON	89	89		
50105220	PIPE CULVERT REMOVAL	FOOT	56	56		
54215763	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2	2		
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	66	66		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	9684	9684		