F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	•	COOK	312	13
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
60A62	• (1919.15, 2021-922 PT1 & PT2) R-1			

SUMMARY OF QUANTITIES

					90% FEDERAL / 10% STATE									
					URBAN ROADWAY	RETAINING WALL		BRIDGE		SIGNING	SAFETY	LIGHTING	SURVEILLANCE	CDOT LIGHTING
						O16-W923	O16-W931	STR NO 016-0142	STR NO 016-1148					
	CODE NO.	ITEM	UNIT	QUANTITY	J000	Y007	Y007	SFTY-2A	SFTY-2A	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y030-1E
•	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4							4			
•	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1							1			
	Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	1,017	1,017									
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1									
⊙	Z0076600	TRAINEES	HOUR	1500	1500	△1								
•	X0325499	AERIAL CABLE, 2 1/C NO. 4	FOOT	150										150
•	X0325491	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., SCH. 80 PVC	FOOT	653										653
•	X0325492	CONVENTIONAL STREET LIGHTING UNIT WALL MOUNTED, INSTALL ONLY	EACH	8										8
•	X0325494	GALVANIZED STEEL CONDUIT IN TRENCH, 2" DIA., SCH. 40	FOOT	25										25
•	80700110	GROUND ROD, 3/4" DIA. X 10 FT.	EACH	8										8
•	X0325500	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, TYPE J	EACH	2									2	
▲2 •	X0324223	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1										1
•	X0945500	PAINT EXISTING POLE COMPLETE	EACH	8										8
•	X0325495	REMOVE EXISTING STREET LIGHTING UNIT AND SALVAGE	EACH	9										9
•	X0324901	REMOVE EXISTING STREET LIGHTING FOUNDATION	EACH	9										9
•	X0325496	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	25										25
•	X0325493	CABLE IN CONDUIT, TRIPLEX, 2-1/C NO. 6 AND 1-1/C NO. 8 GND.	FOOT	840										840
	X0325501	FABRIC REINFORCED ELASTOMERIC MAT	SQ FT	63			63							
	X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	15					15					
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	993				458	535					
	X0325498	DUCTILE IRON PIPE	FOOT	143	143									
	X0325502	MEDIAN BARRIER GATE SYSTEM	EACH	1	1									
	X0325503	REMOVAL OF EXISTING TEMPORARY SOIL RETENTION SYSTEM	FOOT	926	926									
	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	4,500	4,500									
	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1									
△1	66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2									

⊙ Y080

• DENOTES SPECIALTY ITEMS

CTE | AECOM

△2 Rev. 9-11-06

△1 Rev. 8-21-06

S00-7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: June 9, 2006 CHECKED BY: RMG

6/6/2006 9:38:43 AM

P:\PROJECTS\ILTIS\cntrs 18 & 19\contract 1\sum\general\S16\S00720.dgn