

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032 BY	WILL	805	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
		S00-08 OF 8		

CODE NO.	ITEM	UNIT	URBAN STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE																
				ROADWAY Sta. 573+00.00 to Sta. 789+00.00 1000-2A	US 30 Sta. 587+80.82 X231-2A	EJ&E SB Sta. 608+37.25 X171-5B	EJ&E NB Sta. 608+37.25 X171-5B	MINK Sta. 630+09.46 X020-2A	RENWICK Sta. 631+48.98 SFTY-2A	MS Sta. 710+34.50 X131-2A	LILLY CACHE Sta. 773+45.67 X020-2A	RTE 126 Sta. 781+12.54 SFTY-2A	LIGHTING Sta. 573+00.00 to Sta. 789+00.00 Y030-1E							
X6050700	REMOVE INLET BOX	EACH	8	8																
X6370905	BARRIER BASE	FOOT	11,700	11,700																
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	11,518	11,518																
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	12	12																
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1																
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	274	274																
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	7	7																
* X8160370	UNIT DUCT, WITH 3-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	410																	410
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	61,315	61,315																
Z0002600	BAR SPLICERS	EACH	3,020		1,406	1,192	190				232									
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1																
△ Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE NARROW), TEST LEVEL 3	EACH	4	4																
△ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	12	12																
△ Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	10	10																
△ Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	10	10																
△ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	13	13																
Z0047300	PROTECTIVE SHIELD	SQ YD	1,597		998	470	129													
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HR</del>	<del>1,000</del>	<del>1,000</del>																
X0325561	CULVERTS TO BE GROUTED	CU YD	26	26																
X8110145	CONDUIT ATTACHED TO STRUCTURE, 1" DIA, RIGID GALVANIZED STEEL PVC COATED	FOOT	320																	320
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	390		20	73	18	10	91										178	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	5		5															
△ X0325562	BITUMINOUS BASE COURSE SUPERPAVE, N50, 2 1/2"	SQ YD	49,877	49,877																
X0325563	BITUMINOUS BASE COURSE, SUPERPAVE, N70, 8"	SO YD	4,861	4,861																
X0325564	BITUMINOUS BASE COURSE, SUPERPAVE, N90, 8"	SQ YD	49,877	49,877																
X0325565	BITUMINOUS BASE COURSE, SUPERPAVE, N90, 10 1/4"	SQ YD	9,791	9,791																

△ SFTY-3N  
\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE
S. VERTHEIN	08/01/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI ROUTE 55  
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

SUMMARY OF QUANTITIES

SCALE: 1" = 50'  
DATE: 07-21-06

DRAWN BY  
CHECKED BY



Rev. 9-5-06

FINAL