

SUMMARY OF QUANTITIES

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	588	15
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62303	(2021-922 PT2 ETC 2324.6-1P)	R-11		

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE												
				ROADWAY IDOT J000	ROADWAY CDOT J000	RETAINING WALLS 39TH-47TH Y007	MWRD CULVERT X028-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1												
Z0076600	TRAINEES	HOUR	2000	2000												
X0325502	MEDIAN BARRIER GATE SYSTEM	EACH	2	2												
X0325515	LUG SYSTEM COMPLETE 41'	EACH	1	1												
X0325514	LUG SYSTEM COMPLETE 49'	EACH	1	1												
X0325517	CONDUIT EMBEDDED IN STRUCTURE, 1 1/4" DIA., GALVANIZED STEEL	FOOT	1	1												
X0325085	TEMPORARY PAVEMENT (INTERSTATE)	SQ YD	2,863	2,341							522					
X0325505	CONDUIT ENCASED, REINFORCED CONCRETE, 1-2" DIA., CNC	FOOT	397													397
X0325506	CONDUIT ENCASED, REINFORCED CONCRETE, 2-2" DIA., CNC	FOOT	115													115
X0325510	VIDEO TAPING OF PIPE UNDERDRAINS	FOOT	9,387	9,387												
X0325526	TEMPORARY PAVEMENT (VARIABLE DEPTH)	TON	481	481												
X0325516	CLEANING PIPE UNDERDRAINS	FOOT	4,694	4,694												
X6013700	PIPE UNDERDRAIN REMOVAL, SPECIAL	FOOT	3,602	3,602												
Z0018100	DRAINAGE STRUCTURES TO BE ADJUSTED, SPECIAL	EACH	21	21												
X0325567	STABILIZED SUB-BASE 4 1/2"	SQ YD	123,252	123,252												
60404910	FRAMES AND GRATES, TYPE 20	EACH	10	10												
XX004210	DUCTILE IRON PIPE STORM SEWERS, 12"	FOOT	473	473												
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6"	SQ FT	91	91												
XX005742	DETECTABLE WARNING TILES	SQ FT	26	26												
X0325500	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, TYPE J	EACH	1													1
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	20,000	20,000												
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1												
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2												
70101000	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1												
XX005111	SHEET PILING REMOVAL	L SUM	1	1												

0 - Y080
 - SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC
 CONSULTING ENGINEERS
 Chicago, Illinois
 312.228.0100
 www.bbainc.com

Rev. 9-14-06
 Rev. 8-22-06

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)
 SUMMARY OF QUANTITIES
 SCALE: 1"=81.3'
 DATE: 06/09/06
 DRAWN BY: RGR
 CHECKED BY: DOM

S00-09
 6/9/2006