F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	588	30
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62303 * (2021-922 PT2 ETC 2324.6-1P) R-11

ROADWAY REMOVAL SCHEDULE

STATION	TO	STATION	BITUMINOUS SURFACE REMOVAL 2-1/2" SQ YD	PAVEMENT REMOVAL SQ YD	COMBINATION CURB AND GUTTER REMOVAL FOOT	CONCRETE BARRIER REMOVAL FOOT	MEDIAN REMOVAL SQ FT	PAVED SHOULDER REMOVAL SQ YD	GUARDRAIL REMOVAL FOOT	TEMPORARY CONCRETE BARRIER REMOVAL FOOT	LUG SYSTEM REMOVAL EACH	IMPACT ATTENUATOR REMOVAL EACH
3475+50.00	TO	3479+00.00	0	1,665	350	64	0	100	156	242	0	0
3479+00.00	TO	3491+00.00	0	6,952	1,200	71	0	0	0	1,122	0	1
3491+00.00	TO	3503+00.00	0	6,243	1,198	27	0	5	0	1,077	0	0
3503+00.00	TO	3515+00.00	0	7,904	1,203	0	0	0	0	1,199	0	0
3515+00.00	TO	3526+00.00	0	8,048	1,119	0	0	212	0	562	0	2
3526+00.00	TO	3529+00.00	0	1,925	615	0	0	296	0	230	0	0
3529+00.00	TO	3541+00.00	1036	10871	4426	0	5277.6	516	132	89	0	0
3541+00.00	TO	3533+00.00	325	9582	2618	49	1734.5	828	201	945	0	0
3533+00.00	TO	3565+00.00	1109	10304	2693	31	3815.3	187	157	1285	0	0
3565+00.00	TO	3577+00.00	0	8904	3694	23	1969.8	756	235	1370	0	0
3577+00.00	TO	3589+00.00	289	4907	3213	69	2043.9	985	307	1193	2	0
3589+00.00	TO	3601+00.00	0	8335	3025	27	0	686	107	1163	0	0
3601+00.00	TO	3613+00.00	0	8570	2629	41	0	36	229	1018	0	0
3613+00.00	TO	3625+00.00	0	8532	3099	29	0	84	225	1105	0	0
3625+00.00	TO	3637+00.00	0	4702	1604	0	0	160	0	1013	0	0
3637+00.00	TO	3638+05.00	0	427	0	0	0	0	0	0	0	0
		TOTALS	2,759	107,871	32,686	431	14,841	4,851	1,749	13,613	2	3

CURB AND GUTTER SCHEDULE

STATION	TO	STATION	CONCRETE GUTTER, TYPE B FOOT	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 FOOT	COMBINATION CONCRETE CURB & GUTTER, TYPE M-2.24 FOOT	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.48 (MODIFIED) FOOT	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.12 FOOT	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.24 FOOT
3475+50.00	TO	3479+00.00	0	0	0	0	0	0
3479+00.00	TO	3491+00.00	0	0	0	285	0	0
3491+00.00	TO	3503+00.00	0	0	0	127	0	928
3503+00.00	TO	3515+00.00	0	0	0	995	0	24
3515+00.00	TO	3526+00.00	0	0	0	113	0	629
3526+00.00	TO	3529+00.00	0	0	0	0	0	225
3529+00.00	TO	3541+00.00	0	887	239	533	283	1365
3541+00.00	TO	3533+00.00	372	300	0	894	0	777
3533+00.00	TO	3565+00.00	266	583	288	684	0	1192
3565+00.00	TO	3577+00.00	0	0	320	524	0	843
3577+00.00	TO	3589+00.00	0	31	339	592	0	843
3589+00.00	TO	3601+00.00	0	0	0	278	0	1016
3601+00.00	TO	3613+00.00	828	0	0	0	0	410
3613+00.00	TO	3625+00.00	1038	0	0	0	0	139
3625+00.00	TO	3637+00.00	943	0	0	0	0	75
3637+00.00	TO	3638+05.00	0	0	0	0	0	0
		TOTALS	3,445	1,801	1,186	5,025	283	8,467

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

SCH-01

REVISIONS	
NAME	DATE
REVISED SHEET	6/23/06

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)

GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)

ROADWAY SCHEDULES

SCALE: NTS DRAWN BY: RA

DATE: 06/09/06 CHECKED BY: RS

12:25:48 PM 6/23/2006

N:\BBDcad\Add\N\SHEETS\660_08CSCH02.dgn