

SCHEDULE OF STORM SEWERS

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 2, 12	SS CL A 2, 15	SS CL A 2, 18	SS WMQP 12	TRENCH BACKFILL (CU. YD.)	ROCK EXCAVATION
24-01	15-29-03	63.8	12	1.00%	63.8				13.4	
24-02	15-29-07	64.5	12	1.00%	64.5				10.7	
24-03	15-29-11	68.9	12	1.00%	68.9				8.1	
25-01	15-29-14	68.4	12	1.00%	68.4				57.9	
25-03	15-29-17	79.3	12	0.50%	79.3				87.1	
25-04	25-03	35.9	12	2.50%	35.9				11.7	
25-02	25-04	66.0	12	1.00%	66.0				12.8	
24-05	25-02	161.0	12	1.00%	161.0				41.3	
24-04	24-05	13.8	12	1.00%	13.8				1.0	
25-05	15-29-21	72.3	18	1.00%			72.3		62.9	
25-06	15-30-03	27.2	12	1.00%	27.2				21.1	
25-07	25-06	55.8	12	1.00%	55.8				15.0	
25-12	15-30-06	19.6	12	1.00%	19.6				20.9	
25-13	25-12	54.6	12	0.70%	54.6				46.4	
25-14	25-13	23.0	12	1.00%	23.0				4.8	
25-11	25-14	14.8	12	1.00%	14.8				2.0	
25-10	25-11	12.2	12	1.00%	12.2				1.3	
25-09	25-10	30.9	12	1.00%	30.9				2.8	
25-08	25-09	18.0	12	1.00%	18.0				1.8	
25-15	25-14	11.0	12	1.00%	11.0				1.1	
25-16	25-15	25.9	12	1.00%	25.9				2.3	
25-17	25-16	11.0	12	1.00%	11.0				0.7	
26-01	15-30-09	30.9	12	1.00%	30.9				33.9	
25-18	26-01	56.6	12	1.00%	56.6				22.7	
25-19	25-18	20.5	12	1.00%	20.5				3.2	
26-02	25-19	70.9	12	1.00%	70.9				6.5	
26-03	15-30-12	72.1	12	1.00%	72.1				21.7	
26-04	26-03	100.8	12	1.00%	100.8				7.7	
26-06	15-31-03	61.5	15	1.00%		61.5			21.8	
26-05	26-06	44.4	12	1.00%	44.4				5.7	
27-02	15-31-06	58.4	12	1.00%	58.4				14.6	
27-01	27-02	27.0	12	1.00%	27.0				4.1	
26-07	27-01	36.0	12	1.00%	36.0				3.5	
27-03	27-02	27.0	12	1.00%	27.0				3.1	
27-04	27-03	19.0	12	1.00%	19.0				1.5	
27-05	15-31-10	64.2	12	1.00%	64.2				21.6	
27-06	27-05	98.0	12	1.00%	98.0				18.3	
27-07	15-32-03	47.3	12	1.00%	47.3				43.4	
27-08	27-07	18.9	12	1.00%	18.9				14.2	
27-09	27-08	40.9	12	1.00%	40.9				11.4	
28-09	27-09	36.6	12	1.00%	36.6				6.4	
28-01	28-09	10.3	12	1.00%	10.3				1.3	
28-02	28-01	18.0	12	1.00%	18.0				1.7	
28-05	28-01	90.8	12	1.00%	90.8				19.4	
28-10	28-05	20.3	12	1.00%	20.3				0.7	

SCHEDULE OF STORM SEWERS

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 2, 12	SS CL A 2, 15	SS CL A 2, 18	SS WMQP 12	TRENCH BACKFILL (CU. YD.)	ROCK EXCAVATION
28-04	15-32-07	51.2	12	1.00%	51.2				5.7	
28-03	28-04	23.0	12	1.00%	23.0				1.9	
28-06	15-32-11	51.2	12	1.00%	51.2				5.5	
28-08	15-32-15	51.5	12	1.00%	51.5				5.7	
28-07	28-08	96.0	12	1.00%	96.0				9.4	
28-11	28-08	4.5	12	1.00%	4.5				0.5	
29-02	15-33-09	49.3	12	1.00%	49.3				7.0	
29-01	29-02	25.0	12	1.00%	25.0				2.5	
29-03	29-02	31.8	12	1.00%	31.8				3.1	
29-06	29-02	4.5	12	1.00%	4.5				0.2	
29-04	15-33-13	50.3	12	1.00%	50.3				1.3	
29-05	15-33-17	53.1	12	1.00%	53.1				5.5	
30-01	15-34-03	57.1	12	1.00%	57.1				6.3	
30-03	15-34-07	59.5	12	1.00%	59.5				11.0	
30-04	30-03	15.5	12	1.00%	15.5				2.1	
30-05	30-04	18.0	12	1.00%	18.0				2.0	
30-02	30-05	131.0	12	1.00%	131.0				22.8	
31-01	15-34-11	68.9	12	1.00%	68.9				17.8	10.58
30-07	31-01	81.0	12	1.00%	81.0				6.4	
30-06	30-07	19.5	12	1.00%	19.5				1.5	
31-02	15-35-03	63.2	12	0.50%	63.2				6.6	15.01
31-04	15-35-13	64.1	12	1.00%	64.1				9.6	19.26
31-03	31-04	11.0	12	1.00%	11.0				0.8	7.07
31-05	31-04	11.0	12	1.00%	11.0				0.8	7.07
31-06	15-35-15	64.7	12	1.00%	64.7				1.5	19.31
32-01	15-35-21	64.1	12	1.00%	64.1				8.1	13.39
32-02	32-01	91.2	12	1.00%	91.2				10.3	
32-03	15-36-03	64.7	12	1.00%	64.7				22.6	
32-04	32-03	91.0	12	1.00%	91.0				15.3	
33-01	32-04	95.9	12	1.00%	95.9				10.6	
33-04	15-36-08	51.8	12	0.80%	51.8				13.1	
33-03	33-04	2.4	12	1.00%	2.4				0.2	
33-02	33-03	18.2	12	0.80%	18.2				4.5	
33-05	33-02	56.0	12	1.00%	56.0				6.2	
33-06	15-36-12	51.6	12	1.00%	51.6				5.4	
33-07	33-06	49.5	12	2.50%	49.5				45.1	
34-01	15-37-01	51.5	12	1.00%	51.5				5.8	
34-02	15-37-07	51.5	12	1.00%	51.5				6.0	
34-03	15-37-13	51.8	15	1.00%		51.8			7.0	
34-04	34-03	11.5	12	1.00%	11.5				1.1	
34-05	34-04	10.5	12	1.00%	10.5				0.7	
34-06	15-37-21	50.4	12	1.00%	50.4				6.1	
34-07	15-38-01	52.7	12	1.00%	52.7				6.1	
35-01	34-07	11.0	12	1.00%	11.0				0.9	
35-02	15-38-08	57.3	12	1.00%	57.3				6.5	

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

REVISIONS	
NAME	DATE
REVISED	6/23/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)
DRAINAGE SCHEDULES
PROPOSED STORM SEWER PIPES
SCALE: 1"=N.T.S.
DATE: 06/09/06
DRAWN BY: JAM
CHECKED BY: DDM