

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	(26-150)M	ROCK ISLAND	116	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

URBAN  
80% FED  
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY 1000
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	120
81400200	HEAVY DUTY HANDHOLE	EACH	3
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN NO 18 3 PR	FOOT	846
88600100	DETECTOR LOOP, TYPE 1	FOOT	144
89502380	REMOVE EXISTING HANDHOLE	EACH	3
* X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24"	FOOT	40
X0322118	REMOVE CONCRETE FLARED END SECTIONS	EACH	2
X0324885	CONDUIT INSTALLED 1" DIA, NON-METALLIC	FOOT	21
X0324886	CONDUIT INSTALLED 1 1/4" DIA, NON-METALLIC	FOOT	419
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	404
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	1023
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	4193
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	20
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	875
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
X032519	DRAIN FOR AGGREGATE BASE COURSE	SOYD	23

\* SPECIALTY ITEMS  
+ NON-PARTICIPATING

PLOT DATE = Wed Jun 21 13:06:57 2006  
FILE NAME = I:\032519\032519.dgn  
PLOT SCALE = 50.000000 X IN.  
USER NAME = mg111j

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY

## SUMMARY OF QUANTITIES