

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789	56-BR-1	MADISON	23	3
STA.		TO STA.		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X080-2A	SFTY-3N
20200500	EARTH EXCAVATION (WIDENING)	CU YD	40	40	
20400800	FURNISHED EXCAVATION	CU YD	60	60	
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
25100105	MULCH, METHOD 1	ACRE	0.25	0.25	
28000300	TEMPORARY DITCH CHECKS	EACH	10	10	
28100109	STONE RIPRAP, CLASS A5	SQ YD	180	180	
28200200	FILTER FABRIC	SQ YD	180	180	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3	
40600300	AGGREGATE (PRIME COAT)	TON	1	1	
40600990	TEMPORARY RAMP	SQ YD	100	100	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	562	562	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	800	800	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	0.2	0.2	
50300225	CONCRETE STRUCTURES	CU YD	0.5	0.5	
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	359	359	
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	930	930	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	30	30	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	153	153	
51500100	NAME PLATES	EACH	1	1	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	110	110	
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	282	282	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	412.5	412.5	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	298	298	
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	60	60	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10	
67100100	MOBILIZATION	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X080-2A	SFTY-3N
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1214	1214	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	560	560	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	405	405	
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	280	280	
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	280	280	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1674	1674	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3	3	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	10	10	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	252	252	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4	
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SQ FT	359	359	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	2	2	
X3560160	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 12 INCH	SQ YD	104	104	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	69	69	
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	31	31	
X7200200	WIDE LOAD SIGNING	L SUM	1	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2

*SPECIALTY ITEMS